CPY 903

Advanced Assessment and Diagnosis

A Textbook in Counselling Psychology

CPY 903

Advanced Assessment and Diagnosis

A Doctoral-Level Textbook in Counselling Psychology

TRIUNE BIBLICAL UNIVERSITY GLOBAL EXTENSION, USA

First edition

New York, USA

Advanced Assessment and Diagnosis: A Doctoral-Level Textbook in Counselling Psychology. CPY 903. First edition.

© 2026 TRIUNE BIBLICAL UNIVERSITY GLOBAL EXTENSION, USA. All rights reserved.

Published by Triune Biblical University Global Extension, USA (Online University, Shirley, New York, USA). www.tbuglobalextensionusa.com

All rights reserved. No part of this publication may be reproduced, distributed, or transmitted in any form or by any means without the prior written permission of the publisher, except for brief quotations in reviews and for classroom use within the licensee institution.

This textbook is issued for academic use and is not for sale.

The text does not reproduce proprietary test items or copyrighted diagnostic criteria. Students must consult the authorised manuals of individual instruments and the current editions of diagnostic classifications. Clinical examples are fictional composites and do not describe identifiable persons.

Diagnostic criteria quoted or paraphrased in this book are drawn from the Diagnostic and Statistical Manual of Mental Disorders, Fifth Edition, Text Revision (American Psychiatric Association, 2022) and from the Clinical Descriptions and Diagnostic Requirements for ICD-11 Mental, Behavioural and Neurodevelopmental Disorders (World Health Organization, 2024). Copyright in those works remains with their respective owners.

Typeset in EB Garamond 11/15.2 pt with Source Serif 4 display type. Trim size 152 × 229 mm.

Contents

List of Figures xiii

List of Tables xiv

Abbreviations xv

Preface xix

How to Use This Book xxii

Part I: Foundations and Measurement 1

Chapter 1. Foundations of Advanced Psychological Assessment and Diagnosis 3
- Introduction 4
- 1.1 The Place of Assessment in Counselling Psychology 5
- 1.2 Assessment as a Decision Process 7
- 1.3 From Referral Question to Assessment Plan 8
- 1.4 Diagnosis, Formulation and Treatment Planning 10
- 1.5 Dimensional and Categorical Thinking 11
- 1.6 Sources of Assessment Evidence 12
- 1.7 Base Rates and Clinical Probability 14
- 1.8 Functional Impairment and Context 15
- 1.9 Evidence-Based Assessment 16
- 1.10 Interprofessional Assessment 18
- 1.11 Limits of Assessment Conclusions 19
- 1.12 Integrating Findings into Responsible Decisions 20
- Chapter Summary 22
- Review Questions 23
- Discussion Questions 23
- Further Reading 24

Chapter 2. Clinical Interviewing, Mental Status Examination and Diagnostic Reasoning 25
- Introduction 25
- 2.1 Designing a Purposeful Clinical Interview 27
- 2.2 Opening the Interview and Establishing Rapport 28
- 2.3 History of Presenting Concerns 30
- 2.4 Developmental, Family and Social History 31
- 2.5 Mental Status Examination 33
- 2.6 Symptom Chronology and Course 35
- 2.7 Collateral Information and Records 37

2.8 Differential Diagnosis 38
2.9 Medical and Substance-Related Explanations 39
2.10 Interviewing Under Conditions of Distress 40
2.11 Structured and Semi-Structured Interviews 41
2.12 Documenting Diagnostic Reasoning 42
Chapter Summary 45
Review Questions 45
Discussion Questions 45
Further Reading 46

Chapter 3. Psychometrics: Reliability, Validity, Norms and Measurement Error 49
Introduction 50
3.1 Measurement Models and Observed Scores 51
3.2 Reliability and Score Consistency 52
3.3 Standard Error and Confidence Intervals 54
3.4 Validity as Evidence for Interpretation 55
3.5 Content and Response Process Evidence 56
3.6 Relations with Other Variables 57
3.7 Internal Structure 58
3.8 Norms, Percentiles and Standard Scores 60
3.9 Sensitivity, Specificity and Predictive Values 61
3.10 Cut Scores and Classification Accuracy 63
3.11 Fairness and Measurement Invariance 64
3.12 Evaluating Technical Manuals 65
Chapter Summary 67
Review Questions 67
Discussion Questions 68
Further Reading 68

Chapter 4. Test Selection, Administration, Scoring and Interpretation 71
Introduction 71
4.1 Matching Measures to Referral Questions 73
4.2 Evaluating Test Quality and Suitability 74
4.3 Qualifications and Scope of Practice 75
4.4 Preparing the Assessment Environment 76
4.5 Standardised Administration 77
4.6 Accommodations and Accessibility 78
4.7 Scoring and Quality Control 79
4.8 Response Styles and Validity Indicators 81
4.9 Interpreting Profiles and Score Patterns 82
4.10 Combining Tests with Other Evidence 83
4.11 Technology-Assisted Assessment 84

4.12 Avoiding Common Interpretation Errors ... 85
Chapter Summary ... 87
Review Questions ... 87
Discussion Questions ... 88
Further Reading ... 88

Part II: Assessing Dispositions and Abilities ... 89

Chapter 5. Personality Assessment and Interpersonal Functioning ... 91
Introduction ... 91
5.1 Purposes of Personality Assessment ... 92
5.2 Trait and Dimensional Models ... 94
5.3 Broad-Band Personality Inventories ... 95
5.4 Narrow-Band Measures ... 97
5.5 Interpersonal and Attachment Assessment ... 98
5.6 Response Style and Impression Management ... 99
5.7 Performance-Based and Projective Approaches ... 100
5.8 Personality Functioning and Severity ... 101
5.9 Personality Assessment in Case Formulation ... 102
5.10 Feedback from Personality Assessment ... 103
5.11 Cultural Interpretation of Personality Scores ... 104
5.12 Integrating Personality Findings ... 105
Chapter Summary ... 107
Review Questions ... 108
Discussion Questions ... 108
Further Reading ... 109

Chapter 6. Cognitive, Intellectual and Neuropsychological Assessment ... 111
Introduction ... 112
6.1 Questions Addressed by Cognitive Assessment ... 113
6.2 Theories of Intellectual Functioning ... 114
6.3 Interpreting Cognitive Profiles ... 115
6.4 Attention and Processing Speed ... 116
6.5 Learning and Memory ... 117
6.6 Executive Functions ... 118
6.7 Language and Visuospatial Skills ... 119
6.8 Neuropsychological Screening ... 120
6.9 Performance Validity ... 121
6.10 Medical and Neurological Context ... 122
6.11 Functional Implications of Cognitive Findings ... 123
6.12 Communicating Cognitive Results ... 124
Chapter Summary ... 126
Review Questions ... 127

Discussion Questions ... 127
Further Reading ... 127

Chapter 7. Achievement, Aptitude, Career and Functional Assessment ... 129
Introduction ... 129
7.1 Academic Achievement Assessment ... 131
7.2 Reading, Writing and Mathematics ... 132
7.3 Aptitude and Learning Potential ... 133
7.4 Career Interests and Values ... 135
7.5 Work Personality and Work Adjustment ... 136
7.6 Adaptive Behaviour ... 137
7.7 Functional Capacity and Daily Activities ... 138
7.8 Disability and Accommodation Decisions ... 139
7.9 Career Assessment with Adults in Transition ... 140
7.10 Integrating Educational and Career Data ... 141
7.11 Ethical Use of Occupational Tests ... 141
7.12 Writing Functional Recommendations ... 142
Chapter Summary ... 145
Review Questions ... 145
Discussion Questions ... 145
Further Reading ... 146

Part III: Assessing Clinical Presentations ... 147

Chapter 8. Assessment of Mood, Anxiety, Obsessive-Compulsive, Trauma and Stress-Related Problems ... 149
Introduction ... 149
8.1 Assessing Depressive Presentations ... 150
8.2 Assessing Anxiety Presentations ... 152
8.3 Panic and Agoraphobic Symptoms ... 153
8.4 Obsessions and Compulsions ... 154
8.5 Trauma Exposure and Post-Traumatic Symptoms ... 155
8.6 Stress and Adjustment Problems ... 156
8.7 Somatic Overlap and Medical Explanations ... 157
8.8 Severity Measures and Symptom Monitoring ... 157
8.9 Functional Analysis of Avoidance ... 159
8.10 Differential Diagnosis Across Internalising Problems ... 160
8.11 Comorbidity and Diagnostic Hierarchy ... 162
8.12 Integrated Formulation and Feedback ... 163
Chapter Summary ... 165
Review Questions ... 165
Discussion Questions ... 165
Further Reading ... 166

Chapter 9. Assessment of Bipolar, Psychotic and Other Severe Mental Disorders 167
Introduction 168
9.1 Recognising Manic and Hypomanic Presentations 169
9.2 Assessing Psychotic Experiences 170
9.3 Thought Form and Thought Content 171
9.4 Negative Symptoms and Functional Decline 172
9.5 Mood Disorders with Psychotic Features 173
9.6 Substance-Induced and Medical Presentations 174
9.7 Developmental and Cultural Explanations 175
9.8 Collateral History and Longitudinal Evidence 176
9.9 Insight, Judgement and Decision-Making Capacity 176
9.10 Risk and Immediate Safety Needs 177
9.11 Diagnostic Uncertainty and Provisional Conclusions 178
9.12 Communicating Findings in Severe Presentations 179
Chapter Summary 181
Review Questions 182
Discussion Questions 182
Further Reading 182

Chapter 10. Assessment of Personality Disorders and Enduring Relational Patterns 185
Introduction 186
10.1 Understanding Enduring Personality Patterns 187
10.2 Trait-Based and Categorical Approaches 188
10.3 Identity and Self-Functioning 189
10.4 Interpersonal Functioning 190
10.5 Longitudinal and Developmental Evidence 191
10.6 Differentiating State from Trait 192
10.7 Personality and Trauma 193
10.8 Personality and Neurodevelopmental Conditions 194
10.9 Personality and Substance Use 195
10.10 Structured Personality Interviews 195
10.11 Feedback without Stigma 196
10.12 Formulating Enduring Relational Patterns 197
Chapter Summary 199
Review Questions 200
Discussion Questions 200
Further Reading 200

Chapter 11. Assessment of Substance Use, Behavioural Addictions and Risk Behaviour 203
Introduction 204

11.1 Patterns of Substance Use ... 205
11.2 Screening and Case Finding ... 206
11.3 Intoxication and Withdrawal ... 207
11.4 Severity and Functional Consequences ... 208
11.5 Polysubstance Use ... 209
11.6 Substance-Induced Mental Symptoms ... 209
11.7 Behavioural Addictions ... 210
11.8 Motivation and Readiness for Change ... 211
11.9 Medical and Social Risk ... 212
11.10 Collateral Data and Biological Measures ... 213
11.11 Assessment for Harm Reduction Planning ... 214
11.12 Integrated Diagnostic Formulation ... 215
Chapter Summary ... 217
Review Questions ... 217
Discussion Questions ... 218
Further Reading ... 218

Part IV: Development, Culture and Relational Systems ... 221

Chapter 12. Child and Adolescent Assessment ... 223
Introduction ... 223
12.1 Developmentally Informed Assessment ... 224
12.2 Multi-Informant Assessment ... 225
12.3 Parent and Caregiver Interviews ... 226
12.4 Interviewing Children and Adolescents ... 227
12.5 Behavioural Observation ... 229
12.6 School Records and Teacher Reports ... 230
12.7 Neurodevelopmental Assessment ... 230
12.8 Emotional and Behavioural Problems ... 232
12.9 Trauma and Safeguarding in Youth Assessment ... 233
12.10 Family and Cultural Context ... 234
12.11 Consent, Assent and Confidentiality ... 235
12.12 Integrated Youth Formulation and Feedback ... 235
Chapter Summary ... 238
Review Questions ... 238
Discussion Questions ... 239
Further Reading ... 239

Chapter 13. Couples, Family and Systemic Assessment ... 241
Introduction ... 241
13.1 The Unit of Assessment in Relational Work ... 242
13.2 Relationship History and Presenting Concerns ... 243
13.3 Dyadic Interaction and Communication ... 244

13.4 Conflict Patterns and Repair ... 245
13.5 Attachment and Relationship Security ... 246
13.6 Family Structure and Boundaries ... 247
13.7 Parenting and Co-Parenting ... 248
13.8 Violence, Coercion and Safety Screening ... 249
13.9 Individual Symptoms in Relational Context ... 250
13.10 Cultural and Socioeconomic Context ... 251
13.11 Measures of Relationship Functioning ... 251
13.12 Systemic Formulation and Feedback ... 252
Chapter Summary ... 254
Review Questions ... 255
Discussion Questions ... 255
Further Reading ... 255

Chapter 14. Multicultural, Language, Disability and Fairness Considerations in Assessment ... 257
Introduction ... 258
14.1 Culture and the Meaning of Symptoms ... 259
14.2 Language Proficiency and Interpreter Use ... 260
14.3 Test Translation and Adaptation ... 261
14.4 Bias and Fairness ... 262
14.5 Normative Samples and Representativeness ... 263
14.6 Disability and Reasonable Accommodations ... 264
14.7 Migration, Acculturation and Context ... 265
14.8 Socioeconomic Conditions and Opportunity ... 265
14.9 Community Values and Cultural Context ... 266
14.10 Gender and Sexuality in Assessment ... 267
14.11 Intersection of Multiple Social Positions ... 268
14.12 Culturally Responsible Formulation ... 269
Chapter Summary ... 271
Review Questions ... 271
Discussion Questions ... 272
Further Reading ... 272

Part V: Risk, Integration and Communication ... 273

Chapter 15. Risk Assessment: Suicide, Self-Harm, Violence, Abuse and Safeguarding ... 275
Introduction ... 275
15.1 Principles of Risk Assessment ... 276
15.2 Suicidal Thoughts and Behaviour ... 277
15.3 Non-Suicidal Self-Injury ... 279
15.4 Violence and Aggression Risk ... 280

15.5 Domestic Abuse and Coercive Control ... 280
15.6 Child and Vulnerable Adult Safeguarding ... 281
15.7 Static and Dynamic Risk Factors ... 282
15.8 Protective Factors and Reasons for Living ... 283
15.9 Structured Professional Judgement ... 284
15.10 Safety Planning and Immediate Intervention ... 285
15.11 Documentation and Communication of Risk ... 285
15.12 Reassessment and Continuity of Care ... 286
Chapter Summary ... 288
Review Questions ... 288
Discussion Questions ... 289
Further Reading ... 289

Chapter 16. Integrated Case Formulation, Differential Diagnosis, Report Writing and Feedback ... 291
Introduction ... 292
16.1 Integrating Multimethod Evidence ... 293
16.2 Weighing Conflicting Findings ... 294
16.3 Differential Diagnosis as Hypothesis Testing ... 294
16.4 Formulation beyond Diagnostic Labels ... 295
16.5 Linking Assessment to Treatment Planning ... 296
16.6 Writing Clear Psychological Reports ... 297
16.7 Communicating Uncertainty ... 298
16.8 Feedback as a Clinical Intervention ... 299
16.9 Ethical and Legal Responsibilities ... 300
16.10 Digital Assessment and Artificial Intelligence ... 301
16.11 Quality Assurance and Peer Consultation ... 302
16.12 Advanced Case Conference and Final Synthesis ... 303
Chapter Summary ... 305
Review Questions ... 306
Discussion Questions ... 306
Further Reading ... 306

References ... 309

Glossary ... 315

Appendix A: Assessment Planning and Quality Checklist ... 321
A.1 Before the assessment ... 321
A.2 During the assessment ... 322
A.3 Scoring and analysis ... 322
A.4 Before finalising the report ... 323
A.5 After the assessment ... 323

Appendix B: Structure for an Integrated Psychological Report 325
B.1 Identifying information 325
B.2 Reason for referral 325
B.3 Sources of information 325
B.4 Relevant background 326
B.5 Behavioural observations and mental status 326
B.6 Assessment methods 326
B.7 Results by clinically meaningful domain 326
B.8 Integrated interpretation and differential considerations 326
B.9 Diagnostic conclusions 327
B.10 Formulation 327
B.11 Strengths and protective factors 327
B.12 Recommendations 327
B.13 Limitations and conditions affecting interpretation 327
B.14 Summary for the reader 327

Appendix C: Case Formulation Template 329
C.1 The presenting pattern 329
C.2 Predisposing factors 329
C.3 Precipitating factors 329
C.4 Maintaining factors 330
C.5 Protective factors 330
C.6 The formulation as narrative 330
C.7 Predictions and tests 330
C.8 Intervention implications 330

About the Author 331

Index 333

List of Figures

Figure 1.1. The movement from referral question to responsible decision. Each step constrains the next; the final decision inherits the uncertainties recorded at every earlier step. . . . 4
Figure 2.1. The structure of a diagnostic interview. Each element supplies evidence for a different claim, and the mental status examination is interpreted against, not instead of, the history. . . . 26
Figure 3.1. The psychometric chain. Each link is a separate empirical claim, and no link can be inferred from the strength of the others. . . . 50
Figure 3.2. Positive and negative predictive values for an instrument with sensitivity .90 and specificity .90, plotted against prevalence. The values are computed from Bayes' theorem; the instrument is held constant while the setting varies. . . . 62
Figure 4.1. The test-use cycle. Selection, administration and scoring each protect or threaten the validity of the interpretation that follows. . . . 72
Figure 5.1. Personality assessment integrates model, method and context. No single instrument supplies the construct; the assessor must construct it. . . . 92
Figure 6.1. Cognitive assessment as a sequence of claims, each requiring its own evidence. Capacity, context and consequence are separate questions. . . . 112
Figure 7.1. Functional assessment links capacity, demand and support. The decision concerns the fit between them, not the capacity alone. . . . 130
Figure 8.1. Assessment across the internalising spectrum. Overlapping presentations require explicit discrimination rather than reliance on the most salient symptom. . . . 150
Figure 9.1. Assessment of severe presentations. Each domain supplies evidence that may support or undermine the others, and no single domain is decisive. . . . 168
Figure 10.1. Assessment of personality disorder. Severity, traits, development and context must converge before a diagnosis is warranted. . . . 186
Figure 11.1. Assessment of substance use. Description, consequence and context must be established before diagnosis or planning. . . . 204
Figure 12.1. Child assessment. Development, multiple informants and multiple settings must be integrated before conclusions are drawn. . . . 224
Figure 13.1. Relational assessment. Safety screening precedes all other assessment; formulation concerns patterns between people, not deficits within one. . . . 242
Figure 14.1. Culturally responsible assessment. Culture and language condition every stage, from construct definition to feedback. . . . 258
Figure 15.1. Risk assessment as a process. Information, formulation, plan and review matter more than a summary judgement. . . . 276
Figure 16.1. Integration and communication. The evidence is weighed, formulated, written and discussed; each stage is an opportunity to lose or gain accuracy. . . . 292

List of Tables

Table 1.1. Planning decisions, their rationale, and the failure they prevent 9
Table 1.2. Sources of assessment evidence: contribution and characteristic limitation 13
Table 2.1. The mental status examination: domains and observations 34
Table 3.1. Forms of reliability and the error each addresses 52
Table 3.2. Common score scales and their interpretation 60
Table 4.1. Criteria for evaluating a candidate instrument 74
Table 5.1. Representative personality instruments and their principal uses 96
Table 7.1. Academic domains, component skills and assessment implications 133
Table 7.2. Weak and strong functional recommendations 143
Table 8.1. Discriminating features among commonly confused internalising presentations 161

Abbreviations

Acronyms and abbreviations used in this book

Abbreviation	Expansion
AERA	American Educational Research Association
APA	American Psychological Association
ADHD	Attention-deficit/hyperactivity disorder
ASD	Autism spectrum disorder
AUDIT	Alcohol Use Disorders Identification Test
BDD	Body dysmorphic disorder
CFI	Cultural Formulation Interview
CI	Confidence interval
CBT	Cognitive behavioural therapy
DSM-5-TR	Diagnostic and Statistical Manual of Mental Disorders, Fifth Edition, Text Revision
GAD-7	Generalised Anxiety Disorder-7 item scale
HCR-20	Historical-Clinical-Risk Management-20
ICD-11	International Classification of Diseases, Eleventh Revision
ICF	International Classification of Functioning, Disability and Health
IQ	Intelligence quotient
IRT	Item response theory
ITC	International Test Commission
MSE	Mental status examination
MMPI	Minnesota Multiphasic Personality Inventory
NPV	Negative predictive value
OCD	Obsessive-compulsive disorder
PAI	Personality Assessment Inventory
PHQ-9	Patient Health Questionnaire-9 item scale
PID-5	Personality Inventory for DSM-5
PPV	Positive predictive value

Abbreviation	Expansion
PTSD	Post-traumatic stress disorder
RIASEC	Realistic, Investigative, Artistic, Social, Enterprising, Conventional (Holland's model of vocational interests)
ROC	Receiver operating characteristic
SCID-5	Structured Clinical Interview for DSM-5 Disorders
SCID-5-AMPD	Structured Clinical Interview for the DSM-5 Alternative Model for Personality Disorders
SCID-5-PD	Structured Clinical Interview for DSM-5 Personality Disorders
SD	Standard deviation
SEM	Standard error of measurement
SPD	Standard error of the difference
START	Short-Term Assessment of Risk and Treatability
WHO	World Health Organization

Typographic conventions

Convention	Use in this book
Italic	Titles of works; emphasis; names of statistical tests
Bold	Headings and, within tables, the labels of rows requiring emphasis
En dash (–)	Ranges of numbers and pages; interruption of sense
Em dash (—)	Parenthetical interruption, used sparingly
[...]	Editorial notes; square brackets mark information that the publisher or author must supply
%	Used only in numeric expressions (for example, 16 per cent is written out)

Notes on usage

Titles of diagnostic classifications are given in full at first mention in each chapter, with the abbreviation thereafter. The names of instruments are given in full at first mention, with the abbreviation thereafter; instruments are not abbreviated when the abbreviation would be unfamiliar to a general reader.

British spelling is used throughout, except in the titles of published instruments, organisations and works.

Preface

This book is written for doctoral students and practising psychologists who are learning to conduct psychological assessment at a level that can withstand scrutiny — by a supervisor, a multidisciplinary team, a tribunal, or a client who reads the report and asks, reasonably, how the conclusion was reached.

Its premise is that advanced assessment is distinguished less by the instruments used than by the quality of the reasoning that surrounds them. Any competent practitioner can administer a battery. What distinguishes advanced practice is the capacity to formulate a question that matters, to select methods proportionate to that question, to weigh evidence of uneven quality, to hold several explanations in view at once, and to communicate a conclusion that is both decisive enough to guide action and honest about its margins.

Three commitments organise the book.

Assessment exists to answer a question. Instruments, interviews and records are means; the decision the assessment was commissioned to inform is the end that gives them sense. Each chapter therefore begins from the question and works towards the method, rather than the reverse.

Every conclusion is probabilistic. Scores carry error, informants disagree, and diagnostic categories are useful simplifications of heterogeneous presentations. The book treats measurement error, base rates and diagnostic uncertainty not as technical footnotes but as the substance of responsible interpretation.

Assessment is an ethical act. Its conclusions can open or close access to treatment, education, employment, custody and liberty. The practitioner

therefore owes the client a transparent account of what was measured, what was inferred and what remains uncertain.

Organisation

The sixteen chapters are grouped into five parts. Part I establishes the foundations: the purposes of assessment, the design of interviews, and the psychometric basis of score interpretation. Part II addresses the assessment of dispositions and abilities — personality, cognitive function, and achievement, aptitude and career. Part III takes up the major clinical presentations: mood, anxiety, obsessive-compulsive, trauma-related, bipolar, psychotic, substance-related and enduring personality difficulties. Part IV considers children and adolescents, couples and families, and the cultural, linguistic and disability considerations that condition every interpretation. Part V addresses risk and safeguarding, and closes with the integration of evidence into formulation, reports and feedback.

Each chapter follows a consistent structure: learning objectives; key terms; an introduction that places the topic in the broader argument of the book; numbered sections that move from principle to application; an Advanced Case Conference that demonstrates the reasoning on a composite case; a summary; review and discussion questions; and a reading list. The case conferences are fictional composites constructed to illustrate assessment reasoning, not descriptions of identifiable clients.

A note on scope and limits

The book does not reproduce proprietary test items, scoring materials or copyrighted diagnostic criteria. Students must consult the authorised manuals of individual instruments and the current editions of the diagnostic classifications before administering or interpreting any measure. A textbook can teach principles; it cannot replace test-specific training, supervised practice or professional competence.

Diagnostic systems are revised. This edition refers to the *Diagnostic and Statistical Manual of Mental Disorders*, fifth edition, text revision (DSM-5-TR), together with approved DSM-5-TR updates available at the

time of writing; to the World Health Organization's *Clinical Descriptions and Diagnostic Requirements for ICD-11 Mental, Behavioural and Neurodevelopmental Disorders* (2024); and to the 2014 *Standards for Educational and Psychological Testing*. Practitioners remain responsible for checking later revisions and jurisdiction-specific requirements.

British spelling has been used throughout, except in the titles of published instruments, organisations and works, which retain their original spelling.

New York, USA

How to Use This Book

The book is designed for a doctoral course that combines seminars, supervised practice and independent reading. It can be read sequentially, but it is also organised so that it can be used flexibly.

Sequential reading

Chapters 1 to 4 establish the reasoning and measurement framework on which everything else depends. Readers who are new to assessment should read these chapters first, in order. Chapters 5 to 16 can then be read according to the curriculum, although each assumes familiarity with the concepts introduced in Part I.

Reading alongside a placement

Each chapter's Advanced Case Conference is a worked example of the reasoning the chapter describes. Readers on placement are encouraged to read the case conference alongside their own caseload, and to write their own case conference in the same format for supervision. The format — referral, evidence, reasoning, decision, teaching point — is deliberately the same as the structure of a well-written report.

Diagnostic systems

Two classification systems are referred to throughout: DSM-5-TR and ICD-11. They are not interchangeable, and the differences matter for some presentations, notably personality disorder, post-traumatic stress disorder and substance use. Readers should consult the primary texts for criteria,

and should note which system a given service uses, since the criteria applied affect eligibility for treatment and for funding.

Instruments

The book discusses instrument families and the principles by which they are evaluated, but it does not reproduce items, scoring rules or norm tables. When learning a specific instrument, readers should work from the manual, under supervision, with attention to the reliability, validity, norm group and stated limits of interpretation discussed in Chapter 3.

The learning features

Each chapter contains:

- **Learning objectives**, which state what the reader should be able to do after the chapter.
- **Key terms**, listed at the start and defined in the glossary.
- **Numbered sections**, which move from principle to application.
- **Tables**, which summarise distinctions that are easily confused.
- **Figures**, which present the chapter's conceptual structure.
- **An Advanced Case Conference**, which demonstrates the reasoning on a composite case.
- **A chapter summary**, which restates the argument.
- **Review questions**, which test comprehension and application.
- **Discussion questions**, which are designed for seminar use and have no single correct answer.
- **Further reading**, which identifies the sources on which the chapter draws.

A note for instructors

The discussion questions are written to expose disagreement rather than to elicit a correct answer, and they work best when students are asked to defend a position and then to argue the opposite. The case conferences can be used as the basis for role-play, for written formulations, or for peer review exercises in which students critique each other's reasoning. Appendix A provides a planning and quality checklist that students can use as a self-assessment tool before submitting assessed work.

PART I

Foundations and Measurement

The purposes of assessment, the logic of clinical inference, interviewing, and the psychometric basis of score interpretation.

Chapter 1 · Chapter 2 · Chapter 3 · Chapter 4

CHAPTER 1

Foundations of Advanced Psychological Assessment and Diagnosis

Learning Objectives

After working through this chapter, the reader should be able to:

- explain the purposes that psychological assessment serves in counselling psychology, and distinguish assessment from testing;
- describe assessment as a sequence of decisions in which each step constrains the next;
- translate a referral question into an assessment plan with proportionate methods and defensible limits;
- reason with base rates, competing hypotheses and known sources of error when interpreting findings;
- distinguish diagnosis, case formulation and treatment planning as related but non-identical products;
- identify the technical, cultural and ethical limits that qualify any assessment conclusion.

Key terms: assessment versus testing · referral question · competing hypotheses · case formulation · differential diagnosis · base rate · functional impairment · evidence-based assessment · multimethod assessment · decision threshold · interpretive limit

Introduction

Advanced assessment is not a longer version of routine testing. What changes at doctoral level is the *quality of the inference* the practitioner is willing to defend. A student who can administer and score a battery may still be unable to say what the scores mean for this person, at this moment, in this setting, and with what margin of error. The purpose of this book is to develop that second competence: the disciplined movement from data to a conclusion that another qualified professional could inspect, challenge and, where necessary, overturn.

Three commitments organise the chapters that follow. The first is that assessment exists to answer a question that matters. Instruments, interviews and records are means; the referral question is the end that gives them sense. The second is that every conclusion is probabilistic. Scores carry error, informants disagree, and diagnostic categories are useful simplifications of heterogeneous presentations. The third is that assessment is an ethical act. Its conclusions can open or close access to treatment, education, employment, custody and liberty, and the assessor therefore owes the client a transparent account of what was measured, what was inferred and what remains uncertain.




Figure 1.1. The movement from referral question to responsible decision. Each step constrains the next; the final decision inherits the uncertainties recorded at every earlier step.

Figure 1.1 presents the logic of the book in compressed form. The remaining sections of this chapter elaborate each element of that sequence, and the chapters that follow apply it to interviewing, measurement, specific instrument families and specific clinical presentations. Throughout, the emphasis falls on reasons rather than labels: a diagnosis that cannot be justified in writing is not yet a diagnosis, only an impression.

1.1 The Place of Assessment in Counselling Psychology

Counselling psychology has historically defined itself by attention to the person in context, to developmental and relational history, and to strengths as well as deficits. Assessment in this tradition is therefore not a diagnostic ritual performed before therapy begins, but a continuous and collaborative activity that informs formulation, monitors change and structures the ending of treatment. Its distinctive contribution is the integration of standardised measurement with an account of meaning: what the difficulty is, what it means to this person, and what function it serves in their life.

Assessment and testing are not synonyms

Testing is a procedure: a standardised stimulus set, a specified response format, a scoring rule and a norm or criterion against which performance is compared. Assessment is the broader process of which testing may or may not form a part. It begins with a question, selects methods proportionate to that question, integrates data from multiple sources, and ends with a communication that is useful to somebody. Meyer and colleagues (2001) demonstrated that psychological tests generally achieve respectable validity for the constructs they measure, but the same evidence shows that validity attaches to *interpretations* rather than to instruments. A test does not carry its meaning with it; the assessor supplies the meaning and is accountable for it.

This distinction has practical consequences. It explains why a technically well-administered battery can still yield a poor assessment, and why an assessment conducted without standardised instruments can, in some cir-

cumstances, be defensible. It also explains why the competence required for advanced practice cannot be reduced to test administration: the difficult skills are question formulation, method selection, integration and communication.

The institutional context of assessment

Assessment is commissioned by someone. Referrals arrive from general practitioners, psychiatrists, schools, courts, employers, insurers, adoption agencies and, increasingly, from clients themselves. Each source brings an implicit theory of what the problem is and what a useful answer would look like. A paediatric referral asking whether a child "has ADHD" has already framed the difficulty as an individual disorder rather than, say, a classroom-fit problem; a court asking about parenting capacity has framed it as a prediction about future behaviour. Part of advanced competence is recognising these frames early, negotiating them where they are inadequate, and recording the negotiation.

Counselling psychologists also work in settings where the assessment itself is an intervention. A careful history can be the first occasion on which a client's experience has been taken seriously and organised coherently; feedback can reframe a self-condemnatory narrative. Finn and Tonsager (1997) argued that assessment information can produce measurable therapeutic benefit when it is shared collaboratively, and this finding has been absorbed into what is now called therapeutic or collaborative assessment. The implication is not that assessment must always be therapeutic, but that its interpersonal dimension is never neutral.

Assessment as a professional identity

For the doctoral practitioner, assessment competence is a marker of professional standing. It signals the capacity to hold technical and relational knowledge together: to know the standard error of a difference, and also to know that a client who arrives twenty minutes late may be communicating something about the assessment. The chapters of this book are organised to develop both capacities simultaneously, because in practice they cannot be separated.

1.2 Assessment as a Decision Process

An assessment is best understood as a decision tree rather than a data-collection exercise. The first decision concerns scope: which questions are answerable within the resources available, and which must be referred elsewhere. The second concerns methods. The third concerns thresholds: how much evidence is required before a conclusion is offered. The fourth concerns communication: what the client, the referrer and any other legitimate audience need to know. Each decision narrows the space of possible conclusions, and each should be revisable in the light of new evidence.

Sequential and iterative structure

Although assessment plans are written in sequence, real assessments loop. A discrepancy between interview and questionnaire may send the assessor back to the history; a collateral report may reopen a question that had appeared settled. Explicitly acknowledging this iterative structure protects against the common error of treating the initial plan as a contract. In practice, three to five significant revisions of a hypothesis set are normal in a complex adult assessment, and records that show no revision at all usually indicate that no genuine hypothesis was ever tested.

Efficiency is an ethical requirement

Because assessment consumes the client's time, money and emotional resources, proportionate selection of methods is an ethical as well as an economic matter. Every additional instrument must be justified by the probability that it will change a decision. This principle, sometimes called incremental validity, is the strongest available argument against the indiscriminate batteries that characterise inexperienced practice. Where a battery is retained for reasons of convention or institutional requirement, the assessor should say so rather than implying that each instrument earned its place.

Documenting decisions

The decision record is the assessor's protection and the client's guarantee. A workable record states the referral question in the referrer's own terms,

the questions the assessor intended to answer, the methods chosen and the reasons for them, the hypotheses under consideration, the evidence that would discriminate between them, and the point at which the evidence was judged sufficient. This record need not be long, but it must be specific enough that a colleague could reconstruct the reasoning and identify precisely where they would have decided differently.

1.3 From Referral Question to Assessment Plan

Referral questions vary in precision from the unusable ("please assess") to the over-specified ("please confirm PTSD"). The assessor's task is to convert whatever arrives into one or more answerable questions, each with a stated decision attached. "Is this person depressed?" is not answerable in the abstract; "Is the current presentation better explained by a depressive episode than by hypothyroidism, grief or burnout, and would the answer change the next treatment step?" is.

Qualities of a well-formed assessment question

A well-formed question specifies the population or person, the constructs at issue, the comparison or decision that the assessment must inform, and the standard of evidence the decision requires. It also specifies a time frame: whether the question concerns current state, recent episode or lifelong pattern determines whether state measures, retrospective interviewing or informant history will carry most weight. Where the referrer cannot supply these elements, the assessor supplies provisional ones and records them as assumptions.

Proportionality

The plan should be proportionate in three senses: in cost and burden relative to the stakes; in intrusiveness relative to the question; and in precision relative to the decision threshold. A screening question about alcohol use in a university counselling service may be answered by a validated self-report questionnaire; a question about fitness to stand trial requires a different order of evidence, different qualifications and different reporting conven-

tions. Proportionate planning also means anticipating what will *not* be done and stating why.

Planning for what could go wrong

Competent plans include contingencies. If the client does not attend, if an interpreter is needed, if records are unavailable, if the client's reading level prevents a self-report measure, if risk emerges mid-assessment — each contingency should have a planned response. Table 1.1 sets out the planning decisions that most often determine whether an assessment succeeds, together with the failure mode that each decision prevents.

Table 1.1. Planning decisions, their rationale, and the failure they prevent

Planning decision	Why it matters	Failure prevented
Define the decision the assessment must inform	**Methods are selected for their bearing on a decision, not for their prestige**	**Over-testing; reports that answer no question**
Specify constructs before selecting instruments	**Construct clarity prevents measuring convenient proxies**	**Score-led assessment in which the battery defines the problem**
State the required standard of evidence	**High-stakes decisions need converging, independent evidence**	**Conclusions that outrun the data**
Plan the comparison or alternative explanations	**Differential reasoning requires rival hypotheses to be explicit**	**Confirmation bias; premature closure**
Plan for language, literacy and sensory access	**Validity depends on comprehension of the task**	**Misinterpreted scores presented as ability**
Set the communication plan at the outset	**Feedback shapes whether findings are used**	**Reports that are filed but never acted upon**
Record what will not be assessed	Scope limits are part of the conclusion	Implied claims beyond competence or remit

1.4 Diagnosis, Formulation and Treatment Planning

Three products emerge from clinical assessment, and confusing them is one of the most common sources of poor practice. A *diagnosis* is a classification decision: does this presentation meet the criteria for a recognised disorder, and which one? A *formulation* is an explanatory account: why this person, at this time, in this context, has developed and maintained these difficulties? A *treatment plan* is a set of actions derived from both. Diagnostic classification is retrospective, rule-governed and comparatively reliable; formulation is prospective, theory-laden and comparatively personal.

What diagnosis does and does not do

Diagnosis does several things well. It supports communication between professionals, links presentation to an evidence base, underwrites access to services and reimbursement, and imposes a discipline of explicit criteria that reduces idiosyncratic labelling. It does not explain aetiology, predict individual response to treatment reliably, or capture the person's own understanding. Nor is it stable across all presentations: mild and mixed presentations frequently fail to meet full criteria while still requiring treatment, which is why residual and unspecified categories exist and why their use should be documented rather than apologised for.

Formulation as the bridge

Formulation uses assessment evidence to construct a testable account of onset, maintenance and change. A useful formulation specifies predisposing factors, precipitants, maintaining processes, protective resources and the practical barriers that limit recovery. It should be expressed in language the client can contest, and it should predict something: if the formulation is right, then a specified intervention should produce a specified change. Where a formulation makes no predictions, it is usually a description rather than an explanation.

From formulation to plan

Treatment planning translates formulation into sequenced action, and the translation is where assessment earns its practical value. A plan that names a therapy but not the target mechanism is a plan that cannot be evaluated. Good plans specify what will be addressed first, why that target was prioritised, what would count as progress, and what would prompt a return to assessment. They also acknowledge constraints: waiting lists, cost, family obligations and the client's own preferences legitimately shape what is feasible, and a plan that ignores them is a document about an imaginary client.

1.5 Dimensional and Categorical Thinking

Psychopathology can be described categorically, as the presence or absence of a disorder, or dimensionally, as a position on one or more continuous distributions. The two descriptions answer different questions and are not in competition. Categorical description is indispensable for communication, service eligibility and legal decision-making; dimensional description preserves information about severity and subthreshold variation that categories discard.

Evidence bearing on the distinction

Structural research on the classification of mental disorders has consistently found that comorbidity is the rule rather than the exception, that symptom distributions in the population are continuous rather than bimodal, and that the boundaries between neighbouring categories are porous. The current editions of both major classifications have responded unevenly to this evidence. The *Diagnostic and Statistical Manual of Mental Disorders*, fifth edition, text revision (DSM-5-TR; American Psychiatric Association, 2022) retains a predominantly categorical architecture while adding dimensional severity ratings, cross-cutting symptom measures and a hybrid model for personality disorders in its emerging-measures section. The eleventh revision of the *International Classification of Diseases* (ICD-11) characterises personality disorder by severity of disturbance with optional trait qualifi-

ers, a substantially dimensional departure (World Health Organization, 2024).

Consequences for the assessor

Dimensionally-minded assessors report severity and threshold information alongside any diagnosis: not only that criteria are met, but how far above threshold the presentation lies, and which criteria are marginal. They record subthreshold presentations explicitly rather than forcing them into residual categories. They treat a diagnostic boundary as a decision rule with an error rate rather than a fact about the person. And they resist the temptation to resolve genuine diagnostic uncertainty by choosing the category that seems least objectionable, a practice that is common, well-intentioned and usually misleading.

1.6 Sources of Assessment Evidence

Different methods answer different questions, and the most persistent error in advanced practice is asking one method to do the work of another. An interview yields meaning, chronology and the client's own account; systematic observation yields behaviour in context; informant report yields the perspective of someone who sees the client in settings the assessor never will; records yield documented history and prior reasoning; standardised measures yield comparison with a reference group. Table 1.2 summarises the distinctive contribution and characteristic limitation of each source.

Table 1.2. Sources of assessment evidence: contribution and characteristic limitation

Source	Principal contribution	Characteristic limitation
Clinical interview	**Meaning, chronology, context, the client's account**	**Vulnerable to recall bias, impression management and interviewer effects**
Behavioural observation	**Actual behaviour in a specific setting**	**Reactivity; limited sampling across settings**
Informant report	**Perspective of family, partners, teachers or carers**	**Informant distress, motive and opportunity to observe**
Records and prior reports	**Documented history; earlier reasoning and its errors**	**Uneven quality; outdated conclusions recycled uncritically**
Standardised tests	**Normative comparison; quantified error**	**Construct and population specificity; administration constraints**
Performance validity measures	**Whether effort and engagement were sufficient**	**Imperfect sensitivity; not a test of honesty**
Biological and medical investigations	**Ruling out or identifying medical contributors**	**Not diagnostic of psychological disorders; access and cost**
Self-monitoring and ecological measures	Behaviour in natural settings over time	Adherence; reactivity; data burden

Convergence and divergence

Multimethod assessment is valuable not because agreement is reassuring, though it is, but because disagreement is informative. A client who reports severe depressive symptoms while presenting as organised, socially engaged and functionally intact has supplied the assessor with a discrepancy that requires explanation. Possible explanations include situational fluctuation, concealment, insight differences, measurement reactivity, informant perspective or a genuine mismatch between symptom report and functional capacity. Each implies a different next step. Averaging the two sources destroys exactly the information that would have resolved the question.

Choosing among sources

Source selection follows from the question. Questions about frequency and topography of behaviour favour observation and self-monitoring; questions about developmental history favour records and informants; questions about current severity favour standardised state measures; questions about meaning favour interview. When resources permit only one source, the assessor should state in the report which claims rest on that source alone, and how confident the conclusion can therefore be.

1.7 Base Rates and Clinical Probability

One of the most consequential findings in the assessment literature is that clinicians reason poorly about probability. The base rate of a condition in the setting where the assessment occurs determines how much weight a positive finding can bear. Where a condition is rare, even a highly specific test generates more false positives than true positives, because the pool of people without the condition is so much larger. This is not a technicality; it is the arithmetic that governs screening programmes, forensic opinions and diagnostic impressions formed in specialist clinics.

The arithmetic in practice

Suppose a screening instrument with sensitivity of .90 and specificity of .90 is used in a setting where the condition affects 2 per cent of those assessed. Of 1,000 people, 20 have the condition and 18 are correctly identified; 980 do not, and 98 are incorrectly identified as positive. A positive result therefore carries a probability of roughly 16 per cent that the condition is present. In a setting where prevalence is 30 per cent, the same instrument yields a positive predictive value above 70 per cent. The instrument has not changed; the setting has. Interpreting a score without knowing the setting is therefore an arithmetic error, not merely a stylistic one.

Consequences for threshold setting

Base rates also govern where a decision threshold should sit. Where the cost of a missed case is high and the cost of a false positive is moderate — suicid-

al risk in an emergency department, for instance — a lower threshold is defensible, provided the assessment plan includes a way to resolve the false positives. Where a positive result triggers an irreversible consequence — a child protection removal, a fitness-for-duty determination — the threshold must be higher and the evidence converging. The assessor's responsibility is to make this trade-off explicit rather than to pretend that a cut score carries intrinsic authority.

Clinician behaviour

Research on clinical judgement has documented systematic departures from normative probability reasoning, including insensitivity to base rates, overconfidence in sparse evidence and premature closure on an early hypothesis. The remedy is structural rather than exhortatory: routine statement of the setting's base rate, routine statement of the likelihood ratio implied by each finding, and routine review by a colleague before high-stakes conclusions are issued. These habits are more reliable than the intention to be unbiased, which everyone possesses and which almost no one can sustain unaided.

1.8 Functional Impairment and Context

Diagnosis describes the pattern of symptoms; impairment describes what the pattern prevents. The two are correlated but far from identical, and the difference matters for treatment planning, for eligibility decisions and for the ethical requirement not to pathologise understandable reactions. A person may meet criteria for a depressive episode while continuing to work effectively; another may fall well short of criteria while unable to leave the house. Assessment that reports only symptom counts has measured half of what the referrer needs.

Domains of functioning

Functioning is best assessed domain by domain rather than as a global impression. Work or study, household management, financial organisation, self-care, close relationships, parenting, social participation and health be-

haviour each carry different demands and different consequences of failure. Within each domain, the assessor distinguishes capacity from performance: what the person could do under optimal conditions, and what they actually do in their current environment. The gap between the two is often the most clinically informative finding in the assessment.

Context as an explanatory resource

Context is not noise to be controlled but information to be interpreted. Behaviour that appears disordered in one setting may be adaptive in another: hypervigilance in a context of genuine danger, withdrawal in a context of relentless humiliation, perfectionism in a context of conditional approval. An assessor who records only the behaviour has described a symptom; an assessor who records the behaviour and the conditions that elicit and maintain it has described a person. This is the sense in which counselling psychology's attention to context is a technical asset rather than a sentimental preference.

Reporting impairment

Impairment should be reported in behavioural terms that the referrer can use: not "moderate impairment" alone, but what the person can no longer do, for how long, with what accommodation and at what cost. Where impairment is disputed — as it often is in disability, insurance and educational determinations — the assessor should describe the evidence on which the judgement rests, including the client's own account, observed performance, informant report and any documentary corroboration, and should state what was not verified.

1.9 Evidence-Based Assessment

Evidence-based practice in psychology requires the integration of the best available research evidence, clinical expertise and the client's characteristics, culture and preferences. Applied to assessment, the principle implies that instrument selection, interpretation and decision thresholds should each be justified by evidence rather than convention. An instrument earns its place

by demonstrated reliability and validity for the population and purpose at hand, by incremental validity over cheaper alternatives, and by evidence that its use improves outcomes.

What the evidence base covers

The evidence relevant to assessment is broader than test manuals. It includes research on the diagnostic accuracy of instruments and interviews, on clinical judgement and its biases, on the effects of feedback on treatment engagement, and on the outcomes of assessment-driven decision-making. Assessment research has been unevenly translated into routine practice: many widely used instruments have limited independent validation in the populations where they are most often applied, and some well-validated procedures are under-used because they are unfamiliar or laborious. The assessor's obligation is to know the state of the evidence for what they use, including its gaps.

Expertise and its limits

Clinical expertise is a legitimate component of evidence-based practice, but it is not a licence for idiosyncrasy. Expertise shows itself in the quality of question formulation, in the recognition of when a standard procedure does not fit, in the calibration of confidence to evidence, and in the willingness to seek consultation. It does not show itself in the confident impression that contradicts the data. Where expertise and evidence conflict, the conflict should be recorded and, where possible, tested rather than resolved by seniority.

Client characteristics and preferences

The third element of evidence-based practice is the client. Language, culture, age, education, sensory and cognitive capacity and the client's own goals all affect whether an assessment is valid and whether its conclusions are useful. A measure validated in one population and administered to a client from another is not automatically invalid, but its validity is an empirical question that the assessor must address rather than assume. Chapter 14

treats this question in detail; here it is enough to note that cultural validity is a property of an interpretation, not a courtesy extended to a client.

1.10 Interprofessional Assessment

Complex presentations are rarely assessed by one profession alone. Psychiatrists contribute medical formulation and pharmacological reasoning; neurologists and physicians contribute differential medical explanation; speech and language therapists, occupational therapists and educational psychologists contribute functional and developmental expertise; social workers contribute safeguarding and systemic knowledge; nurses contribute observation across time. The counselling psychologist's contribution is typically the integration of psychological measurement with formulation, and the quality of that contribution depends on the quality of the exchange around it.

Communication across professional boundaries

Interprofessional assessment fails most often at the boundary rather than within each profession. Referrals arrive without the information needed to plan; reports are written in vocabulary the receiving professional cannot use; recommendations assume resources that do not exist in the receiving setting. Effective practice includes agreeing at the outset what each party will contribute, what format the output should take, and who holds responsibility for what. Where disagreements persist — about diagnosis, about risk, about capacity — the disagreement itself should be documented, because the next clinician will need to know that the question is contested.

Role boundaries and competence

Interprofessional working also requires clarity about competence. The assessment of neurological disorder, of medication effects, of legal capacity and of child protection risk each carry requirements that a doctoral qualification in counselling psychology does not by itself satisfy. Recognising the boundary of one's competence, referring appropriately and contribut-

ing what one is qualified to contribute are marks of seniority rather than admissions of inadequacy.

1.11 Limits of Assessment Conclusions

Every assessment conclusion is bounded by the methods that produced it, the population in which those methods were validated, the conditions under which they were administered and the time at which they were made. Advanced practice consists partly in stating those bounds precisely. "Within the limits of a single-session assessment using self-report measures in a client whose literacy in the test language was uncertain, the evidence is consistent with a moderate depressive episode; alcohol use was not assessed and may affect the picture" is a conclusion that can be acted upon. The same finding reported as "moderate depression" cannot.

Sources of uncertainty

Uncertainty enters at four points. Measurement error affects every score and should be expressed as a confidence interval rather than a point estimate. Sampling error affects every inference from a normative group to an individual. Method variance means that different methods measure partly different things. And genuine indeterminacy exists where the available evidence is compatible with more than one explanation. Only the last is usually acknowledged in reports; the first three are more common and more tractable.

Time and change

A single assessment describes a period, not a person. Symptoms fluctuate with sleep, substances, medication, menstrual cycle, seasonal change, relationships and circumstance. Conclusions about stable traits require evidence of stability, and conclusions about change require repeated measurement with instruments capable of detecting it. Where an assessment is used to make a decision that will persist — a diagnosis that will follow a child through school, a determination of capacity — the report should state its own expiry conditions: what change would require reassessment.

The limits of the assessor

Finally, the assessor's own limits belong in the account. Fatigue, unfamiliarity with a language or culture, a strong reaction to the client, an institutional pressure toward a particular conclusion: these are not disqualifying, but they are relevant. Consultation, supervision and, where appropriate, disclosure to the client are the available remedies. A report that records "assessment conducted without access to school records; conclusions about developmental history are provisional" is more professional than one that conceals the gap.

1.12 Integrating Findings into Responsible Decisions

Integration is the point at which the book's central skill is exercised. It requires holding several kinds of evidence in view at once, weighing them according to their quality and relevance, and producing a conclusion that is both decisive enough to guide action and honest about its margins. The common failure modes are well documented: the primacy effect of the first hypothesis, the anchoring effect of a prior diagnosis in the records, the tendency to average discrepant data rather than investigate the discrepancy, and the tendency to write reports that describe the assessment rather than answer the question.

A workable integration procedure

A defensible procedure has five steps. First, restate the decision the assessment was commissioned to inform. Second, list the hypotheses that were under consideration, including the ones that were discarded. Third, array the evidence relevant to each, noting its source, quality and direction. Fourth, state which hypothesis is best supported and why, and what evidence would have changed the conclusion. Fifth, translate the conclusion into recommendations that are specific, feasible and linked to identified needs.

This procedure has the additional advantage of being auditable. A colleague reading the record can see which evidence was weighed, which was

omitted and whether the conclusion follows. Where the procedure reveals that the evidence is insufficient for any conclusion, that is itself a finding and should be reported as such, with a specification of what further assessment would resolve.

Recommendations that can be used

Recommendations are the part of the report most likely to be acted upon and most likely to be written carelessly. Effective recommendations name an action, an agent, a setting and a review point: "the school to provide extended time in written examinations for the next two terms, reviewed at the end of the spring term with a re-administration of the timed reading measure" is usable; "support with examinations" is not. Recommendations should be proportionate to the evidence, should distinguish what is required from what is desirable, and should not smuggle in clinical claims that the assessment did not establish.

Closing the loop

Assessment ends with feedback and follow-up, not with the signature on the report. Feedback gives the client an opportunity to correct factual errors, to contest interpretations and to influence the plan; follow-up establishes whether the recommendations were implementable and whether the formulation predicted what happened. Both practices improve the accuracy of subsequent assessments, because they expose the assessor to the consequences of their inferences. The ethical warrant for assessment is that it helps; the empirical test of that warrant is whether it did.

> **Advanced Case Conference**
>
> **The referral.** A community mental health team asks for assessment of a 34-year-old man, referred by his general practitioner, with the question: "Does he have bipolar disorder?" The general practitioner notes two episodes of elevated mood in five years, each following a period of heavy alcohol use and each lasting four to six days; a long history of unstable employment; and a recent presentation with low mood after a relationship ended. The team's psychiatrist has already prescribed a mood stabiliser.

The evidence. Semi-structured interview establishes no episode of elevated mood lasting more than four days, no marked impairment during the episodes, and no hospitalisation. Collateral report from a sibling describes the same two episodes as "him being on form for a week", with no change in functioning. A structured diagnostic interview supports a hypomanic episode; neither episode meets criteria for mania. Screening identifies harmful alcohol use over eight years and a current moderate depressive episode. Records document two earlier diagnoses of recurrent depression, made without assessment of alcohol use.

The reasoning. Three hypotheses compete: bipolar II disorder; alcohol-related mood instability with a superimposed depressive disorder; and a primary depressive disorder with substance use. The structured interview supports the first, but the temporal association with drinking and the absence of interepisode elevation weaken it. The base rate of bipolar disorder in a community mental health setting is low enough that a single supporting source should not carry the conclusion. Discriminating evidence would be prospective mood charting over three months, corroborated by an informant, together with a period of reduced drinking.

The decision. The report records a provisional diagnosis of bipolar II disorder with a stated confidence level, documents harmful alcohol use as a cooccurring focus of treatment, and recommends prospective monitoring before any change to the mood stabiliser is considered. It states explicitly what would change the conclusion: a third episode independent of substance use, or prospective charting showing sustained elevation with functional change. The general practitioner is advised that the diagnostic question remains open, and that the current treatment plan does not depend on its resolution.

The teaching point. The assessment did not answer the question that was asked, and saying so was the correct outcome. A conclusion that answered it would have required evidence the assessment did not have.

Chapter Summary

Assessment in counselling psychology is a decision process organised around a question, not a battery organised around an instrument. Its products are distinct: diagnosis classifies, formulation explains and treatment planning prescribes, and conflating them produces reports that

neither classify accurately nor explain usefully. Interpretation is probabilistic throughout, and base rates, measurement error and method variance determine how much a finding can bear. Functional impairment and context are not ancillary information but part of what a diagnosis means for a particular person. Evidence-based assessment requires instrument selection and threshold setting to be justified by evidence for the specific purpose at hand, and it treats clinical expertise as a discipline of calibration rather than a licence for impression. Finally, the limits of an assessment are part of its conclusion: a report that states its own uncertainty is more useful, and more honest, than one that does not.

Review Questions

1. Distinguish testing from assessment, and explain why the distinction matters for interpreting a score.
2. Using an example from your own placement or service, state a referral question in the form specified in Section 1.3 and identify the decision it informs.
3. Calculate the positive predictive value of a test with sensitivity .85 and specificity .80 in settings with prevalence of 5 per cent and 40 per cent. What follows for screening policy?
4. Explain why a discrepancy between self-report and informant report should be investigated rather than averaged.
5. What does it mean to say that the limits of an assessment are part of its conclusion? Illustrate with a report sentence.

Discussion Questions

1. A court asks you to determine whether a parent has a personality disorder. How do you negotiate the referral question, and what do you record about the negotiation?
2. The team psychiatrist has already started treatment. What are the professional and ethical considerations in reporting a provisional rather than a confirmed diagnosis?

3. Should a diagnosis ever be withheld from a client at the request of a third party? Argue both positions and state your own with reasons.
4. How would you decide whether a new instrument has earned a place in your service's assessment protocol?
5. In what circumstances, if any, is an assessment without standardised instruments defensible?

Further Reading

American Educational Research Association, American Psychological Association, & National Council on Measurement in Education. (2014). *Standards for educational and psychological testing*. American Educational Research Association.

American Psychiatric Association. (2022). *Diagnostic and statistical manual of mental disorders* (5th ed., text rev.). American Psychiatric Association Publishing.

Cronbach, L. J., & Meehl, P. E. (1955). Construct validity in psychological tests. *Psychological Bulletin, 52*(4), 281–302.

Finn, S. E., & Tonsager, M. E. (1997). Information-gathering and therapeutic models of assessment: Complementary paradigms. *Psychological Assessment, 9*(4), 374–385.

Messick, S. (1995). Validity of psychological assessment: Validation of inferences from persons' responses and performances as scientific inquiry into score meaning. *American Psychologist, 50*(9), 741–749.

Meyer, G. J., Finn, S. E., Eyde, L. D., Kay, G. G., Moreland, K. L., Dies, R. R., Eisman, E. J., Kubiszyn, T. W., & Reed, G. M. (2001). Psychological testing and psychological assessment: A review of evidence and issues. *American Psychologist, 56*(2), 128–165.

World Health Organization. (2024). *Clinical descriptions and diagnostic requirements for ICD-11 mental, behavioural and neurodevelopmental disorders*. World Health Organization.

CHAPTER 2

Clinical Interviewing, Mental Status Examination and Diagnostic Reasoning

Learning Objectives

After working through this chapter, the reader should be able to:

- design an interview whose structure follows from the referral question rather than from habit;
- conduct a mental status examination that is systematic, observable and reportable;
- reconstruct symptom chronology and course so that onset, duration and change can be dated;
- evaluate medical, substance-related and developmental explanations before settling on a psychological one;
- apply structured and semi-structured interviews appropriately and understand their limits;
- document diagnostic reasoning in a form that another clinician can audit.

Key terms: presenting concern · history taking · mental status examination · symptom chronology · collateral information · differential diagnosis · structured interview · diagnostic formulation · confirmatory bias · anchoring

Introduction

The interview is the most used and least examined instrument in mental health practice. It is used to establish rapport, gather history, observe beha-

viour, assess risk and arrive at a formulation, and it is expected to accomplish all of this within an hour and without a manual. Yet the interview is also a measurement procedure with known properties: it is sensitive to interviewer style, vulnerable to memory reconstruction on the part of both parties, and dependent for its validity on the questions that were asked and the questions that were not.

This chapter treats interviewing as a technical activity that can be designed, evaluated and improved. It sets out how to build an interview from the referral question, how to conduct and record a mental status examination, how to establish chronology, how to test alternative explanations, and how to document reasoning. The emphasis throughout is on the difference between a conversation that produces a warm feeling and an interview that produces defensible evidence. The two are not opposites; the best interviews produce both, but when they diverge, evidence must win. Figure 2.1 traces the interview as a sequence of evidence-gathering steps, each answering a different question and each requiring its own check.




Figure 2.1. The structure of a diagnostic interview. Each element supplies evidence for a different claim, and the mental status examination is interpreted against, not instead of, the history.

2.1 Designing a Purposeful Clinical Interview

An interview should be designed before it is conducted. Design means deciding, in advance, which questions must be answered, which methods will answer them, how long each element will take and what will be sacrificed if time runs short. Interviews that are not designed tend to follow the client's narrative wherever it leads: informative, often humane, but unreliable as evidence, because the topics that were covered reflect conversational flow rather than the decision at hand.

From question to interview plan

The design process begins with the referral question and works backwards. If the question concerns diagnostic status, the interview must cover criterion-relevant symptoms, their duration and their functional impact, and must probe the boundary with neighbouring conditions. If it concerns formulation for psychotherapy, the interview must establish developmental history, relational patterns, maintaining cycles and the client's own understanding. If it concerns risk, the interview must cover ideation, intent, plan, means, past behaviour, protective factors and the immediate environment. A single interview can serve more than one purpose, but only if the purposes are named and time is allocated to each.

Structure and flexibility

Structure and responsiveness are usually presented as a tension; in practice they are complementary. A structured spine — a fixed sequence of domains that will be covered regardless of how the conversation develops — frees the interviewer to follow the client's account within each domain without fear of losing coverage. The spine protects against the common failure in which an emotionally charged opening topic consumes the session and the developmental history is never taken. Flexibility then operates inside the structure: the order of questions, the depth of probing and the use of silence are all adjustable.

Time budgeting

Experienced interviewers budget time explicitly. A ninety-minute first interview might allocate fifteen minutes to the presenting problem and its chronology, fifteen to developmental and family history, ten to medical and substance history, fifteen to the mental status examination, ten to risk, ten to the client's goals and expectations, and fifteen to feedback and closure. Where the budget is exceeded in one domain, the interviewer decides consciously what will be deferred and records the decision. Unrecorded omissions become invisible gaps in the eventual report.

The interviewer as an instrument

Every interviewer has a characteristic style and a characteristic set of blind spots. Some ask leading questions under time pressure; some avoid asking about suicide; some over-elaborate the areas they find interesting. Because the interviewer is the instrument, the instrument requires calibration: recording interviews, reviewing them with a supervisor, and comparing one's own conclusions with those of a colleague who saw the same client. These practices are standard in psychotherapy training and under-used in assessment training, where the assumption persists that interviewing is a natural skill rather than a disciplined one.

2.2 Opening the Interview and Establishing Rapport

Rapport in assessment is not a preliminary courtesy but a validity condition. Clients who are anxious, suspicious or uncertain about the purpose of the interview give shorter answers, under-report stigmatised experiences and withhold information about risk. The opening minutes therefore do substantive work: they establish why the assessment is taking place, who will see the results, what the limits of confidentiality are, and what the client can expect to happen.

Explaining purpose and limits

The explanation should be given in plain language and should be specific to the setting. A formulation such as the following covers the essentials without jargon: "You have been referred by your general practitioner because of difficulty sleeping and low mood. I will ask about how this started, what has made it better or worse, and how it is affecting your life. I will write a report for your doctor, and I will show you what I have written before it is sent. What you tell me is confidential, with the exception of a serious risk to your safety or someone else's, which I would discuss with you first wherever possible."

Consent is then obtained for the assessment as described, and separately for any recording, collateral contact or release of information. Consent obtained at the start is not a substitute for consent at each subsequent stage; clients retain the right to decline particular lines of enquiry.

Managing expectations and anxiety

Clients arrive with assumptions about assessment, often drawn from television, previous negative experiences or fear of being judged. Naming these assumptions early is usually more effective than reassurance. "Some people worry that this is a test they can fail, or that what they say will be used against them. It is not, and it will not be, unless there is a risk I have to act on; if that happens I will tell you." Where a client has had a previous assessment they experienced as dismissive, asking about it yields both rapport and information about how they are likely to present now.

Culture, language and the etiquette of disclosure

The conventions of first meetings vary. Direct eye contact, the use of first names, questions about family or about income may be appropriate in one cultural setting and intrusive in another. Interpreters change the interpersonal geometry of the interview and require their own briefing. Clients from settings where mental distress is expressed somatically may open with bodily complaints, and the interviewer who redirects too quickly to psychological content may lose the account entirely. The practical rule is to ask

about, rather than assume, the client's preferences on matters of address, accompaniment and disclosure.

2.3 History of Presenting Concerns

The history of the presenting concern is the evidential centre of the interview. It must establish what the problem is, when it began, how it has changed, what makes it better or worse, what the client has already tried, and what the client believes is happening. Each of these elements supports a different inference, and each is vulnerable to a characteristic distortion.

Establishing the problem in behavioural terms

Clients describe problems in evaluative language: "I'm a failure", "I can't cope", "my anxiety is terrible". The interviewer's task is to convert these evaluations into descriptions that can be dated, counted and compared. What does "can't cope" look like on a Tuesday morning? How many days in the past month did the client leave the house? What does "terrible" mean on a scale where the worst week of the client's life is ten? Conversion is not pedantry; it is what makes change measurable and what allows a second clinician to understand the baseline.

Onset, duration and course

Dating onset is more difficult than it appears, because clients reconstruct beginnings in the light of present understanding. Three techniques improve accuracy: anchoring to public events (a move, a bereavement, a job change, a pandemic); asking about the last period of normal functioning and working forwards; and obtaining collateral confirmation. The distinction between abrupt and gradual onset, between episodic and continuous course, and between stable and deteriorating trajectory carries substantial diagnostic weight. A first episode of psychosis that develops over two years is a different clinical object from one that develops over two weeks.

Precipitants, maintaining factors and prior attempts

Having established the pattern, the interview turns to what surrounds it. Precipitants are events temporally associated with onset; maintaining factors are processes that keep the problem going, including avoidance, reassurance-seeking, sleep disruption, alcohol use, relationship conflict and occupational strain. Asking what the client has already tried — and what happened — yields information about both the problem and the client's model of it. Clients who have consulted five practitioners and been helped by none are telling the assessor something that should be examined rather than assumed.

The client's explanatory model

Every client arrives with an explanation. It may be biomedical, moral, interpersonal, spiritual or none of these. Eliciting the explanation serves three purposes: it identifies beliefs that will shape engagement; it may contain information the assessor lacks; and it establishes the terms in which feedback will eventually have to be given. Explanations that are factually incorrect, such as a belief that low mood is caused by a permanently damaged brain, can often be modified through discussion of evidence, but only after they have been heard.

2.4 Developmental, Family and Social History

Developmental history is often deferred when time is short, and its absence is one of the most frequent weaknesses of assessment reports. Yet it supplies information that no current-state measure can: the trajectory of the person's functioning, the presence of longstanding difficulties that were previously tolerated, and the family and social context in which the present problem is embedded.

Developmental milestones and early history

Pregnancy and birth complications, early illness, language and motor milestones, schooling and peer relationships, and the age at which difficulties were first noticed all belong in the record. The purpose is not to assemble a

complete biography but to identify deviations with diagnostic relevance: a child whose language developed late and who has always found social rules opaque presents a different differential from one whose difficulties began abruptly at fourteen. Where the client cannot report early history, an informant or contemporaneous record should be sought, and the source of the information stated.

Family history

Family history of mental disorder, substance use, suicide and neurological illness is relevant to both risk and formulation. It should be recorded with the same care as other clinical information: who, what, when, and whether the diagnosis was made clinically or reported by the family. Family history reported by a client who has never met the affected relative is weaker evidence than a documented admission, and the difference should be visible in the record.

Social and occupational history

Education, employment, housing, income, relationships, caring responsibilities and migration history describe the conditions under which the person functions. They are not background colour; they are the context against which impairment is judged. A client who has stopped working because their employer closed has not necessarily deteriorated in functioning, and a client who continues to work while profoundly depressed may be doing so at unsustainable cost. Asking about the shape of an ordinary week is often the most efficient route into this material.

Adverse experiences and trauma

Enquiry about adverse experiences should be routine, specific and paced. Routine, because clients rarely volunteer such material unprompted; specific, because "have you experienced trauma?" invites a considered answer about identity rather than a factual one; paced, because detailed trauma enquiry in a first interview can be destabilising when the purpose is assessment rather than treatment. The interviewer asks what happened, when,

and whether it is currently affecting sleep, intrusions or avoidance, and defers detailed narrative to a context where it can be contained.

2.5 Mental Status Examination

The mental status examination (MSE) is the structured description of the client's current psychological functioning, observed and elicited during the interview. Its conventions derive from clinical psychiatry and have been refined over more than a century; its purpose is to make observable data comparable across examiners and over time. The MSE is not a diagnosis and should not be written as one. It is a record of findings, each of which must be described in terms specific enough to be contested.

Domain structure

A complete examination covers appearance and behaviour, speech, mood and affect, thought form, thought content, perception, cognition, insight and judgement. Table 2.1 lists the domains, the observations that belong to each, and the descriptive vocabulary conventionally used. The order is flexible, but all domains should be addressed, and negative findings should be recorded as explicitly as positive ones: "no perceptual abnormality elicited" is a finding; silence is not.

Table 2.1. The mental status examination: domains and observations

Domain	Observations to record	Example phrasing
Appearance and behaviour	Dress, hygiene, posture, gait, eye contact, cooperation, psychomotor activity	"Dressed appropriately for the season; cooperative; motor activity slowed throughout"
Speech	Rate, volume, prosody, quantity, fluency, articulation	"Normal rate and volume; fluent; no word-finding difficulty"
Mood and affect	Self-reported mood; observed range, reactivity, congruence	"Describes mood as 'flat, grey'; affect restricted but reactive to humour"
Thought form	Rate and flow, coherence, loosening of associations, circumstantiality, perseveration	"Tangential at times; no derailment or incoherence"
Thought content	Preoccupations, obsessions, delusions, overvalued ideas, suicidal and homicidal ideation	"Preoccupied with contamination; no delusional conviction"
Perception	Hallucinations in each modality, illusions, depersonalisation, derealisation	"Denies auditory or visual hallucination; transient derealisation during panic"
Cognition	Orientation, attention, memory, executive function, estimated premorbid level	"Oriented; digit span 6 forwards; recalls 3/3 after delay"
Insight	Attribution of symptoms, acceptance of treatment, understanding of risk	"Attributes difficulties to 'stress' but accepts referral; partial insight"
Judgement	Decision-making, social judgement, risk-related behaviour	"Has continued driving despite blackouts; judgement impaired in this domain"

Observation before enquiry

Much of the examination is observational and should be recorded before the client's self-report is reported. A client who describes severe agitation while sitting still for fifty minutes has supplied a discrepancy worth recording. Affect is observed; mood is reported; the two should never be conflated. The examiner records what was seen, what was heard and what was

said, in language that distinguishes the three: “reported”, “appeared”, “described”.

Cognitive screening within the MSE

A brief cognitive screen belongs in every MSE where cognition is relevant to the question: orientation to time, place and person; attention by digit span or serial sevens; registration and delayed recall of three items; and a measure of executive function such as verbal fluency or a clock-drawing task. Screening is not assessment. A poor screening result indicates the need for formal cognitive assessment, and a good result does not exclude significant difficulty in a high-functioning person, particularly where the screen is affected by education, language or culture. Chapter 6 treats formal cognitive assessment in detail.

Recording and its uses

The MSE should be written in the past tense, in prose, in the third person, and without diagnosis. It should be specific enough that another examiner could compare their own findings on a later occasion, which is the point of a standard vocabulary. Phrases such as “affect appropriate” or “insight poor” should be avoided unless the basis for the judgement is given. The most useful MSE records are those written with an eye to the next assessment rather than only to the present one.

2.6 Symptom Chronology and Course

Chronology is the skeleton of diagnosis. Most of the distinctions that matter clinically depend on sequence and duration: whether low mood preceded or followed heavy drinking; whether obsessions appeared before or after the onset of depression; whether attention difficulties were present before the age of twelve; whether a period of elevated mood lasted four days or four weeks. An interview that establishes the presence of symptoms without establishing their temporal relations has collected half the necessary evidence.

Building a timeline

The most reliable technique is to construct a timeline with the client, working backwards from the present and anchoring each event to something memorable. A sheet of paper with a horizontal line, marked by years and significant events, converts a rambling history into a sequence that both parties can inspect. Discrepancies emerge naturally: the client who dated their low mood to a divorce is found, on the timeline, to have consulted their general practitioner two years earlier.

Duration and episodicity

Duration matters both for diagnostic thresholds and for prognosis. Interviewers systematically under-estimate the duration of episodes and over-estimate the duration of remissions, because recent symptoms are more memorable than recent wellness. Asking "when was the last week in which you felt like your usual self?" is often more informative than asking about the beginning of the current episode.

Course and its diagnostic implications

Course describes the trajectory over time: single episode with recovery, recurrent episodes with inter-episode recovery, continuous course, deteriorating course, or fluctuating course without clear episodes. Course is often more discriminating than symptom content. Rapid onset with full recovery and preserved inter-episode functioning supports a different set of explanations from a slow, insidious deterioration with progressive functional decline.

Reconciling discrepant timelines

Where the client's timeline contradicts the records or an informant, the assessor should not simply prefer one source. Discrepancies usually have explanations: memory decay, shame, different definitions of the problem, or a genuine change in the client's understanding. Recording both accounts and the reason for preferring one is more valuable than silently adopting the more convenient version.

2.7 Collateral Information and Records

Collateral information is evidence supplied by someone other than the client, or documented before the current assessment. Its value is that it is independent of the client's current presentation; its limitation is that it is also independent of the client's current experience. Neither source is intrinsically superior, and the assessor's task is to weigh them.

Obtaining collateral well

Collateral contact requires the client's consent in almost all circumstances, and the client should know what will be asked and what will be shared. Where consent is refused, the assessor can still proceed but should record the refusal and its effect on the confidence of the conclusions. Informants should be briefed on the purpose of the contact, asked for specific observations rather than global judgements, and told what will happen with the information. An informant asked "is he depressed?" will answer with an opinion; an informant asked "what have you noticed about his sleep, appetite and interest in things he used to enjoy over the past two months?" will answer with evidence.

Records: uses and hazards

Records establish chronology, document prior assessments and reveal previous reasoning, including previous errors. They also transmit error with the authority of print: a diagnosis made in a fifteen-minute consultation and repeated in four subsequent letters acquires spurious solidity. The assessor should distinguish primary documentation from summarised reports, note the source and date of each, and treat an unsupported diagnosis in the records as a hypothesis rather than a finding.

Weighing conflicting accounts

Where accounts conflict, the assessor examines three things: the opportunity of each source to observe the behaviour in question; the motive each might have for distortion; and the specificity of the description. A partner who has lived with the client for a decade and describes nightly waking at

three in the morning is a stronger source on sleep than a client who reports sleeping "fine". A teacher who has known the child for six weeks is a weaker source on developmental history than a parent, though possibly stronger on classroom behaviour.

2.8 Differential Diagnosis

Differential diagnosis is the disciplined comparison of competing explanations. It is not the production of a list; it is the identification of the evidence that would separate the items on the list. Performed well, it converts an open-ended interview into a sequence of discriminating questions and gives the eventual report a visible logic.

Generating the differential

The differential should include, at minimum, the most likely explanation, the most serious explanation that must not be missed, and the explanation the client or referrer considers most likely. Neighbouring categories within the same diagnostic family should be considered explicitly, since these are the errors that occur most often: depressive episode versus persistent depressive disorder versus bipolar depression; generalised anxiety versus panic disorder with agoraphobic avoidance; obsessive-compulsive disorder versus generalised anxiety; post-traumatic stress disorder versus adjustment disorder.

Discriminating evidence

For each pair of explanations, the assessor identifies the findings that would separate them: age of onset, episodicity, presence of elevated mood, response to previous treatment, family history, substance involvement, and the presence of a defining feature such as obsessions or flashbacks. These discriminating findings become the priority questions for the remainder of the interview, and their absence from the record is the clearest sign that differential reasoning did not take place.

When the differential cannot be resolved

Some differentials cannot be resolved at a single assessment. Where the discriminating evidence requires observation over time — as it does for bipolar spectrum presentations, for personality difficulties in a young adult, and for the boundary between trauma-related and psychotic phenomena — the correct output is a provisional conclusion with a stated review point, not a forced choice. Recording the unresolved differential, and what would settle it, is the mark of a completed rather than an abandoned assessment.

2.9 Medical and Substance-Related Explanations

A substantial minority of presentations that appear psychological at first contact have a medical or substance-related contributor, and a further group has both. The assessor is not expected to practise medicine, but is expected to know which questions to ask, which findings prompt referral, and how medical and substance factors alter the interpretation of psychological data.

Medical contributors to consider

Conditions that commonly present with psychiatric symptoms include thyroid dysfunction, anaemia, vitamin B12 deficiency, sleep apnoea, chronic pain, diabetes, autoimmune conditions, temporal lobe epilepsy, delirium and early dementia; medications including corticosteroids, beta-blockers, isotretinoin, interferon and some hormonal treatments may also contribute. The interview should establish recent physical investigations, current medication, changes in medication, chronic illness and unexplained physical symptoms. Findings that mandate prompt medical referral include new confusion, focal neurological signs, headache of recent onset with vomiting, unexplained weight loss and first presentation of psychosis in later life.

Substance use

Substance use is systematically under-detected in routine interviews. Standard practice is to ask about tobacco, alcohol, cannabis, stimulants, opioids,

prescribed medication used outside prescription, and novel psychoactive substances, using a quantity–frequency approach and a validated screen where time allows. The relevant temporal questions are whether use preceded, coincided with or followed the onset of symptoms, and whether there has been a period of abstinence during which symptoms resolved. A presentation that has never been observed in the absence of substance use cannot be attributed confidently to a primary psychological disorder.

Integrating medical and psychological evidence

Medical and psychological explanations are not competitors in most cases. Chronic illness produces psychological distress; psychological disorder worsens medical outcomes; medication produces symptoms that are then treated as psychiatric. The report should state the medical information available, note what is unknown, and specify what would change the interpretation. Where information is unavailable, the limitation belongs in the conclusions rather than in a footnote.

2.10 Interviewing Under Conditions of Distress

Much assessment occurs when the client is distressed, intoxicated, acutely psychotic, in pain, in crisis or in an emergency department at three in the morning. Under these conditions the standard interview must be adapted, and the assessor must decide what can reliably be assessed now and what must wait.

Acuity and its consequences

Acute distress narrows attention, impairs recall and increases suggestibility. A client in crisis may not be able to give a coherent developmental history, and pressing for one wastes the opportunity to establish safety and engagement. The priority sequence is: immediate safety; physical needs such as pain, hunger, intoxication or withdrawal; orientation and coherence; the presenting crisis; and only then a fuller history, either later in the same contact or at a scheduled follow-up.

Interviewing clients with psychosis or severe agitation

With psychotic presentations the interviewer adjusts pace, uses shorter sentences, avoids confrontation of delusional content where it is not necessary to the question, and records the content accurately without endorsing it. Agitation calls for environmental measures before verbal ones: reducing noise, ensuring an exit, sitting at an angle, keeping the door open, and involving colleagues where risk is escalating. The interviewer's own arousal is data; noticing fear is a reason to attend to safety rather than to suppress the observation.

Emergency assessment and the limits of consent

In emergencies, assessment may proceed without full consent where necessary to protect life, and the legal basis will vary by jurisdiction. The assessor should record what was done, on what authority, and what the client was told. Capacity to consent to assessment should be considered rather than assumed, particularly where intoxication, delirium, intellectual disability or acute psychosis is present. A short, documented capacity assessment is preferable to a silent assumption either way.

2.11 Structured and Semi-Structured Interviews

Structured and semi-structured diagnostic interviews exist to improve the reliability of diagnosis by fixing the questions, the decision rules and the order of enquiry. Their use is one of the better-evidenced practices in diagnostic assessment, and their neglect in routine practice is one of the more persistent gaps between evidence and service delivery.

The available formats

Fully structured interviews specify every question and every coding decision, allowing administration by trained interviewers without clinical judgement. Semi-structured interviews specify the domains and the decision rules but leave the wording and the follow-up probing to the clinician. Instruments in common use include the Structured Clinical Interview for DSM-5 (SCID-5; First, Williams, Karg, & Spitzer, 2016), the Mini

International Neuropsychiatric Interview (Sheehan et al., 1998) and the ICD-11 based schedules developed for epidemiological and clinical use. Each has a defined training requirement and a defined scope; none assesses everything, and most are weak on personality, risk and functional impairment.

Strengths and costs

The strengths are reliability, completeness and auditability: a structured interview ensures that criterion-relevant questions are asked and that the answers are recorded in a comparable form. The costs are time, training, rigidity and a tendency to produce diagnosis without formulation. The instruments were designed for research and epidemiological use, and their translation into clinical practice requires the addition of exactly the contextual and functional enquiry that they do not supply.

Using them well

Used well, a semi-structured interview forms the spine of the diagnostic part of the assessment, with the assessor supplementing it with history, collateral and functional enquiry. Used badly, it becomes a checklist administered without attention, producing a diagnosis that is technically derived and clinically shallow. The difference is visible in the report: a checklist yields a list of criteria met; a well-conducted interview yields criteria met, alternatives excluded, and the reasoning that connects them.

2.12 Documenting Diagnostic Reasoning

The interview concludes with a written record. Its purpose is to allow another qualified professional to understand what was asked, what was found, what was concluded and how confident the conclusion should be. Documentation is therefore not an administrative afterthought but the final stage of the reasoning process, and it is often the stage at which weaknesses become visible.

Structure of the interview record

A workable record contains: the source of referral and the question asked; the client's account of the presenting problem; chronological history; developmental, family, social and medical history; substance use; risk; the mental status examination; the methods used, including any structured interview; a formulation; a differential diagnosis with the evidence for and against each alternative; conclusions with confidence; and recommendations. Each section should distinguish reported information from observed information and from the assessor's inference.

Recording uncertainty

Uncertainty should be recorded in specific terms. "Diagnosis uncertain" is uninformative. "Criteria for a moderate depressive episode appear to be met; the assessment of duration depends on the client's dating of onset, which conflicts with the general practitioner's record; a bipolar spectrum explanation cannot be excluded on current evidence" tells the reader exactly where the doubt lies and what would resolve it.

Language, stigma and the client's access

Records are increasingly accessible to clients, and should be written in language that the client could read without harm. Pejorative descriptors, speculation about personality presented as fact, and irrelevant personal detail should be excluded. This is not only an ethical requirement but a clinical one: records written with the client as a potential reader tend to be more precise and less judgemental, and both qualities improve their professional usefulness.

> **Advanced Case Conference**
>
> **The referral.** A 29-year-old woman is referred by her employer's occupational health service after three months of increasing absence. The stated question is whether she is fit to return to work and whether she has depression.

The interview. She describes low mood, early waking, loss of appetite and loss of confidence beginning nine months earlier after a reorganisation placed her under a manager she experiences as humiliating. She has not worked for eleven weeks. The mental status examination shows slowed speech, restricted but reactive affect, no perceptual abnormality, and intact cognition. She describes passive suicidal ideation without intent. She drinks two bottles of wine most evenings, which she dates to the same period; she has not had a drink-free week since the onset. PHQ-9 score is 18.

The differential. Major depressive episode; alcohol-induced mood disturbance; adjustment disorder with depressed mood; and an underlying anxiety disorder with secondary avoidance. The discriminating questions concern sequence and abstinence: mood symptoms and drinking began within the same month; she reports no period of abstinence long enough to observe mood; her account of "humiliation" includes panic symptoms in the manager's presence dating from before the reorganisation.

The reasoning. The depression is real and severe enough to warrant treatment, and the alcohol use is likely both a consequence and a maintaining factor. The presence of pre-existing panic-like symptoms weakens a pure adjustment explanation and raises the possibility of an anxiety disorder that the reorganisation exacerbated. Fitness for work cannot be determined from severity alone; it depends on the availability of adjustments and on whether the panic can be managed in the specific work setting.

The decision. The report records a moderate depressive episode with harmful alcohol use, notes the unresolved question of an underlying anxiety disorder, and recommends treatment for both before any determination of fitness. It specifies workplace adjustments that would be tested on a phased return, and it states that the assessment of fitness will need to be repeated once drinking has reduced and treatment is established. The occupational health service is advised that returning a diagnosis without a functional assessment would not answer the question it asked.

The teaching point. The interview established sequence, not just severity. The sequence changed the formulation, and the formulation changed the recommendation.

Chapter Summary

The clinical interview is a designed instrument. Its structure should follow from the referral question, its time should be budgeted, and its coverage should be fixed in advance so that emotionally salient material does not displace the domains that matter for the decision. The mental status examination converts observation into a standard vocabulary, and its value depends on the examiner distinguishing what was seen from what was reported. Chronology and course are the backbone of differential reasoning: many diagnostic questions are settled by sequence and duration rather than by symptom counts. Medical and substance-related explanations must be considered before a psychological one is adopted, and structured interviews improve reliability while supplying neither formulation nor functional assessment. Documentation is the final act of reasoning, and a record that states its uncertainty precisely is more useful than one that conceals it in confident prose.

Review Questions

1. Explain how the referral question determines the structure of an interview, using two contrasting referral questions.
2. What is the difference between mood and affect, and why should they be recorded separately?
3. Describe three techniques for improving the accuracy of reported onset.
4. Why does a period of abstinence matter when assessing a presentation complicated by substance use?
5. What does a semi-structured diagnostic interview add, and what does it not add, to a clinical assessment?

Discussion Questions

1. A client refuses consent for collateral contact. How does this affect the confidence of your conclusions, and what do you record?

2. Should every client be asked about suicidal ideation in the first interview? Consider the evidence, the ethics and the practicalities.
3. The records contain a diagnosis made six years ago by a clinician who saw the client once. How do you handle it?
4. How would you adapt an interview for a client who is agitated and suspicious in an emergency department?
5. Is there a place for assessment without a structured interview in doctoral-level practice? Defend your position.

Further Reading

American Psychiatric Association. (2022). *Diagnostic and statistical manual of mental disorders* (5th ed., text rev.). American Psychiatric Association Publishing.

Croskerry, P. (2003). The importance of cognitive errors in diagnosis and strategies to minimize them. *Academic Medicine, 78*(8), 775–780.

First, M. B., Williams, J. B. W., Karg, R. S., & Spitzer, R. L. (2016). *Structured Clinical Interview for DSM-5 Disorders, Clinician Version (SCID-5-CV)*. American Psychiatric Association Publishing.

Grove, W. M., Zald, D. H., Lebow, B. S., Snitz, B. E., & Nelson, C. (2000). Clinical versus mechanical prediction: A meta-analysis. *Psychological Assessment, 12*(1), 19–30.

Nordgaard, J., Sass, L. A., & Parnas, J. (2013). The psychiatric interview: Validity, structure, and subjectivity. *European Archives of Psychiatry and Clinical Neuroscience, 263*(4), 353–364.

Robins, E., & Guze, S. B. (1970). Establishment of diagnostic validity in psychiatric illness: Its application to schizophrenia. *American Journal of Psychiatry, 126*(7), 983–987.

Sheehan, D. V., Lecrubier, Y., Sheehan, K. H., Amorim, P., Janavs, J., Weiller, E., Hergueta, T., Baker, R., & Dunbar, G. C. (1998). The Mini-International Neuropsychiatric Interview (M.I.N.I.): The development and validation of a structured diagnostic psychiatric interview for DSM-IV and ICD-10. *Journal of Clinical Psychiatry, 59*(Suppl. 20), 22–33.

World Health Organization. (2024). *Clinical descriptions and diagnostic requirements for ICD-11 mental, behavioural and neurodevelopmental disorders*. World Health Organization.

CHAPTER 3

Psychometrics: Reliability, Validity, Norms and Measurement Error

Learning Objectives

After working through this chapter, the reader should be able to:

- explain the classical test model and the meaning of observed score, true score and error;
- select and interpret indices of reliability appropriate to the intended use of a measure;
- calculate and apply the standard error of measurement and the standard error of a difference;
- evaluate the five sources of validity evidence set out in current professional standards;
- interpret norms, standard scores and percentiles without overstating their precision;
- reason about sensitivity, specificity and predictive values in relation to base rates;
- identify what a technical manual does and does not establish.

Key terms: observed score · true score · measurement error · reliability coefficient · standard error of measurement · standard error of the difference · validity argument · internal structure · measurement invariance · standard score · percentile rank · sensitivity · specificity · predictive value · cut score · differential item functioning

Introduction

Psychometrics is the discipline that allows an assessor to say how much confidence a score deserves. It is not an optional technical background to clinical practice but the grammar in which score-based claims are made. An assessor who cannot compute a confidence interval around an obtained score, or explain why a difference between two subtests may be unremarkable, is not in a position to interpret the instrument they have used, however well they administered it.

This chapter sets out the minimum technical apparatus required for advanced practice. It treats reliability as a property of scores rather than of tests, validity as an argument rather than a coefficient, and norms as a comparison sample rather than a standard of health. It also insists on a distinction that the clinical literature often blurs: the difference between the accuracy of a measure and the usefulness of a decision made with it. A test can be accurate and still be a poor basis for a decision, if the decision threshold is badly placed or the base rate in the setting is low. Figure 3.1 sets out the psychometric chain, in which each link is a separate empirical claim rather than an inference from the others.




Figure 3.1. The psychometric chain. Each link is a separate empirical claim, and no link can be inferred from the strength of the others.

3.1 Measurement Models and Observed Scores

Every score produced by a psychological test is an observation, not a quantity known without error. Classical test theory formalises this intuition: an observed score is the sum of a true score and an error component, where the true score is defined as the expected value of observed scores across hypothetical repeated administrations. The model is deliberately modest. It does not claim that the true score is a fixed property of the person, only that a given measurement procedure has an expected value for that person at that time.

The classical model and its assumptions

The classical model assumes that error is random, uncorrelated with true score and uncorrelated across measurements. These assumptions are convenient rather than universally true: practice effects, fatigue, mood change and item exposure all produce error that is systematic rather than random. The practical consequence is that classical indices may over-state the stability of a score across occasions, which is why test–retest coefficients are usually lower than internal consistency coefficients for the same instrument.

Domain-sampling and latent-variable models

Two other families of measurement model are worth distinguishing. Domain-sampling models treat a test as a sample from a universe of equivalent items; generalisability theory extends this by allowing the assessor to quantify how much of the error is attributable to particular facets, such as occasion, rater or item set. Latent-variable models treat the observed items as indicators of an unobserved construct and estimate the relationship between them. Item response theory, a latent-variable approach, has the practical advantage of placing persons and items on the same scale, which is why it underpins many modern adaptive tests and norming programmes.

Why the model matters clinically

The model matters because interpretations differ according to which one is assumed. An internal-consistency interpretation treats a high coefficient as

evidence that the items measure one thing; a test–retest interpretation treats it as evidence that the score is stable. Neither implies the other, and neither implies validity. The assessor who asks "what does this coefficient tell me about the claim I am about to make?" will avoid most of the misinterpretations that appear in reports.

3.2 Reliability and Score Consistency

Reliability refers to the consistency of scores across replications of a measurement procedure. It is not a single property but a family of properties, each defined by the source of error that is allowed to vary. A coefficient is meaningless unless the assessor knows which source of error it addresses. Table 3.1 distinguishes the principal forms of reliability and identifies the source of error that each one addresses.

Table 3.1. Forms of reliability and the error each addresses

Coefficient	Source of error allowed to vary	Typical use and caution
Internal consistency (α, ω)	Item content within a single administration	Estimating homogeneity; α assumes unidimensional items and equal loadings
Split-half with correction	Item halves within one administration	Rarely reported; superseded by α and ω
Test–retest	Occasions	Stability of scores; affected by practice, memory and genuine change
Alternate forms	Item sets	Form equivalence; requires large, matched item pools
Inter-rater	Raters	Consistency of scoring judgements; requires independent ratings
Inter-method	Methods	Convergence across procedures; lower than within-method coefficients
Standard error of measurement	All random error	Precision of an individual score; depends on the reliability estimate used

Internal consistency

Cronbach's alpha remains the most reported coefficient, and the most misused. It is a lower bound to reliability under restrictive assumptions of essential tau-equivalence, and it is inflated by test length and by item redundancy. Sijtsma (2009) argued that alpha's usefulness is limited and that its routine reporting has obscured the more relevant question of whether a set of items measures a single attribute; McNeish (2018) and Dunn, Baguley and Brunsden (2014) have made the same case and recommended alternatives such as omega. For the assessor, the practical implications are that a high alpha does not establish unidimensionality, that alpha should be reported for the specific sample used, and that a very high alpha (above .95) in a short scale may indicate redundant items rather than excellent measurement.

Test–retest and stability

Test–retest reliability is relevant whenever a score will be interpreted as a stable characteristic or used to evaluate change. Coefficients are affected by the interval: too short and respondents remember their answers; too long and genuine change attenuates the coefficient. For state measures, low test–retest reliability is expected and appropriate, since the construct itself is meant to vary. Reporting a state measure's stability as though it were a virtue, or a trait measure's instability as though it were a defect, are both category errors.

Inter-rater reliability and agreement

Where a score depends on clinical judgement — a diagnostic interview, a personality rating, a risk assessment — inter-rater reliability is central. Cohen's kappa corrects for chance agreement on categorical judgements and is conventionally interpreted with the benchmarks proposed by Landis and Koch (1977), although these are arbitrary and should be reported alongside raw agreement and prevalence. For continuous ratings, intraclass correlation coefficients are preferable to simple correlations because they

account for systematic differences between raters as well as rank-order agreement.

3.3 Standard Error and Confidence Intervals

A reliability coefficient is not directly useful at the level of the individual case. What the assessor needs is an estimate of how far an individual's obtained score is likely to be from their true score. The standard error of measurement provides this: it is the standard deviation of the hypothetical distribution of obtained scores around a person's true score, and it is computed as the standard deviation of the test multiplied by the square root of one minus the reliability coefficient.

Using the standard error

Because the error distribution is approximately normal, a 95 per cent confidence interval is obtained by adding and subtracting 1.96 standard errors from the obtained score. For an instrument with a standard deviation of 15 and a reliability of .90, the standard error is 4.74 and the 95 per cent interval around an obtained score of 100 runs from approximately 91 to 109. Two consequences follow. First, a score is a region, not a point, and reports should present it as such. Second, differences between scores that lie within overlapping intervals should not be interpreted as meaningful.

The standard error of the difference

Comparisons between two scores require a different statistic, because each score carries its own error. The standard error of the difference incorporates the reliability and the correlation between the two measures, and it is always larger than the standard error of either score alone. This is why the difference between a verbal and a performance score of ten points is often unremarkable, and why the interpretation of subtest scatter requires the difference to exceed a threshold that the manual should specify. Assessors who interpret any difference as a profile are reading noise.

Regression to the mean and extreme scores

Where a client is selected for assessment because their score was extreme — a high score on a screening questionnaire, a low score on an intake measure — a second administration will tend to be closer to the mean even if nothing has changed. This is a statistical property, not evidence of improvement or deterioration. Its practical implication is that change should be evaluated against a comparison group or a reliable change index rather than against the raw difference between two scores.

3.4 Validity as Evidence for Interpretation

Validity is the degree to which evidence and theory support the interpretations and uses of test scores. It is a property of an interpretation, not of an instrument, and it is never established once and for all. The current *Standards for Educational and Psychological Testing* frame validation as the accumulation of evidence across five sources: evidence based on test content, on response processes, on internal structure, on relations with other variables, and on the consequences of testing (American Educational Research Association, American Psychological Association, & National Council on Measurement in Education, 2014).

The unified view

Messick's (1995) unified conception of validity integrated these sources into a single argument about score meaning, and it remains the dominant framework. In this view, construct validity is not one type among several but the whole of the argument, of which content, structure and external relations are components. Kane (2013) extended the approach by describing validation as the construction of an interpretive argument that can be evaluated for its inferences and assumptions. Both frameworks share a practical implication: the assessor should be able to state the argument that connects an observed score to the claim being made, and should be able to identify the weakest link in that argument.

What validity is not

Validity is not the same as reliability, though reliability constrains it. It is not established by factor analysis alone, by correlation with another instrument alone, or by the test's widespread use. Nor is it a property that transfers automatically across populations, languages or purposes. An instrument validated for screening in primary care is not thereby validated for forensic determination, and an instrument validated in one cultural setting requires evidence before it is used in another.

Threats to validity in practice

The most common threats in clinical practice are not statistical but procedural: administration that departs from the standard without being recorded; interpretation that ignores the reference group; use of a measure outside its validated age range; coaching or rehearsal of items; and the accumulation of multiple small deviations, none of which alone would invalidate the score. The assessor's protection is documentation specific enough to allow a reader to judge whether the interpretation was warranted.

3.5 Content and Response Process Evidence

Content evidence concerns the relationship between the test's items and the construct domain it is intended to represent. Response process evidence concerns what respondents actually do when they answer. Both are usually established during test development, and both are frequently assumed rather than examined in clinical practice.

Content representativeness

A test's content should sample the domain it claims to measure, in proportions that reflect the domain's structure. This is a judgement informed by expert review, task analysis and, where relevant, curriculum or diagnostic specifications. The relevant question for the assessor is not whether the items look sensible but whether the domain they sample corresponds to the construct in which the referral question is framed. A measure of "depression" that omits anhedonia, or a measure of "executive function" that

samples only one executive subdomain, will produce scores that are valid for something narrower than the label suggests.

Response processes

Response process evidence asks whether respondents are doing what the test assumes they are doing. A reading comprehension item assumes decoding and comprehension; if the respondent cannot decode, the item measures something else. A self-report item about "worry" assumes that the respondent interprets worry in the intended sense, which varies with language, culture and clinical experience. Cognitive interviewing during test development, and think-aloud studies, are the standard methods for examining these assumptions. In clinical practice the equivalent is vigilance: the assessor watches how the client engages with the task, not only what score results.

Fairness as a content issue

Content and response process evidence are also where fairness begins. Items that presuppose knowledge, vocabulary or experience unevenly distributed across groups introduce construct-irrelevant variance, which is a validity problem before it is an equity problem. The professional standards treat fairness as integral to validity rather than as a separate consideration, and this framing is the correct one.

3.6 Relations with Other Variables

Evidence based on relations with other variables examines whether scores behave as the construct implies they should. It includes convergent evidence (correlation with measures of the same or related constructs), discriminant evidence (low correlation with measures of different constructs), criterion-related evidence (prediction of a current or future outcome) and nomological evidence (fit within a network of theoretical relationships).

Convergent and discriminant evidence

A new measure of anxiety should correlate substantially with established anxiety measures and less substantially with measures of, say, working memory. The pattern, not any single coefficient, carries the argument. Where correlations with everything are moderate, the measure may be assessing general distress rather than the specific construct claimed — a common problem in clinical self-report, where negative affectivity inflates correlations among all symptom scales.

Criterion-related evidence

Criterion-related evidence addresses the practical question directly: does the score predict the outcome the decision concerns? For diagnostic instruments, this is expressed as sensitivity, specificity and predictive values, treated in Section 3.9. For prognostic instruments, it may be expressed as the proportion of variance in outcome explained, or as the area under a receiver operating characteristic curve. Criterion evidence is highly context-specific: a coefficient obtained in a specialist clinic may not hold in primary care, because the range of presentations and the base rate differ.

Nomological networks and incremental validity

The strongest validity arguments place a measure within a network of expected relationships derived from theory, including relationships with variables it should *not* predict. Incremental validity is a special and practically important case: does the measure add predictive accuracy beyond information already available, such as a brief interview or an existing record? Many instruments with respectable validity have negligible incremental validity, and the assessor who asks this question is doing more for their clients than the one who asks only whether the instrument is "validated".

3.7 Internal Structure

Internal structure evidence concerns the relationships among items and subscales: whether the measure behaves as a unidimensional scale, a set of correlated factors or a hierarchical structure with a general factor. It is usu-

ally examined by exploratory factor analysis during development and confirmatory factor analysis thereafter.

Dimensionality and its clinical meaning

Dimensionality is not an abstract statistical property. A measure that is unidimensional yields a total score that can be interpreted as a single quantity; a measure with several weakly correlated factors yields a total score that averages different things and may obscure clinically important variation. Many symptom inventories are best modelled as hierarchical, with a general distress factor and specific factors for depression, anxiety and somatic complaints. Interpreting the total score of such a measure as though it indexed a single disorder is a common error with practical consequences for treatment selection.

Factor analysis: uses and limits

Confirmatory factor analysis tests a specified model against observed covariance, and its fit indices are sensitive to sample size, model complexity and the distribution of items. A model that fits adequately in one sample may fail in another, and adequate fit does not establish that the model is the correct one — only that it is not incompatible with the data. Exploratory analysis, conversely, can generate a structure from noise if sample size, extraction method and rotation are chosen carelessly. The assessor reading a manual should look for replication across independent samples rather than a single well-fitting model.

Reliability at the factor level

Where a measure has subscales, reliability should be reported for each. A total score with excellent reliability can contain a subscale with reliability so low that its interpretation is unjustified. Reporting subscale means without subscale reliability is one of the more common defects of clinical reports, and it is particularly consequential when the subscale is the basis for a recommendation.

3.8 Norms, Percentiles and Standard Scores

A norm is a description of the distribution of scores in a defined reference sample. It converts a raw score into a statement about relative standing, and nothing more. The sample defines the comparison, and the comparison is only as meaningful as the sample's relevance to the person being assessed.

Score scales

Standard scores express a person's position relative to the reference sample in units of the sample's standard deviation. Table 3.2 summarises the common scales and their interpretation. Percentile ranks express the proportion of the reference sample scoring at or below the obtained score; they are intuitive but not interval-scaled, so differences between percentiles at the extremes correspond to larger differences in the underlying trait than the same differences near the middle.

Table 3.2. Common score scales and their interpretation

Scale	Mean	Standard deviation	Example and interpretation
z-score	0	1	−1.5: 1.5 SD below the reference mean
T-score	50	10	65: 1.5 SD above the mean, near the 93rd percentile
Deviation IQ / index score	100	15	85: 1 SD below the mean, near the 16th percentile
Scaled score	10	3	7: 1 SD below the mean, near the 16th percentile
Stanine	5	2	3: below average band, roughly the 11th–23rd percentile
Percentile rank	50	—	16: 16 per cent of the reference sample scored at or below this value

The normative sample

Manuals should report the size, recruitment method, date of data collection, stratification variables and exclusion criteria of the normative sample, together with the reliability of scores in that sample. Three questions follow. Does the sample represent the population to which the client belongs? Is it current enough that secular changes have not invalidated it? And is the sample large enough that the norm tables are stable at the extremes, where clinical decisions often fall?

Age, education and the Flynn effect

Normed scores decline in validity as the reference data age, a phenomenon associated with secular increases in measured ability across successive cohorts (Flynn, 1987). Instruments that are not renormed may therefore over-estimate ability in later cohorts. Age and education corrections improve comparability but can also mask genuine impairment in high-functioning individuals, particularly on cognitive measures where a client's demographic prediction may exceed their obtained score despite real decline. The assessor should know which norms were applied, and should record the basis for any demographic adjustment.

3.9 Sensitivity, Specificity and Predictive Values

Where a score is used to classify people — as above or below a threshold, as likely or unlikely to have a condition — the relevant psychometric properties are those of the classification, not those of the score's correlation with a criterion. The four indices are sensitivity (the proportion of people with the condition who are correctly identified), specificity (the proportion without the condition who are correctly identified), positive predictive value (the proportion of positive results that are true positives) and negative predictive value (the proportion of negative results that are true negatives).

Why predictive values matter more than sensitivity

Sensitivity and specificity are properties of the test; predictive values are properties of the test *in a setting*. As Figure 3.2 shows, for an instrument

with sensitivity and specificity of .90, the positive predictive value falls steeply as prevalence falls. At a prevalence of 2 per cent, fewer than one in six positive results is a true positive; at 30 per cent, more than three in four are. The same instrument, the same cut score and the same patient can therefore yield very different conclusions depending on where the assessment takes place.




Figure 3.2. Positive and negative predictive values for an instrument with sensitivity .90 and specificity .90, plotted against prevalence. The values are computed from Bayes' theorem; the instrument is held constant while the setting varies.

Likelihood ratios

Likelihood ratios summarise the evidential weight of a result in a form that can be combined with a pre-test probability. The positive likelihood ratio is sensitivity divided by one minus specificity; the negative likelihood ratio is one minus sensitivity divided by specificity. A positive likelihood ratio of 5 raises the odds of the condition fivefold; a negative likelihood ratio of 0.2 reduces them fivefold. Likelihood ratios have the practical advantage of being independent of prevalence, which makes them transportable across settings, and the practical disadvantage of requiring the assessor to estimate a pre-test probability from other information.

From detection to decision

The step from detection to decision requires attention to the consequences of each kind of error. Where a false negative is dangerous and a false posit-

ive is manageable, a lower threshold is appropriate; where a false positive triggers irreversible action, a higher threshold is required, together with converging evidence. Naming the asymmetry of consequences is part of the assessor's duty, because it is the part of threshold setting that no statistic can supply.

3.10 Cut Scores and Classification Accuracy

Cut scores are the operational expression of a decision rule. Their selection is a judgement about the relative costs of false positives and false negatives, informed by the distribution of scores in the relevant populations and by the purpose of the classification.

How cut scores are derived

Cut scores may be derived by criterion-keying (choosing the score that best separates groups defined by an external criterion), by receiver operating characteristic analysis (choosing the point that maximises the balance of sensitivity and specificity, or that satisfies a pre-specified constraint), or by normative convention (choosing a score at a fixed percentile). Each method embeds an assumption about what matters. Criterion-keying depends on the quality of the criterion; ROC analysis depends on the choice of the balance point; normative convention depends on the relevance of the norm group.

Banding and its uses

Because scores carry error, many instruments report interpretive bands rather than exact values. Banding reduces over-interpretation of small differences but can create false discontinuities at band boundaries, where a one-point difference places a client in a different descriptive category. Reporting the obtained score, its confidence interval and the band it falls within is more informative than reporting the band alone.

Classification accuracy in context

Classification accuracy statistics are conditional on the sample in which they were derived. A cut score validated in a sample with a mean score well above the clinical threshold will perform differently in a general population sample. Where local validation is impossible, the assessor should report the published accuracy statistics, the base rate in their own setting, and the resulting predictive values, and should state that the latter are estimates.

3.11 Fairness and Measurement Invariance

Fairness concerns the extent to which score interpretations are comparable across groups defined by characteristics irrelevant to the construct, such as sex, age, language, culture, disability or socioeconomic status. In psychometric terms, the central question is measurement invariance: whether the instrument measures the same construct in the same metric across groups.

Levels of invariance

Configural invariance requires that the same items load on the same factors in each group. Metric (weak) invariance requires that factor loadings be equal, which permits comparison of correlations and regression coefficients. Scalar (strong) invariance requires that item intercepts also be equal, which is necessary before comparing means. A measure may show configural but not scalar invariance in a given language, in which case group differences in total scores are ambiguous — they may reflect the construct, the response style, or the translation.

Differential item functioning

Differential item functioning occurs when two people of equal standing on the construct have different probabilities of endorsing a particular item because of group membership. It is detected by methods ranging from the Mantel–Haenszel procedure to item response theory based approaches, and its practical remedy is either item revision or interpretation of the scale with the affected items removed. The assessor consulting a manual should

look for evidence of invariance across the populations in which the measure will be used, not merely across the whole normative sample.

Translation and adaptation

Translating an instrument is not a matter of linguistic equivalence alone. The International Test Commission's guidelines require documented forward and backward translation, pilot testing, cognitive interviews and evidence of equivalence, together with attention to cultural appropriateness of item content. Where an instrument has been translated without such evidence, its scores should be interpreted with caution, and the limitation should be stated in the report. Chapter 14 extends this discussion to the broader question of culturally responsible assessment.

3.12 Evaluating Technical Manuals

The technical manual is the assessor's primary source for everything in this chapter. Reading it critically is a professional skill, and the criteria are reasonably straightforward once the questions are known.

A reading protocol

A defensible protocol asks the following. What is the construct, and how is it defined? What is the normative sample, when was it collected and how was it stratified? What reliability evidence is reported, for which samples and which score levels? What validity evidence is reported, and against which criteria? Is there evidence of measurement invariance across the groups to which the client belongs? What is the standard error, and how should it be used in reporting? What are the stated limits of interpretation, and what uses does the manual explicitly disclaim?

Common deficiencies

Common deficiencies include norming samples that are large but unrepresentative; reliabilities reported only for the total score; validity evidence confined to correlations with instruments measuring the same construct; absence of invariance evidence for the populations in which the test is mar-

keted; and cut scores presented without their derivation or their accuracy statistics. Reading for these gaps takes less time than reading the marketing material and is considerably more useful.

What the manual cannot tell you

Finally, the manual cannot tell the assessor whether the instrument is appropriate for the particular question, client and setting. That judgement requires clinical knowledge of the presentation, awareness of the service context and attention to the consequences of the decision. The manual constrains and informs that judgement; it does not replace it.

Advanced Case Conference

The referral. A rehabilitation service asks for assessment of a 47-year-old man four months after a moderate traumatic brain injury. The question is whether his reported memory difficulties reflect injury-related impairment or a depressive presentation, and what support he needs on returning to work.

The measures. Two memory measures are administered. The first has a mean of 100 and a standard deviation of 15, with an internal consistency of .93 and a standard error of measurement of 4.0; his score is 84. The second has a mean of 50 and a standard deviation of 10, with a test–retest reliability of .81 and a standard error of 5.6; his T-score is 38. A depression inventory yields a score in the moderately severe range, and a performance validity measure is within normal limits.

The reasoning. The two memory scores are consistent: both lie approximately one standard deviation below the mean, and their confidence intervals overlap substantially. Neither is low enough to suggest severe amnesia. The depression score is high, and the performance validity measure reduces, though does not eliminate, the likelihood that effort accounts for the memory findings. The critical question is whether the memory scores are lower than would be expected from his premorbid level, which requires demographic estimation rather than a comparison with the population mean; his education and occupational history suggest a premorbid level in the above-average range.

The decision. The report states that current memory performance is below estimated premorbid level and below the normative mean, but that the confidence intervals do not permit a precise estimate of the deficit. It records depression as a probable contributor and recommends treatment before a final determination of cognitive impairment. It recommends a phased return with written instructions and reduced memory load, reviewable in three months with repeat testing, and states explicitly that a second assessment will be more informative than the first for estimating change.

The teaching point. The psychometrics did not produce the conclusion; they constrained it. The overlapping confidence intervals prevented an overinterpretation of the difference between two memory scores, and the demographic comparison supplied the question that the norm-referenced comparison could not answer.

Chapter Summary

Reliability and validity are properties of scores and interpretations, not of instruments. Reliability coefficients are meaningful only in relation to the source of error they address, and the standard error of measurement translates a coefficient into a statement about a single client's score. Validity is an argument assembled from content, response process, internal structure, external relations and consequences, and the assessor should be able to identify its weakest link. Norms describe relative standing in a defined sample, and their relevance depends on the sample's correspondence to the client. Sensitivity and specificity describe tests, while predictive values describe tests in settings; the base rate governs the translation, and no instrument can escape it. Finally, fairness requires evidence of measurement invariance, without which group differences in scores cannot be interpreted.

Review Questions

1. Why is a reliability coefficient uninterpretable without knowing which source of error it addresses?

2. Compute the standard error of measurement for a test with a standard deviation of 15 and a reliability of .84, and construct a 95 per cent confidence interval around a score of 92.
3. Explain why the standard error of the difference is larger than the standard error of measurement.
4. Distinguish the five sources of validity evidence in the current professional standards.
5. Using Bayes' theorem, explain why a positive result on a highly specific test may still be more likely to be false than true.

Discussion Questions

1. A colleague reports that an instrument is "validated" because its manual reports a Cronbach's alpha of .94. What questions would you ask?
2. How should an assessor respond when the only available norms for an instrument were collected twenty years ago?
3. What evidence would persuade you that a translated instrument measures the same construct as the original?
4. Should subscale scores be reported when the manual gives no subscale reliability data? Argue both sides.
5. How would you explain a confidence interval to a client in a feedback session without oversimplifying it?

Further Reading

American Educational Research Association, American Psychological Association, & National Council on Measurement in Education. (2014). *Standards for educational and psychological testing*. American Educational Research Association.

Cronbach, L. J., & Meehl, P. E. (1955). Construct validity in psychological tests. *Psychological Bulletin, 52*(4), 281–302.

Dunn, T. J., Baguley, T., & Brunsden, V. (2014). From alpha to omega: A practical solution to the pervasive problem of internal consistency estimation. *British Journal of Psychology, 105*(3), 399–412.

Flynn, J. R. (1987). Massive IQ gains in 14 nations: What IQ tests really measure. *Psychological Bulletin, 101*(2), 171–191.

Kane, M. T. (2013). Validating the interpretations and uses of test scores. *Journal of Educational Measurement, 50*(1), 1–73.

Landis, J. R., & Koch, G. G. (1977). The measurement of observer agreement for categorical data. *Biometrics, 33*(1), 159–174.

McNeish, D. (2018). Thanks coefficient alpha, we'll take it from here. *Psychological Methods, 23*(3), 412–433.

Meredith, W. (1993). Measurement invariance, factor analysis and factorial invariance. *Psychometrika, 58*(4), 525–543.

Messick, S. (1995). Validity of psychological assessment: Validation of inferences from persons' responses and performances as scientific inquiry into score meaning. *American Psychologist, 50*(9), 741–749.

Sijtsma, K. (2009). On the use, the misuse, and the very limited usefulness of Cronbach's alpha. *Psychometrika, 74*(1), 107–120.

CHAPTER 4

Test Selection, Administration, Scoring and Interpretation

Learning Objectives

After working through this chapter, the reader should be able to:

- select instruments by reference to the referral question, the construct and the population;
- evaluate test quality, suitability and the qualifications required for competent use;
- prepare an assessment environment and session that protect the validity of results;
- administer standardised instruments and document any departure from standard procedure;
- apply scoring checks that catch the errors most likely to distort conclusions;
- recognise response styles and validity indicators without over-interpreting them;
- interpret profiles and score patterns conservatively and integrate them with other evidence.

Key terms: incremental validity · test–user qualification · standardised administration · accommodation · scoring reliability · response style · social desirability · validity scale · profile analysis · base-rate error · computer-based assessment

Introduction

Between the decision to assess and the interpretation of a score lies a sequence of practical choices that determine whether the score means any-

thing at all. Which instrument, administered by whom, under what conditions, scored how, checked against what? These questions are unglamorous and decisive. Most of the serious errors in score-based assessment originate here rather than in the sophistication of the interpretation: an instrument chosen because it was available, administered in an unsuitable room, scored with an outdated norm, and interpreted without attention to the client's response style.

This chapter treats these choices as a connected whole. Selection follows from the question and the population. Administration is a validity condition that can be protected or destroyed. Scoring is a quality-control process with known failure modes. Interpretation begins with what the score is designed to measure, proceeds through a consideration of response style and comparison data, and ends with an integration that draws on evidence outside the test. The chapter closes with the two areas where practice has changed most rapidly: technology-assisted assessment and the recurring errors that experienced assessors make as often as novices. Figure 4.1 places selection, administration and scoring within a single cycle, each stage of which can protect or undermine the interpretation that follows.




Figure 4.1. The test-use cycle. Selection, administration and scoring each protect or threaten the validity of the interpretation that follows.

4.1 Matching Measures to Referral Questions

Instrument selection is a matching problem: the properties of the measure must correspond to the requirements of the question, the characteristics of the client and the constraints of the setting. When the match is poor, no amount of interpretive skill will recover the assessment.

Specifying the requirement

The first step is to state, in operational terms, what the instrument must deliver. A question about diagnostic status requires a measure with criterion-referenced accuracy data in a comparable population. A question about severity and change requires a measure with demonstrated sensitivity to change and a reliable change index. A question about functional capacity requires a measure of everyday performance rather than symptom report. A question about personality structure requires a measure with evidence on the relevant dimensional or categorical model. Writing the requirement down before consulting catalogues prevents the common pattern in which the available instrument defines the question.

Breadth, depth and sequence

Where several constructs are relevant, the assessor decides the order of enquiry. A common and defensible sequence is broad screening followed by focused measurement: a general symptom inventory to identify elevations, then specific instruments to characterise the domains that matter for the decision. The sequence saves time and reduces the number of instruments administered to every client, but it must be planned so that the screening stage does not determine which hypotheses are entertained. Screening that is used as a hypothesis-generating device is efficient; screening used as a conclusion is not.

Incremental validity and redundancy

Before adding an instrument, the assessor should ask what it will add to what is already known. Two instruments that measure the same construct with similar method variance usually add little; an instrument that meas-

ures a different construct, or the same construct by a different method, often adds a great deal. Redundancy is not always a defect — corroboration has value where the decision is consequential and the constructs are difficult to measure — but it should be a deliberate choice recorded in the rationale.

4.2 Evaluating Test Quality and Suitability

Having identified candidate instruments, the assessor evaluates them against a consistent set of criteria. The criteria are technical, practical and ethical at once, and Table 4.1 sets them out with the question each is designed to answer. Table 4.1 sets out the criteria used in this chapter to evaluate a candidate instrument.

Table 4.1. Criteria for evaluating a candidate instrument

Criterion	Question to answer	Evidence required
Construct definition	**Is the construct clearly defined and does it match the referral question?**	**Manual, theoretical literature**
Normative adequacy	**Does the reference sample represent this client, and is it current?**	**Norming chapter; publication date; stratification**
Reliability	**Are scores sufficiently precise for individual decisions?**	**Internal consistency, test–retest, inter-rater data**
Validity	**Is there evidence for the intended interpretation and use?**	**Content, structure, external relations, consequences**
Fairness	**Is there evidence of invariance for this client's group?**	**Invariance and differential item functioning studies**
Sensitivity to change	**Can the measure detect the change the decision concerns?**	**Longitudinal studies; reliable change index**
Practicality	**Is administration feasible in this setting and with this client?**	**Time, format, literacy, sensory and motor demands**
Qualification	**Does the assessor hold the training the publisher requires?**	**Test-user classification; supervisory arrangements**
Cost and access	Are materials and scoring affordable and available?	Budget; licensing terms

Evidence beyond the manual

Independent evidence matters, because manuals are published by test developers and are not required to report unfavourable findings. Systematic reviews, independent validation studies and post-publication critiques may reveal limitations that the manual passes over. Where independent evidence is sparse, the assessor should record that fact and calibrate confidence accordingly, rather than treating the manual as a neutral summary of the literature.

Suitability for the individual client

Suitability is a judgement about this person, not about the population. Reading level, visual and hearing acuity, motor control, stamina, language, cultural familiarity with test content and current distress all affect whether the instrument can be administered as designed. Where suitability is marginal, the assessor has three options: choose a different instrument, adapt the administration and document the adaptation as a threat to standardisation, or proceed and interpret with explicit caution. Choosing the third option silently is the error to avoid.

4.3 Qualifications and Scope of Practice

Test publishers classify instruments by the training required for competent use, and professional bodies treat use outside one's competence as an ethical violation regardless of what the publisher permits. The classifications are a floor, not a ceiling: possessing the credential to purchase an instrument does not establish competence to interpret it in a particular context.

Reading the qualification framework

Most frameworks distinguish instruments that require no special qualification, those requiring a professional qualification in psychology or a related field, and those restricted to practitioners with specific training in the instrument and its interpretation. Within the third category, the relevant

questions are whether the practitioner has completed the publisher's training, whether they have supervised experience with the population in question, and whether they maintain competence through continuing professional development and, where relevant, recalibration of scoring judgements.

Boundaries around specialist measures

Certain domains carry boundary requirements that a general doctoral qualification does not satisfy: neuropsychological assessment in medico-legal contexts, forensic risk assessment, assessment for court on parenting capacity, and assessment of capacity to make specific decisions under mental health or capacity legislation. In each case the assessor must know the statutory framework, the reporting conventions and the standards of the relevant specialty. Where the referral requires expertise the assessor does not hold, the correct response is to say so and to contribute what is within competence.

Supervision and delegation

Doctoral trainees administer instruments under supervision, and the supervisor carries responsibility for the interpretation even where the trainee conducted the session. Good supervisory practice includes review of the raw data, independent scoring of a sample of protocols, and discussion of the reasoning that connects scores to conclusions. Where psychometricians or technicians administer tests, the interpreting psychologist remains responsible for selecting the instrument, specifying the conditions of administration, and interpreting the results.

4.4 Preparing the Assessment Environment

The assessment environment is part of the measurement procedure. Noise, interruption, temperature, seating, lighting and the presence of observers all affect performance, and their effects are largest for tasks requiring sustained attention and for clients who are anxious or fatigued.

Physical and interpersonal conditions

A quiet room with a table of appropriate height, seating that allows the assessor to observe without hovering, and freedom from interruption are baseline requirements. The assessor should arrange the room so that test materials are not visible before administration and so that the client cannot see scoring sheets. Where observation by a third party is required — a trainee, an interpreter, a family member — the effect on performance should be considered and, where relevant, measured, since the presence of an observer reliably changes performance on some tasks.

Scheduling and fatigue

Cognitive assessment should be scheduled when the client is likely to be at their best, which for many people is the morning, and should avoid periods immediately after night shifts, during acute pain or in the post-ictal period. Sessions longer than ninety minutes without a break produce fatigue effects that are indistinguishable from impairment. Where a battery requires more time than a single session allows, splitting it across sessions is preferable to compressing it, and the split should be documented.

Preparing the client

Preparation includes explaining what will happen, how long it will take, what the client should do if they need a break, and what will be done with the results. Clients should be told that some tasks will be difficult and that difficulty is expected. They should also be told, in specific terms, what will happen if they decline a task: in most instruments partial administration invalidates the score, and the client has a right to know this before deciding.

4.5 Standardised Administration

Standardisation is the feature that makes norms applicable. The normative sample was tested under specified conditions, and departures from those conditions mean that the comparison is no longer exact. Standardised administration is therefore not bureaucratic rigidity but the condition under which a score can be compared with a norm.

What standardisation requires

It requires fidelity to the manual's instructions on wording, order, timing, materials, prompting, recording and discontinuation rules. It requires that the assessor knows the instructions well enough not to read them mechanically while attending to something else. And it requires that any departure be recorded at the time, with its reason, rather than reconstructed from memory afterwards.

Common departures and their effects

The common departures are familiar: rephrasing a question to be helpful, giving extra time on a timed task, allowing a second attempt, prompting an answer, or continuing past a discontinue rule because the client seems to be improving. Each may be clinically kind and psychometrically costly. A client who is helped to a correct answer has produced a score that reflects the help as well as the ability, and the norm no longer applies. Where an adaptation is clinically necessary, the appropriate response is to record it, to state its likely direction of effect, and to interpret the score qualitatively rather than normatively.

Recording during administration

Contemporary practice records responses verbatim where the instrument requires it, notes latencies and prompts, and records behavioural observations that bear on validity: effort, frustration, guessing, off-task behaviour, and signs of sensory or motor difficulty. These observations often explain discrepancies that would otherwise appear as profile anomalies. Digital recording, where consented to, improves accuracy and supports supervision.

4.6 Accommodations and Accessibility

An accommodation is a change to the standard procedure intended to remove a barrier unrelated to the construct being measured. The distinction between accommodation and modification matters: an accommodation preserves the construct, whereas a modification changes it. Giving a large-print version of a reading passage to a client with low vision is an accom-

modation; reading the passage aloud when the construct is reading comprehension is a modification.

Principles

Four principles govern accommodations. They should address a documented functional limitation rather than a diagnosis. They should preserve the construct, or the change should be declared and interpreted. They should be applied consistently across the assessment so that comparisons between scores remain meaningful. And they should be documented in enough detail that a reader could reproduce the conditions.

Common accommodations

Common accommodations include extended time, separate room, rest breaks, large print, screen magnification, sign language interpretation for instructions, written rather than verbal instructions, and alternative response formats such as pointing or dictation. Each has an evidence base of variable quality for the specific instrument, and the assessor should know whether the accommodation has been shown to preserve score meaning for that instrument, or is being applied on general principle.

Documentation and interpretation

Where an accommodation has been applied, the report should state what was changed, why, and how the score should be interpreted as a result. Where no validated norms exist for the accommodated administration, the score should be reported as descriptive rather than norm-referenced, and the assessor should say so. This is more honest than either refusing the accommodation or presenting an accommodated score as though it were standard.

4.7 Scoring and Quality Control

Scoring errors are common, avoidable and consequential. Studies of hand-scored protocols have repeatedly found non-trivial error rates, and the er-

rors are not random: they cluster where rules are complex, where reversals are required, and where the scorer is tired.

A scoring protocol

A defensible protocol has four elements. Score from the record, not from memory, and record raw responses before applying rules. Apply the manual's rules exactly, including item-level reversal, basal and ceiling rules, and prorating rules where permitted. Score blind to the hypothesis where possible, or have a second person score a sample blind to the expected result. Recompute totals independently, either by hand or with a second entry into the scoring software, and compare.

Checking the output

Automated scoring reduces arithmetic error but introduces its own failures: wrong normative option selected, wrong age entered, wrong test form, wrong scoring key, or software version mismatch. The assessor should verify that the demographic data entered match the client, that the correct norms were applied, and that the output is internally consistent — that subscale scores sum to totals, that percentile and standard scores correspond, and that the reported score falls within the possible range. A short checklist applied to every protocol prevents most errors.

Reporting scores

Reports should give the instrument, the form, the date of administration, the norm group used, the obtained score with its confidence interval and percentile, and a plain-language description of what the score indicates. Where a score is described qualitatively, the descriptor should be tied to a stated range rather than to a general impression: "a score in the low-average range, between the 9th and 24th percentiles" is verifiable; "borderline functioning" is not.

4.8 Response Styles and Validity Indicators

Not every protocol is interpretable. Respondents may under-report symptoms to appear competent, over-report to obtain help or compensation, answer randomly, agree with everything, or misunderstand the task. Instruments with validity scales, and performance validity tests in cognitive assessment, exist to detect these patterns, and their interpretation requires as much care as the interpretation of clinical scales.

The main response styles

Social desirability describes the tendency to present oneself favourably; it is not deception, and it is often adaptive. Malingering describes the intentional production of false or exaggerated symptoms for an external incentive; it is a clinical and legal judgement, not a test result. Over-reporting may also reflect genuine distress, help-seeking, or a personality style characterised by dramatic presentation. Random and acquiescent responding are detectable by inconsistency and infrequency indices.

Interpreting validity indicators

Validity indicators are probabilistic. A single elevated validity scale raises a hypothesis; a pattern of elevations across independent indicators, combined with inconsistent performance on cognitive tasks, raises it further. No indicator establishes malingering, and a normal profile does not exclude exaggeration. The assessor should avoid the two symmetrical errors: dismissing every elevation as "just distress", and treating an elevation as proof of deception.

What follows from an invalid protocol

Where validity is seriously compromised, the appropriate response is to report the finding, describe its probable effect on the scores, and avoid drawing conclusions from the affected data. Where a performance validity test is failed, the interpretation of cognitive scores should be suspended rather than adjusted. In forensic contexts, the finding itself may be material, and the assessor should be familiar with the relevant standards of evidence.

4.9 Interpreting Profiles and Score Patterns

Profile interpretation — the comparison of scores within a battery — is where psychometric discipline most often gives way to narrative invention. Differences between scores are interpreted as evidence of specific strengths and weaknesses, when many such differences are within the range that measurement error and normal variability would produce.

The base-rate problem in profile analysis

The central problem is that patterns are common in the normal population. A two-point elevation on one subscale, a difference of ten points between two indices, or a combination of three moderate scores may occur in a substantial minority of people without any clinical condition. Before interpreting a pattern, the assessor should know its base rate in the relevant population. Where that is unknown, the pattern should be described as an observation rather than interpreted as a finding.

Reliable differences and clinically meaningful differences

A difference must first be reliable (larger than the standard error of the difference) before it can be clinically meaningful. Reliability is necessary but not sufficient: a reliable difference may have no functional consequence. The assessor should ask whether the difference corresponds to something observable in the client's life — a task they avoid, a setting in which they struggle, a report from an informant. Differences that cannot be connected to functioning are usually noise with a narrative attached.

Integrating across instruments

Scores from different instruments should be compared only when the constructs correspond. A high score on a depression inventory and a moderate elevation on a personality scale measuring negative affectivity may reflect the same underlying variance rather than two separate findings. Integration requires a model of what the instruments share, and the assessor should be explicit about which findings are independent and which are likely to be redundant.

4.10 Combining Tests with Other Evidence

Test scores acquire meaning in combination with interview, observation, collateral report and records. The combination is not an average but an argument: each source contributes different information, and the assessor's task is to explain how they fit, where they conflict and which source carries more weight for the specific conclusion.

Convergence, divergence and priority

Where sources converge, confidence rises, provided the sources are genuinely independent. Where they diverge, the assessor investigates rather than averages, and the investigation usually turns on the conditions under which each source was produced: a self-report completed at home during a crisis, an informant report from a relative who sees the client weekly, a test administered after a night without sleep. Specifying those conditions often resolves the discrepancy without any need to prefer one source.

Weighting evidence

Weighting depends on the question. For a question about current symptom severity, a standardised self-report administered recently may carry more weight than an informant's impression formed over months. For a question about lifelong functioning, informant report and records may carry more weight than a self-report completed in an acute state. For a question about capacity to perform a specific task, direct observation of the task is usually the best evidence available.

Presenting integration in a report

Integrated reporting does not place test results in one section and interview findings in another. It organises the report around the questions the assessment was asked to answer, and within each section presents the evidence from all sources that bears on the question. This structure is harder to write and far more useful to the reader, and it makes contradictions visible rather than hiding them in separate sections.

4.11 Technology-Assisted Assessment

Digital administration, online questionnaires, computer-adaptive testing, ecological momentary assessment and automated scoring are now routine. Each offers advantages and introduces failure modes that the assessor must anticipate.

Advantages and risks

Digital administration improves standardisation of timing and presentation, reduces scoring error, enables remote access for clients who cannot attend, and supports repeated measurement. The risks include uncontrolled environments, device variability, connectivity failure, item exposure, and the temptation to administer instruments outside their validated mode. A measure validated in paper format and administered online is not automatically equivalent, and equivalence should be established rather than assumed.

Remote assessment

Remote assessment requires attention to the environment the client is in, the reliability of the connection, the client's familiarity with the technology, and the security of the platform. Cognitive tests that depend on precise timing are particularly vulnerable. Where remote administration is necessary, the assessor should record the conditions and interpret accordingly, and should avoid comparing remote scores with in-person norms unless equivalence has been demonstrated.

Automated interpretation

Automated interpretive reports produce narrative text from score patterns. They are useful as checklists and dangerous as conclusions, because they cannot know the client, the setting or the question, and because their base-rate assumptions are opaque. An assessor who copies an interpretive paragraph into a report without verifying that each claim is supported by the data, and applicable to this client, has transferred responsibility to software.

The professional obligation to justify conclusions cannot be delegated in this way.

4.12 Avoiding Common Interpretation Errors

The recurring errors in test interpretation are well documented and largely preventable. They are not signs of inexperience; several become more likely with confidence.

The principal errors

Confirmatory interpretation: selecting the scores that support the initial hypothesis and discounting those that do not. Base-rate neglect: interpreting a pattern without knowing how common it is. Over-interpretation of small differences: treating scores within the standard error of the difference as meaningful. Reification: treating a label such as "executive dysfunction" as an explanation rather than a description. Context neglect: interpreting a score without reference to the conditions of administration, the client's state, or the demands of their environment. And premature closure: ceasing to gather evidence once a coherent story has formed.

Corrective practices

The correctives are procedural. State the hypothesis before examining the scores and state what would disconfirm it. Compute and report confidence intervals. Consult base-rate tables where available. Write the limitations section before the conclusions section, so that the conclusions must accommodate them. Submit high-stakes conclusions to a colleague for independent review. Keep a record of assessments in which the eventual outcome contradicted the initial interpretation; this is the most effective calibration available to a practitioner.

A discipline of humility

Finally, interpretation should be conducted with explicit awareness of what the instrument cannot show. A test can establish that a person's performance is below that of a reference group; it cannot, by itself, establish why,

whether the difference matters in their life, or what should be done. Those conclusions require the clinical, contextual and ethical reasoning that the rest of this book describes.

Advanced Case Conference

The referral. A university counselling service asks for assessment of a 21-year-old undergraduate who has failed two consecutive years and reports difficulty concentrating. The question is whether a specific learning difficulty is present and whether examination accommodations are warranted.

The assessment. A cognitive battery yields a full-scale score in the average range, with a relative weakness in working memory and processing speed. An achievement battery shows reading accuracy and comprehension in the average range and mathematics in the low-average range. A self-report attention measure is elevated. Performance validity testing is within normal limits. The client reports sleeping five hours a night, working thirty hours a week in addition to study, and describes severe anxiety before examinations.

The reasoning. The profile is common in the general population: a difference between working memory and verbal comprehension of this size occurs frequently and does not by itself indicate a disorder. The achievement scores are consistent with the client's educational history and do not show the discrepancy between ability and attainment that a specific learning difficulty would require. The elevated attention self-report is confounded by sleep restriction and anxiety, and self-report attention measures are known to correlate strongly with distress. The assessment was also conducted during the week before an examination period.

The decision. The report declines to diagnose a specific learning difficulty, explains why the evidence does not support it, and identifies sleep restriction, workload and examination anxiety as the more probable contributors. It recommends a sleep and workload intervention, treatment for anxiety, and a re-assessment after a term if difficulties persist. On accommodations, it recommends limited, function-based provisions — a separate room and rest breaks — while stating that extended time is not supported by the evidence obtained, and that the recommendation may be revisited after reassessment.

The teaching point. The most useful part of the report was the explanation of what the assessment could not establish. A report that had diagnosed a learning difficulty on the basis of an elevated self-report and a common profile would have been plausible, contestable and wrong.

Chapter Summary

Selection, administration, scoring and interpretation form a chain in which each link constrains the meaning of the next. Instruments should be chosen for the question and the population, evaluated against technical and practical criteria, and used only within the assessor's competence. Standardisation is the condition under which norms apply; departures must be documented and their effects stated. Scoring requires independent checks, and automated scoring requires verification rather than trust. Response styles must be considered before clinical scales are interpreted, and validity indicators are probabilistic rather than probative. Profile interpretation should be constrained by base rates and by the standard error of the difference, and integration across sources is an argument rather than an average. Technology changes the mechanics of assessment without changing the professional obligation to justify conclusions in terms of evidence about this client.

Review Questions

1. How does the referral question constrain instrument selection? Illustrate with two contrasting questions.
2. Distinguish an accommodation from a modification and explain why the distinction matters for score interpretation.
3. Describe a scoring quality-control protocol that would catch the three most common scoring errors.
4. Why is a pattern of subtest elevations insufficient on its own to support an interpretation?
5. What are the professional risks of using an automated interpretive report without verification?

Discussion Questions

1. A publisher's classification permits you to purchase an instrument, but you have no supervised experience with the population. What do you do?
2. How should an assessor respond when a client declines a task that is required for a valid total score?
3. Is it ever appropriate to compare scores obtained under different administrative conditions? Under what safeguards?
4. Discuss the ethics of remote cognitive assessment in a rural service with limited alternatives.
5. What would a genuinely independent review of your last ten assessments reveal about your interpretive habits?

Further Reading

American Educational Research Association, American Psychological Association, & National Council on Measurement in Education. (2014). *Standards for educational and psychological testing*. American Educational Research Association.

Grove, W. M., Zald, D. H., Lebow, B. S., Snitz, B. E., & Nelson, C. (2000). Clinical versus mechanical prediction: A meta-analysis. *Psychological Assessment, 12*(1), 19–30.

Kane, M. T. (2013). Validating the interpretations and uses of test scores. *Journal of Educational Measurement, 50*(1), 1–73.

Meyer, G. J., Finn, S. E., Eyde, L. D., Kay, G. G., Moreland, K. L., Dies, R. R., Eisman, E. J., Kubiszyn, T. W., & Reed, G. M. (2001). Psychological testing and psychological assessment: A review of evidence and issues. *American Psychologist, 56*(2), 128–165.

Sweet, J. J., Heilbronner, R. L., Morgan, J. E., Larrabee, G. J., Rohling, M. L., Boone, K. B., Kirkwood, M. W., Schroeder, R. W., & Suhr, J. A. (2021). American Academy of Clinical Neuropsychology (AACN) 2021 consensus statement on validity assessment. *Archives of Clinical Neuropsychology, 36*(5), 623–647.

PART II

Assessing Dispositions and Abilities

Personality and interpersonal functioning, cognitive and neuropsychological ability, and achievement, aptitude and career assessment.

Chapter 5 · Chapter 6 · Chapter 7

CHAPTER 5

Personality Assessment and Interpersonal Functioning

Learning Objectives

After working through this chapter, the reader should be able to:

- explain the purposes that personality assessment serves in counselling psychology;
- compare trait, dimensional and categorical models of personality and their clinical implications;
- select broad-band and narrow-band inventories for specific referral questions;
- assess interpersonal and attachment functioning using multiple methods;
- evaluate response styles and impression management in self-report personality data;
- appraise the evidence for performance-based approaches and their appropriate use;
- communicate personality findings without reification or stigma.

Key terms: trait model · five-factor model · person–environment fit · broad-band inventory · narrow-band measure · interpersonal circumplex · attachment style · impression management · validity scale · personality functioning · level of personality functioning · reification

Introduction

Personality assessment asks a different kind of question from symptom assessment. Symptoms describe what is happening now; personality describes the relatively stable organisation of dispositions, motives, strategies and re-

lational patterns that shape how a person responds across situations and over time. Because that organisation is inferred rather than observed directly, personality assessment depends more heavily on multiple methods and on cautious inference than any other area covered in this book.

The clinical value of the enterprise is considerable. Personality information improves prediction of treatment response and alliance, illuminates the interpersonal cycles that maintain distress, guides the choice between supportive and interpretive approaches, and provides the client with a description of enduring patterns that is often experienced as more respectful than a diagnostic label. The risks are equally considerable: personality language lends itself to reification, to moral judgement disguised as description, and to conclusions that follow the client for years. This chapter develops both the technical and the ethical dimensions of the work. Figure 5.1 shows how model, method and context combine in personality assessment, so that no single instrument carries the construct on its own.




Figure 5.1. Personality assessment integrates model, method and context. No single instrument supplies the construct; the assessor must construct it.

5.1 Purposes of Personality Assessment

Personality assessment is commissioned for several distinct purposes, and the purpose determines the method, the depth and the appropriate form of

reporting. Confusing the purposes produces reports that answer a question nobody asked.

Differential diagnosis and formulation

In diagnostic assessment, personality measures help to distinguish enduring patterns from current states, to identify traits that predispose to particular presentations, and to characterise the personality context in which a symptom disorder occurs. For formulation, the relevant question is usually functional: which enduring strategies maintain the presenting problem, and what would a treatment that addresses them look like?

Treatment planning and prediction

Personality data inform treatment planning in several ways. They predict alliance and dropout risk, identify the interpersonal behaviours likely to be enacted with the therapist, suggest the level of interpretive work the client can tolerate, and indicate the likely response to structured versus exploratory modalities. These predictions are probabilistic and should be stated as such; the evidence for personality-based treatment matching is stronger for some dimensions — such as trait conscientiousness and adherence, or interpersonal hostility and alliance rupture — than for others.

Selection, fitness and legal questions

Personality assessment is also used in employment selection, fitness-for-duty evaluations, custody proceedings and forensic determinations. These applications raise the stakes and change the requirements: the assessor must be familiar with the relevant legal standards, must use instruments with evidence of validity for the specific purpose, must evaluate response style rigorously, and must be able to withstand cross-examination. Instruments validated for clinical description are not thereby validated for forensic prediction, and the distinction should be recorded in the report.

5.2 Trait and Dimensional Models

The dominant framework for describing individual differences is the trait model, in which people are positioned on continuous dimensions along which they differ in degree rather than in kind. The five-factor model, comprising neuroticism, extraversion, openness to experience, agreeableness and conscientiousness, has accumulated substantial cross-cultural and longitudinal support and provides the reference structure for most contemporary inventories.

Strengths of the trait approach

Traits are measurable with high reliability, stable over years in adulthood, heritable to a moderate degree, and predictive of important outcomes including occupational performance, relationship stability and mental health. The five-factor structure has been recovered in many languages and cultures, though the adequacy of the model in every cultural setting remains an empirical question rather than a settled fact. For the assessor, the trait model's principal virtue is that it describes without explaining away: it can say that a client is high in neuroticism and low in agreeableness without implying pathology.

Limits of the trait approach

Traits describe average tendencies, not behaviour in a specific situation. A person high in conscientiousness may be punctilious at work and chaotic at home, and the trait score will not reveal which. Traits also say little about the organisation of personality — how conflict is managed, what happens under stress, how the person experiences themselves and others — which is precisely the information that psychodynamic and interpersonal traditions supply. Finally, extreme trait scores are not diagnoses: high neuroticism is a risk factor, not a disorder.

Hybrid and severity models

Contemporary models attempt to combine trait description with a measure of severity or impairment. The alternative model for personality dis-

orders in DSM-5-TR specifies both a level of personality functioning, rated on dimensions of self and interpersonal functioning, and a set of maladaptive trait domains; ICD-11 characterises personality disorder primarily by severity with optional trait qualifiers (American Psychiatric Association, 2022; World Health Organization, 2024). Both approaches reflect the evidence that traits alone do not distinguish disorder from variation, and that severity of impairment carries most of the clinical information.

5.3 Broad-Band Personality Inventories

Broad-band inventories assess multiple domains within a single administration. They are the workhorses of clinical personality assessment and the instruments most likely to be encountered in doctoral training.

The Minnesota Multiphasic Personality Inventory

The MMPI family, most recently the MMPI-3 and the MMPI-2-RF, combines clinical scales with extensive validity scales and has an unusually large research base (Ben-Porath & Tellegen, 2008). Its strengths are empirical scale construction, sophisticated validity indices and strong normative data. Its limitations include length, reading level, the interpretive complexity of its higher-order structure, and a normative sample that, while large, is specific to the United States. The instrument is best used as a hypothesis-generating device: its scales identify domains in which further enquiry is warranted, and its validity scales inform the interpretation of everything else.

The Personality Assessment Inventory

The Personality Assessment Inventory (PAI; Morey, 2007) was constructed with a coherent theoretical model, uses a four-point response format, and includes validity scales, clinical scales and treatment consideration scales. Its treatment scales are particularly useful in counselling psychology, since they address treatment rejection, aggression, suicidal ideation and stress. Its reading level is lower than the MMPI's, which extends its applicability, though not to clients with significant literacy limitations.

Five-factor inventories

The NEO Personality Inventory-3 (McCrae, Costa, & Martin, 2005) and comparable five-factor instruments provide a normal-range description of personality with excellent psychometric properties. They are often the most useful instruments for counselling psychology, because they describe the person rather than the pathology, and because their facet-level scores connect to specific behaviours. Their limitation is that they were not designed to detect disorder, and their clinical utility depends on the assessor's ability to translate trait descriptions into functional implications. Table 5.1 summarises representative personality instruments and the principal use of each.

Table 5.1. Representative personality instruments and their principal uses

Instrument	Model and structure	Principal use	Key caution
MMPI-3 / MMPI-2-RF	Empirical, hierarchical; validity and clinical scales	Broad clinical description; response style detection	Length; interpretive complexity; US norms
Personality Assessment Inventory	Theoretical; validity, clinical, treatment scales	Clinical description with treatment focus	Requires clinical integration; limited cross-cultural evidence
NEO-PI-3	Five-factor; facets	Normal-range description; formulation	Not designed to detect disorder
PID-5	DSM-5-TR maladaptive trait domains and facets	Dimensional personality disorder assessment	Trait description without severity
SCID-5-AMPD	Level of functioning plus traits	Hybrid personality disorder diagnosis	Interviewer training and time
Interpersonal circumplex measures	Circumplex; dominance and affiliation	Relational patterns and interpersonal problems	Circumplex assumptions; limited coverage of intrapsychic processes

5.4 Narrow-Band Measures

Narrow-band measures assess a single construct or a small cluster of related constructs in depth. They are useful where the broad-band profile has raised a specific question, and they are often better validated for that specific question than the broad instrument that generated it.

Selecting a narrow-band measure

Selection follows the same criteria as any other instrument: construct definition, normative adequacy, reliability at the score level used, validity for the intended interpretation and evidence of fairness for the client's group. The additional consideration is specificity: a measure of "perfectionism" should have evidence that it distinguishes perfectionism from conscientiousness and from obsessive-compulsive symptoms, or the assessor will be measuring general distress under a more specific name.

Examples and their uses

Common narrow-band measures in counselling psychology include measures of defence style, emotion regulation, anger, shame, self-esteem, dependency and self-criticism, alexithymia, and interpersonal problems. Each has a research literature connecting it to treatment process; the assessor should know that literature before using the instrument to make a treatment recommendation. A measure of defence style, for example, is most useful when the assessor can say what a particular defence implies for the therapeutic relationship, not merely that the client scores high on it.

Combining narrow- and broad-band data

The combination is most informative when the narrow-band finding contradicts or qualifies the broad-band profile. A client with a modest elevation on a broad depression scale but an extreme score on a narrow measure of self-criticism may be presenting a picture that the broad instrument smooths over. Discrepancies of this kind are the most productive starting points for formulation.

5.5 Interpersonal and Attachment Assessment

Personality is expressed in relationships, and the assessment of interpersonal functioning is often more clinically useful than the assessment of traits. Two traditions dominate: the interpersonal circumplex, which describes behaviour along dimensions of dominance and affiliation, and attachment theory, which describes expectations about the availability and responsiveness of others.

The interpersonal circumplex

Circumplex measures position a person's characteristic interpersonal behaviour on a circle defined by dominance (agency) and affiliation (communion). The resulting profile describes, for example, a person who is warm and submissive, or cold and dominant, and it identifies the interpersonal problems that accompany each position — being too controlling, too distant, too self-sacrificing or too vindictive. The model's clinical value lies in its account of complementarity: dominant behaviour invites submission, and hostile behaviour invites hostility, which is how interpersonal patterns become self-maintaining.

Attachment assessment

Attachment is assessed by interview, by self-report questionnaire and by observation of interaction. The Adult Attachment Interview (George, Kaplan, & Main, 1985) classifies attachment states of mind from the coherence of narrative about early relationships; self-report measures such as the Experiences in Close Relationships questionnaire (Brennan, Clark, & Shaver, 1998) assess attachment anxiety and avoidance. The two traditions measure different things — one, the organisation of discourse about attachment; the other, self-reported orientation in close relationships — and they do not always agree. The assessor should know which is being measured and should not treat one as a proxy for the other.

Clinical use

Interpersonal and attachment data are most useful when they are translated into predictions about the therapeutic relationship and into hypotheses about recurrent relational patterns. "The client describes intense worry about abandonment and responds to perceived criticism with withdrawal; in the assessment sessions this appeared as silence following a clarifying question" is a formulation that can be worked with. A circumplex coordinate alone is not.

5.6 Response Style and Impression Management

Self-report personality data are always affected by the respondent's approach to the task. In clinical settings, the two most consequential styles are under-reporting, often driven by social desirability, and over-reporting, which may reflect genuine distress, help-seeking, or deliberate exaggeration.

Social desirability and defensiveness

Social desirability is normally distributed in the population and is not in itself pathological. At moderate levels it improves the accuracy of some predictions, since people who present themselves favourably also tend to behave favourably. At extreme levels it invalidates self-report, because the respondent is answering a question about who they would like to be. The assessor's response is to seek corroboration and to interpret the profile as a description of the client's self-presentation rather than of the client.

Over-reporting and its interpretations

Elevated scores on over-reporting indices may indicate deliberate exaggeration, a cry for help, a personality style characterised by dramatic expression, or simply severe distress in a person with limited vocabulary for it. Distinguishing among these requires collateral information, consistency across measures, and attention to the pattern of elevations. The assessor should resist both the naïve reading (the client is exaggerating) and the defensive reading (the client is distressed), and should record the evidence for whichever interpretation the data support.

Interview-based response style

Response style also operates in interviews. Clients present differently to different interviewers, emphasise different aspects of their history depending on what they believe the interviewer wants, and adjust their accounts in the light of the interviewer's reactions. Structured interviews reduce but do not eliminate this. The interviewer's protection is the same as elsewhere: multiple sources, recorded observations, and explicit attention to discrepancies.

5.7 Performance-Based and Projective Approaches

Performance-based measures present ambiguous stimuli and score the responses according to a standardised system. They have a long history in clinical psychology, a contested evidence base, and a continuing role in assessment, particularly where the assessor needs information about implicit processes or where self-report is compromised.

Evidence

The evidence for performance-based measures is uneven and depends on the specific variable being scored. Mihura, Meyer, Dumitrascu and Bombel (2013) conducted systematic reviews and meta-analyses of Comprehensive System Rorschach variables and found that some variables have good validity while others do not; the valid variables tend to concern perceptual accuracy and thought disturbance rather than the broad personality inferences for which the instrument is best known. This finding supports the use of specific Rorschach indices for specific purposes, and it does not support the interpretive traditions that read personality from response content.

Appropriate use

Performance-based measures are most defensible when used to answer a specific question for which a specific variable has demonstrated validity, as one source among several, by an assessor trained in the scoring system and aware of its limits. They are least defensible when used as a general person-

ality description, when scored impressionistically, or when their output is granted more authority than the self-report data it contradicts.

Narrative and collaborative uses

Thematic apperceptive methods retain a place in assessment for eliciting the client's narrative themes, conflicts and representations of relationships, particularly in therapeutic assessment models. Their use in this mode is idiographic: the assessor is not scoring against norms but listening for themes that can be discussed with the client. This is a legitimate clinical activity, provided it is not presented as a standardised finding.

5.8 Personality Functioning and Severity

The most important development in personality assessment over the past two decades is the separation of personality variation from personality disorder by introducing a dimension of severity. Severity describes how far a person's personality organisation impairs their capacity to function in the domains of self and relationships; it is what distinguishes a person with difficult traits from a person with a personality disorder.

Domains of personality functioning

The DSM-5-TR alternative model specifies two broad domains, self and interpersonal, each with two elements. Self functioning comprises identity (the experience of a coherent sense of self and the capacity to regulate self-esteem) and self-direction (the capacity to pursue meaningful goals). Interpersonal functioning comprises empathy (the capacity to understand and appreciate others' experience) and intimacy (the capacity for enduring, mutually satisfying close relationships). ICD-11 uses a similar structure, grading severity from mild personality difficulty through moderate disorder to severe disorder.

Assessing severity

Severity is assessed by interview, by informant report and by observation of the client's functioning over time. Useful indicators include the stability of

the client's self-concept, the coherence of their narrative, their capacity to maintain relationships and employment, the quality of their reflection on their own contributions to difficulties, and the presence of self-harm or repeated crises. Structured instruments, such as the Level of Personality Functioning Scale, support the judgement but do not replace it.

Why severity matters clinically

Severity predicts treatment intensity, risk, and the likelihood of dropout. A client with mild personality difficulties may benefit from time-limited work in a general service; a client with severe personality disorder requires a longer, more structured approach with explicit attention to alliance and containment. Confusing the two leads to either over-treatment or, more commonly, to under-treatment disguised as a diagnosis.

5.9 Personality Assessment in Case Formulation

Personality findings become clinically useful when they are translated into a formulation: an account of how the person's enduring patterns interact with current circumstances to produce and maintain the presenting problem.

From trait to pattern to process

The translation proceeds in three steps. Traits become patterns when they are described in terms of recurring behaviour across situations. Patterns become processes when they are described in terms of mechanism: what triggers them, what they achieve, and what they cost. A client high in neuroticism and low in agreeableness may show a pattern of anticipating criticism and responding with counter-criticism; the process is a cycle in which anticipatory vigilance produces behaviour that elicits the criticism that confirms the expectation.

Developmental and relational context

Formulation situates the pattern in its developmental history and its current relational field. The relevant questions are how the pattern developed,

what function it served, and what maintains it now. A pattern that developed as a protection in an unpredictable household may persist long after the household has gone, maintained by its own consequences. This account is explanatory, testable and non-judgemental in a way that a trait description is not.

Writing the formulation

A written formulation of personality should describe the pattern, its origins, its maintaining processes, its costs and its adaptive value, in language the client could read without feeling accused. It should distinguish what is known from what is inferred, and it should identify the point at which intervention is most likely to be effective. Where the formulation cannot be written in such language, it is usually not yet a formulation.

5.10 Feedback from Personality Assessment

Feedback is where personality assessment either becomes useful or becomes harmful. Clients are frequently given personality labels without explanation, and the experience of being described in a report they never see, in terms they would not recognise, is a recognised source of harm.

Principles of feedback

Feedback should be collaborative, specific and behavioural. It should avoid trait labels used as explanations, translate findings into examples the client recognises, invite correction, and connect each finding to something the client can act on. Where the assessment identified a pattern the client had not noticed, the feedback should present it as a hypothesis to be tested rather than a verdict.

Discussing difficult findings

Some findings are difficult: low empathy, high hostility, marked dependency, or a pattern of self-defeating behaviour. The evidence suggests that these findings can be discussed productively when they are framed as protective or adaptive in origin, described in behavioural terms, connected to

the client's own stated goals, and accompanied by explicit acknowledgement of the assessor's limits. Feedback that moralises, or that uses the assessment as an opportunity to say what the assessor has always thought, is harmful and should not be delivered.

Follow-up

Feedback should be followed by an opportunity to respond, and the client's response should be recorded. Where the client disputes a finding, the dispute is information: it may indicate that the interpretation was wrong, that it was correct but premature, or that it was correct and unwelcome. Distinguishing among these requires the assessor to remain curious rather than defensive.

5.11 Cultural Interpretation of Personality Scores

Personality inventories were developed largely in North America and Western Europe, and their item content, normative data and implicit models of healthy functioning carry cultural assumptions. The assessor must therefore consider whether the construct, the items and the norms are appropriate for the client.

Cultural variation in trait expression

The distribution of traits differs across cultural groups, and the meaning of a given trait level may differ more than the distribution. Assertiveness, emotional restraint, deference to family and directness of self-disclosure are valued differently, and a score that is average in one setting may represent unusual conformity or unusual deviation in another. The five-factor structure has been broadly replicated, but the interpretation of specific facets is more culturally variable than the factor structure suggests.

Norms, reference groups and comparison

Where norms are available for the client's cultural or linguistic group, they should be used, with attention to their quality. Where they are not, the assessor should interpret scores with explicit caution and should prefer with-

in-person and behavioural comparisons. A useful practice is to ask the client what their own reference group would consider typical, which often supplies context that no norm table contains.

Avoiding cultural attribution of pathology

There is a persistent risk that culturally patterned behaviour is read as personality pathology: restraint as constriction, deference as dependency, indirectness as evasiveness, or emotional expressiveness as histrionic. The corrective is not to exempt cultural behaviour from assessment but to generate cultural explanations as competing hypotheses and to test them with the client, the family and, where appropriate, a cultural consultant.

5.12 Integrating Personality Findings

Integration requires the assessor to combine self-report, interview, informant data, behavioural observation and, where used, performance-based measures into a description that is coherent, evidence-based and useful. The obstacles are predictable: sources disagree, instruments measure overlapping constructs, and the pressure to produce a definitive description is strong.

A procedure for integration

A workable procedure begins with the questions the assessment was asked to answer, not with the instruments. For each question, the assessor arrays the evidence from each source and notes its direction and quality. Where sources converge, the finding can be stated with confidence. Where they diverge, the assessor examines the conditions under which each was obtained and decides which is more informative for the specific question. The final description should state the pattern, its functional consequences, its probable developmental origins and its implications for treatment.

Writing without reification

The most important stylistic discipline in personality reporting is to avoid turning a score into an entity. “The client is a narcissistic personality” is a

reification; "the client describes a strong need for admiration and reacts to criticism with rage, which has cost him two jobs and a marriage" is a description. The second can be discussed, tested and treated; the first can only be accepted or rejected. Reports should describe behaviour, its function and its consequences, and should use diagnostic terms only where a diagnosis has been formally established and is required by the recipient.

Limits of the assessment

Finally, the report should state what the assessment could not establish: the stability of the pattern over time where only one assessment was conducted, the possibility of state effects on trait measurement, the absence of informant data where none was available, and the limits of the norms for this client. A personality assessment that acknowledges these limits is more credible than one that presents a fully formed portrait on limited evidence.

Advanced Case Conference

The referral. A psychotherapy service asks for assessment of a 34-year-old woman referred after two failed courses of treatment, the first ending in abrupt termination and the second in a crisis admission. The question is what kind of treatment, if any, is likely to help.

The evidence. Interview reveals longstanding difficulty in close relationships, a history of intense but unstable attachments, recurrent self-harm in her twenties and a pattern of idealisation followed by devaluation of therapists. A five-factor inventory shows very high neuroticism, low agreeableness and low conscientiousness. A broad clinical inventory shows elevations across several scales with a validity profile suggesting moderate over-reporting. Self-report attachment measures indicate high anxiety and high avoidance. There is no informant data; the client declined collateral contact.

The reasoning. The severity of impairment in self and interpersonal functioning, combined with the longstanding pattern and the repeated treatment ruptures, is consistent with a moderate to severe personality disorder. The trait profile is consistent but non-specific, and the over-reporting suggests that the self-report scores should be interpreted as an indication of distress rather than as precise estimates. The pattern of rapid idealisation and devaluation has direct implications for treatment: an unstructured exploratory therapy is likely to reproduce the rupture, while a structured approach with explicit agreements about contact between sessions, a clear treatment frame and a named clinician responsible for coordination is more likely to hold.

The decision. The report describes the pattern and its severity, states the diagnosis provisionally, and recommends a structured, formulation-driven treatment with explicit frame agreements and a named coordinator. It states what would indicate that the treatment is working, and what would indicate that it should be reviewed. It records the absence of collateral data as a limitation and the client's reasons for declining it.

The teaching point. The assessment's value lay in what it said about the treatment, not in what it said about the personality. The most consequential finding was a pattern of relationship rupture, and it changed the recommendation.

Chapter Summary

Personality assessment describes enduring organisation rather than current state, and it requires multiple methods and cautious inference. Trait models provide a reliable descriptive structure but do not by themselves distinguish disorder from variation; severity of impairment in self and interpersonal functioning carries most of the clinical information. Broad-band inventories supply comprehensive description with validity scales, narrow-band measures supply depth, and interpersonal and attachment frameworks supply the relational context in which personality difficulties are enacted. Response style affects every self-report measure and must be interpreted rather than ignored. Performance-based measures are defensible where specific variables have demonstrated validity for specific questions, and not as general personality description. Integration should proceed

from the question, describe patterns and processes rather than traits-as-entities, and state the limits of what a single assessment can establish.

Review Questions

1. Distinguish trait, dimensional and severity-based approaches to personality and state what each contributes to diagnosis.
2. What does a validity scale measure, and what can it not establish?
3. Explain the difference between what the Adult Attachment Interview and a self-report attachment measure assess.
4. Why is severity of impairment more informative than trait extremity for treatment planning?
5. Describe three ways in which a personality report can reify a score into an entity, and how to avoid each.

Discussion Questions

1. A client's self-report suggests marked over-reporting, but the clinical interview suggests genuine and severe distress. How do you proceed, and what do you record?
2. Should performance-based measures be used in doctoral-level counselling psychology assessment? Defend a position with reference to the evidence.
3. How would you give feedback about low empathy without damaging the therapeutic relationship?
4. What are the risks of using personality assessment in employment selection, and what safeguards would you require?
5. The client declines all collateral contact. How does this change the confidence of a personality formulation?

Further Reading

American Psychiatric Association. (2022). *Diagnostic and statistical manual of mental disorders* (5th ed., text rev.). American Psychiatric Association Publishing.

Ben-Porath, Y. S., & Tellegen, A. (2008). *MMPI-2-RF: Manual for administration, scoring, and interpretation*. University of Minnesota Press.

Brennan, K. A., Clark, C. L., & Shaver, P. R. (1998). Self-report measurement of adult attachment: An integrative overview. In J. A. Simpson & W. S. Rholes (Eds.), *Attachment theory and close relationships* (pp. 46–76). Guilford Press.

George, C., Kaplan, N., & Main, M. (1985). *Adult Attachment Interview* [Unpublished manuscript]. Department of Psychology, University of California, Berkeley.

McCrae, R. R., Costa, P. T., Jr., & Martin, T. A. (2005). The NEO-PI-3: A more readable revised NEO Personality Inventory. *Journal of Personality Assessment, 84*(3), 261–270.

Mihura, J. L., Meyer, G. J., Dumitrascu, N., & Bombel, G. (2013). The validity of individual Rorschach variables: Systematic reviews and meta-analyses of the Comprehensive System. *Psychological Bulletin, 139*(3), 548–605.

Morey, L. C. (2007). *Personality Assessment Inventory professional manual* (2nd ed.). Psychological Assessment Resources.

World Health Organization. (2024). *Clinical descriptions and diagnostic requirements for ICD-11 mental, behavioural and neurodevelopmental disorders*. World Health Organization.

CHAPTER 6

Cognitive, Intellectual and Neuropsychological Assessment

Learning Objectives

After working through this chapter, the reader should be able to:

- identify the questions that cognitive assessment can and cannot answer;
- compare major theories of intellectual functioning and their implications for interpretation;
- evaluate cognitive profiles using base rates, discrepancy standards and estimated premorbid ability;
- assess attention, memory, executive function, language and visuospatial skills by domain;
- select and interpret performance validity measures appropriately;
- integrate medical, neurological and developmental context into cognitive conclusions;
- communicate cognitive findings in functional terms that clients and referrers can use.

Key terms: intelligence · g factor · Cattell–Horn–Cattell model · process overlap · premorbid estimation · discrepancy analysis · processing speed · working memory · executive function · performance validity · ecological validity · cognitive reserve

Introduction

Cognitive assessment addresses a distinctive class of questions: what can this person do with their intellectual resources, how does that capacity compare with what would be expected for them, and what does the difference imply for their daily functioning, education or work? These questions matter in developmental assessment, in neurological and psychiatric conditions affecting cognition, in educational and occupational decisions, and in legal contexts where capacity or injury is at issue.

The technical demands are high. Cognitive measures have the most elaborate normative structures in psychology, the strongest evidence on reliability, and the most developed methods for estimating change. They are also the measures most vulnerable to misuse: a low score can be read as a diagnosis, a discrepancy as a deficit, and a profile as an explanation, when none of these inferences is warranted without context. This chapter sets out the theory, the methods and the interpretive discipline required to make cognitive findings both accurate and useful. Figure 6.1 presents cognitive assessment as a sequence of claims, separating capacity, context and consequence.




Figure 6.1. Cognitive assessment as a sequence of claims, each requiring its own evidence. Capacity, context and consequence are separate questions.

6.1 Questions Addressed by Cognitive Assessment

Cognitive assessment answers four broad types of question, and the assessor should know which is being asked before selecting an instrument.

Descriptive questions

Descriptive questions concern the person's current level of performance relative to a reference group: how does this child's reading accuracy compare with others of the same age; how does this adult's processing speed compare with the general population? Descriptive questions are the easiest to answer and the most often confused with the other three.

Diagnostic and aetiological questions

Diagnostic questions ask whether a recognised condition is present: intellectual disability, a specific learning disorder, attention-deficit/hyperactivity disorder, a neurocognitive disorder, or an acquired brain injury. Aetiological questions ask what caused an observed impairment. Cognitive tests contribute to both, but rarely settle either alone: a test score is compatible with many causes, and diagnosis usually requires history, course, medical investigation and functional evidence.

Change and monitoring questions

Change questions ask whether functioning has altered: has cognition declined since a previous assessment; is treatment affecting attention; is rehabilitation producing recovery? These questions require instruments with demonstrated sensitivity to change, reliable change indices, and either a previous assessment or a well-justified estimate of premorbid functioning.

Functional and decision questions

Functional questions ask what the person can do in their own environment, and decision questions ask what should follow: what support is needed at school, whether the person can manage their affairs, whether they can return to work. Cognitive tests inform these questions but do not answer them directly. The relationship between test performance and

everyday functioning — ecological validity — is moderate at best, and the assessor must supplement test data with behavioural and informant evidence.

6.2 Theories of Intellectual Functioning

Interpretation of cognitive scores presupposes a model of what intelligence is. Three families of model dominate, and each carries different implications for how a profile should be read.

The general factor

Spearman's observation that performance on seemingly diverse cognitive tasks is positively correlated led to the concept of a general factor, *g*, which accounts for a substantial proportion of variance across tasks. The finding has been replicated many times and remains one of the most robust in differential psychology. Its interpretive implication is conservative: because all cognitive tasks share variance with *g*, differences between tasks are smaller than they appear, and a profile of strengths and weaknesses may reflect measurement noise more than cognitive structure.

Hierarchical models

The Cattell–Horn–Cattell model proposes a hierarchy in which *g* sits above broad abilities — fluid reasoning, crystallised knowledge, visual–spatial processing, auditory processing, short-term working memory, long-term storage and retrieval, and processing speed — which in turn sit above narrow abilities. This model underpins most contemporary intelligence tests, and it supplies the vocabulary in which profiles are described. Its practical contribution is the identification of broad domains that have distinct developmental trajectories, distinct neural substrates and distinct implications for learning.

Alternative and process accounts

Alternative accounts emphasise processing rather than structure. The process overlap theory of Kovacs and Conway (2016) explains positive correla-

tions among diverse tasks through the overlap of executive processes they recruit, rather than through a single underlying capacity; other accounts emphasise working memory capacity, relational processing or neural efficiency. These models are not yet the basis of clinical instruments, but they matter for interpretation: they caution against treating a broad-ability score as a thing, and they direct attention to the processes that produce performance.

Implications for the assessor

The practical implications are threefold. First, broad scores should be reported and interpreted before narrow ones, because they are more reliable and account for more variance. Second, profile differences should be interpreted only where they exceed the standard error of the difference and where there is corroborating functional evidence. Third, the choice of model should be stated, because instruments built on different models produce scores that are not directly comparable.

6.3 Interpreting Cognitive Profiles

Profile interpretation is the most contested practice in cognitive assessment. The idea that a pattern of relative strengths and weaknesses identifies a specific condition has intuitive appeal and limited empirical support.

The discrepancy approach and its limits

Discrepancy analysis compares a person's attainment or domain scores with an estimate of their general ability. The approach is used in the identification of specific learning disorders, where the defining feature is attainment substantially below the level predicted by ability, and in the identification of cognitive decline, where current performance is compared with estimated premorbid functioning. Its limitations are well known: the comparison is between two fallible estimates, so the standard error of the difference applies to the discrepancy as much as to either score; the base rate of discrepancies in the general population is high; and the decision about how

large a discrepancy must be is a policy choice rather than an empirical discovery.

Estimated premorbid functioning

Estimating premorbid ability is necessary whenever decline is suspected. Three methods are available: demographic estimation from age, sex, education and occupation; reading-based estimation using tests of irregular word reading, which are relatively resistant to neurological decline; and best-performance estimation using the highest score obtained across the history. Each has limitations: demographic estimates are imprecise at the individual level; reading-based estimates are invalid in people with pre-existing reading difficulties, non-native speakers or limited education; and best-performance estimates assume that the person's best performance was genuinely their optimum.

Base rates and the clinical significance of profiles

The base-rate problem is acute here. A difference of one standard deviation between verbal and visuospatial ability, or between a full-scale score and a single index, occurs in a substantial proportion of the healthy population. Before interpreting such a difference as a finding, the assessor should consult published base-rate tables for the instrument and should ask whether the pattern corresponds to something observable: a task the person avoids, a domain in which they have always struggled, or a functional consequence that others have noticed.

6.4 Attention and Processing Speed

Attention is not a single capacity but a family of processes: alerting and arousal, sustained attention or vigilance, selective attention, divided attention and attentional control. Processing speed describes the rate at which cognitive operations are performed. Together they underpin almost every other cognitive task, which is why their assessment must precede the interpretation of domain-specific scores.

Distinguishing the components

Sustained attention is assessed by continuous performance tasks requiring detection of infrequent targets over time. Selective attention is assessed by tasks requiring suppression of distractors, such as Stroop-type procedures. Divided attention is assessed by dual-task paradigms. Processing speed is assessed by simple and choice reaction time tasks, symbol substitution and timed coding. Because these components are separable, a general complaint of "poor concentration" requires specification before it can be assessed.

Confounds

Performance on attention tasks is exquisitely sensitive to sleep, pain, medication, anxiety, depression, motivation and substance use. A single assessment conducted during a period of sleep restriction cannot distinguish an attention disorder from the effects of sleep restriction, and the assessor should establish sleep and substance history before interpreting any attention score. Effort and engagement must be evaluated with performance validity measures, because attention tasks are the easiest to underperform deliberately.

Reporting attention findings

Reports should specify which component was impaired, under what conditions, with what confidence, and with what functional consequence. "Sustained attention was reduced relative to estimated premorbid functioning; the client reports difficulty reading for more than ten minutes and has stopped driving on motorways" is a finding with implications. "Attention deficits" is a label without one.

6.5 Learning and Memory

Memory assessment distinguishes encoding, storage and retrieval, and separates verbal from visual material and immediate from delayed recall. Recognition procedures distinguish retrieval failure from storage failure, and interference paradigms examine susceptibility to proactive and retroactive interference.

Domains and methods

Verbal learning is typically assessed by list-learning tasks that measure acquisition across trials, recall after interference, and recognition. Visual memory is assessed by reproduction or recognition of figures. Working memory is assessed by digit span, spatial span and complex span tasks that require simultaneous storage and processing. Prospective memory — remembering to do something in the future — is often more relevant to everyday functioning than retrospective memory and is often omitted from batteries.

Interpreting memory scores

Three interpretive questions structure the analysis. Is the memory difficulty disproportionate to the person's overall cognitive level, or part of a general decline? Is it material-specific, affecting verbal but not visual memory, which may suggest lateralised dysfunction and warrants medical referral? Is it a retrieval problem, in which case cues improve performance, or an encoding problem, in which case they do not? Each question has implications for both aetiology and rehabilitation.

Functional relevance and everyday memory

Laboratory memory tests predict everyday memory complaints weakly. The assessor should therefore supplement them with self-report and informant measures of everyday memory, and with behavioural observation during the assessment, such as whether the client remembers instructions across tasks. Where test performance and everyday functioning diverge, the divergence is itself a finding that requires explanation, often in terms of strategy use, environmental support or emotional factors.

6.6 Executive Functions

Executive functions are the supervisory processes that organise goal-directed behaviour: inhibition, shifting, updating of working memory, planning, monitoring and emotional regulation. They are among the most eco-

logically important cognitive functions and among the most difficult to measure.

The measurement problem

The central difficulty is that executive function is defined by the demands of a task rather than by its content, and structured test settings supply exactly the structure that executive function is required to provide in everyday life. A client may perform normally on a formal planning task in a quiet room while being unable to organise a shopping trip. This is the "executive paradox": laboratory measures of executive function correlate modestly with everyday executive behaviour, and informant ratings often predict real-world outcomes better than tests do.

Assessment strategy

A defensible strategy combines three sources: performance-based tests of specific executive components; informant-rated questionnaires of everyday executive behaviour, completed by someone who knows the client well; and observation of the client's behaviour during the assessment itself, including their ability to follow multi-step instructions, to shift between tasks, and to manage frustration. The convergence of these sources, or the absence of convergence, is the finding.

Reporting executive findings

Because executive difficulties are most visible in unstructured, novel or emotionally demanding situations, reports should describe the conditions under which the difficulty appears rather than stating a global deficit. This has direct implications for recommendations, which should focus on external structure, environmental modification and routines rather than on the client's effort.

6.7 Language and Visuospatial Skills

Language and visuospatial ability are the two broad domains most often lateralised and most often affected differentially by neurological events.

Their assessment contributes both to diagnosis and to rehabilitation planning.

Language

Language assessment covers naming, fluency, comprehension, repetition, reading and writing. In counselling psychology settings, the most common reasons for assessing language are suspected neurodevelopmental language disorder, suspected aphasia after stroke or injury, and the need to establish whether a client can comprehend an instrument administered in the test language. Brief measures of verbal fluency and naming are sensitive to a range of conditions and are worth including in most cognitive batteries.

Visuospatial and constructional skills

Visuospatial assessment covers visual perception, spatial judgement, construction, visual memory and, in some batteries, navigation and neglect. Copying tasks, block design, judgement of line orientation and spatial span are standard methods. Difficulties may reflect primary visual impairment, which should be excluded by a vision check, or constructional apraxia, or a broader non-verbal learning difficulty.

The verbal–non-verbal discrepancy

The discrepancy between verbal and visuospatial performance is commonly interpreted as evidence of a non-verbal learning disability or of right-hemisphere dysfunction. The interpretation is weak when based on a single administration and strong only when the discrepancy is large, stable, corroborated by functional evidence and consistent with history. Where the discrepancy reflects an artefact of language dominance in a multilingual client, the error can be substantial.

6.8 Neuropsychological Screening

Not every assessment requires a full neuropsychological battery. Screening instruments exist to identify clients who need fuller assessment, to monitor change, and to answer simple questions efficiently.

Screening versus assessment

A screen is a brief procedure with high sensitivity and moderate specificity, designed to ensure that no significant case is missed. It is not designed to characterise a profile or to establish a diagnosis. Instruments such as the Montreal Cognitive Assessment (Nasreddine et al., 2005) and the Mini-Mental State Examination (Folstein, Folstein, & McHugh, 1975) are widely used screens; both are affected by education, language and culture, and both have limited sensitivity to executive and visuospatial impairment in high-functioning people.

When to refer

Referral for full neuropsychological assessment is indicated where a screen is abnormal, where cognitive complaints are accompanied by functional decline, where a neurological condition is suspected, where a decision with significant consequences (capacity, fitness, guardianship) depends on cognitive status, and where the client's presentation is inconsistent with the available information. The assessor should state the reason for referral explicitly, since a vague referral produces a vague assessment.

6.9 Performance Validity

Performance validity refers to the extent to which a person's performance on cognitive testing reflects their true ability. It is distinct from response bias on self-report questionnaires, and it must be assessed in any context where secondary gain is plausible and, increasingly, in all cognitive assessments as a matter of routine.

The rationale

Performance validity tests are designed to be failed by almost no one with genuine cognitive impairment of the severity being assessed, but to be failed by a substantial proportion of people who are deliberately underperforming. Their logic rests on forced-choice paradigms, in which the probability of scoring below chance can be calculated, and on embedded indices within standard tests that detect improbable patterns of performance.

Interpretation

Interpretation requires attention to the base rate of invalid performance in the relevant setting, which ranges from near zero in routine clinical samples to substantial proportions in medico-legal and disability evaluation contexts. A single failed measure is generally insufficient; current consensus statements recommend multiple indicators and consideration of the overall pattern (Sweet et al., 2021). Importantly, invalid performance does not establish malingering: it establishes only that the scores cannot be interpreted as estimates of ability.

What the assessor must report

Where validity is compromised, the assessor must state which measures were failed, the base rate of such failure in comparable samples, the probable effect on other scores, and the limits this imposes on any conclusion. Failing to report an invalid performance, or interpreting cognitive scores despite it, is a serious professional error.

6.10 Medical and Neurological Context

Cognitive findings cannot be interpreted apart from medical and neurological information. The same score carries different implications depending on whether it was obtained before or after a neurological event, during or between episodes of illness, on or off medication, and in the presence or absence of pain and sleep disturbance.

Conditions that shape cognitive findings

Relevant conditions include traumatic brain injury, stroke, epilepsy, multiple sclerosis, Parkinson's disease, dementia and other neurodegenerative conditions, HIV, thyroid disease, vitamin deficiencies, chronic pain, sleep apnoea, and the cognitive effects of psychiatric disorders themselves. Medications with cognitive side effects are common, particularly anticholinergics, benzodiazepines, anticonvulsants and some antidepressants. Substance use, both acute and chronic, affects nearly every domain assessed.

Integrating medical information

The assessor should obtain the medical history, current diagnoses, medication list, results of neuroimaging and other investigations where available, and the chronology relating medical events to cognitive change. Where such information is unavailable, the report must say so, and conclusions about aetiology should be correspondingly cautious. The boundary of competence is important: the identification of a neurological condition is a medical judgement, and the psychologist's contribution is the characterisation of cognitive and functional consequences.

Medical red flags

Certain findings require prompt medical referral rather than psychological formulation: acute confusion, new focal neurological signs, recent-onset seizures, severe headache with vomiting, rapid cognitive decline, and cognitive change in the context of fever or systemic illness. The assessor should know these and act on them without delay.

6.11 Functional Implications of Cognitive Findings

The value of a cognitive assessment to the client depends on its translation into functional implications. This is a separate step of reasoning, and it is the step most often skipped.

From score to activity to participation

A useful translation moves through three levels. The score describes performance on a task. The task maps onto an activity of daily living, such as managing medication or following a conversation in noise. The activity maps onto participation, such as living independently or sustaining employment. Each mapping requires evidence, ideally from observation or informant report, and each introduces uncertainty that should be stated.

Ecological validity and its limits

Ecological validity research shows moderate relationships between cognitive test performance and everyday functioning, stronger for some domains

than others. Memory and executive measures tend to predict instrumental activities better than processing speed or simple attention. The relationship is improved by using multiple measures, by including informant ratings, and by assessing the person in or near their own environment.

Recommendations that follow

Functional recommendations should be specific to the activity and the setting, and should name the support rather than the deficit: a written medication schedule and a weekly check with a pharmacist, rather than "needs support with medication"; a reduced-distraction workspace and written instructions, rather than "has attentional difficulties". Recommendations should also indicate what would prompt review, since cognitive function and environmental demands both change.

6.12 Communicating Cognitive Results

Cognitive reports are read by clients, families, teachers, employers, insurers and tribunals. Each audience needs the same core information in a different form, and the assessor's task is to make the report accurate, accessible and honest about its limits.

Reporting scores

A score should be reported with its name, its scale, its percentile and its confidence interval, together with a plain-language descriptor. Reports should make clear what the score measures and what it does not: a working memory index does not measure intelligence, and a full-scale score does not measure potential. Where normative comparisons are uncertain because of language, culture, education or sensory factors, the report should say so at the point where the score is presented, not in a final paragraph.

Explaining uncertainty

Clients and referrers often prefer certainty, and assessors often supply it. The professional obligation is to explain uncertainty in terms the recipient can use. "Your scores on these tasks were lower than we would expect given

your education and previous work, but the difference is within the range that could be produced by the fatigue and pain you described. I would like to repeat the assessment when you are sleeping better, because that will tell us more than a single test can." This is honest, respectful and actionable.

Feedback as part of the assessment

Feedback on cognitive findings should include the client's own experience of the tasks, the assessor's observations, the functional implications and the recommended next steps. Where findings are unwelcome, the assessor should allow time for reaction and should avoid presenting conclusions as fixed. And where the client's account differs from the assessment, the difference should be explored, since the client often holds information that the test room could not supply.

Advanced Case Conference

The referral. A 58-year-old man is referred by his employer's occupational health service after increasing errors at work over eighteen months. His job requires managing multiple projects and remembering detailed specifications. The question is whether he has a cognitive impairment and whether he can continue in his current role.

The assessment. He obtains a full-scale score in the average range. Verbal comprehension is high average, perceptual reasoning average, working memory low average and processing speed borderline. Delayed memory is low average, with a large primacy effect and poor free recall that improves substantially with cueing. Executive measures show reduced planning efficiency and increased perseveration. Performance validity is within normal limits. A depression inventory is in the moderate range; he reports sleeping five hours and waking early since his wife's death two years ago. He takes a prescribed antihistamine nightly and drinks two to three glasses of wine most evenings.

The reasoning. The profile is not consistent with a generalised dementia: verbal knowledge is preserved, memory shows a retrieval pattern rather than a storage failure, and validity is adequate. It is consistent with a depressionrelated attentional and executive difficulty, compounded by sleep restriction, anticholinergic medication and alcohol. The memory pattern is the key discriminator: cortical memory disorders typically show poor encoding and limited benefit from cueing, whereas the pattern observed here is more typical of reduced effortful retrieval.

The decision. The report describes the profile, declines to diagnose a neurocognitive disorder, and identifies depression, sleep and substance factors as probable contributors requiring treatment before any conclusion about dementia. It recommends a review of the antihistamine with his general practitioner, treatment for depression, and reassessment in six months. On fitness for work, it recommends temporary redistribution of the most memory-demanding projects, with a review, and states that a determination of permanent capacity would be premature.

The teaching point. The most important finding was a pattern, not a score. The pattern directed attention to reversible contributors, and the recommendation was to treat them before concluding anything about permanent decline.

Chapter Summary

Cognitive assessment answers descriptive, diagnostic, change-related and functional questions, and the assessor must know which is being asked. Theories of intelligence supply the reference structure for interpretation, and hierarchical models are the most useful clinically. Profile interpretation is constrained by the standard error of the difference, by base rates in the general population and by the need for functional corroboration. Attention, memory and executive function each require domain-specific assessment and attention to confounds; executive function in particular is poorly captured by laboratory tasks alone. Performance validity must be evaluated in every cognitive assessment and reported when compromised. Medical and neurological information is essential to aetiological conclusions, and

referral is mandatory when red flags are present. The final step, translation into functional implications, is what makes the assessment useful.

Review Questions

1. Distinguish descriptive, diagnostic, change-related and functional questions in cognitive assessment.
2. Why should broad-ability scores be interpreted before narrow ones?
3. Describe three methods of estimating premorbid ability and one limitation of each.
4. What is the executive paradox, and what does it imply for assessment strategy?
5. What does a failed performance validity test establish, and what does it not establish?

Discussion Questions

1. A parent requests a cognitive assessment to "prove" that their child needs a special school placement. How do you negotiate the referral?
2. How should an assessor respond when a cognitive profile is inconsistent with the client's reported functioning?
3. Is it ever appropriate to interpret a cognitive profile in the absence of premorbid data? Under what conditions?
4. What are the ethical issues in assessing cognitive function for a medico-legal report where secondary gain is plausible?
5. How would you explain a borderline processing speed score to a client who fears dementia?

Further Reading

Folstein, M. F., Folstein, S. E., & McHugh, P. R. (1975). "Mini-mental state": A practical method for grading the cognitive state of patients for the clinician. *Journal of Psychiatric Research, 12*(3), 189–198.

Kovacs, K., & Conway, A. R. A. (2016). Process overlap theory: A unified account of the general factor of intelligence. *Psychological Inquiry, 27*(3), 151–177.

Lezak, M. D., Howieson, D. B., Bigler, E. D., & Tranel, D. (2012). *Neuropsychological assessment* (5th ed.). Oxford University Press.

Nasreddine, Z. S., Phillips, N. A., Bédirian, V., Charbonneau, S., Whitehead, V., Collin, I., Cummings, J. L., & Chertkow, H. (2005). The Montreal Cognitive Assessment, MoCA: A brief screening tool for mild cognitive impairment. *Journal of the American Geriatrics Society, 53*(4), 695–699.

Schneider, W. J., & McGrew, K. S. (2018). The Cattell–Horn–Cattell theory of cognitive abilities. In D. P. Flanagan & E. M. McDonough (Eds.), *Contemporary intellectual assessment: Theories, tests, and issues* (4th ed., pp. 73–163). Guilford Press.

Sweet, J. J., Heilbronner, R. L., Morgan, J. E., Larrabee, G. J., Rohling, M. L., Boone, K. B., Kirkwood, M. W., Schroeder, R. W., & Suhr, J. A. (2021). American Academy of Clinical Neuropsychology (AACN) 2021 consensus statement on validity assessment. *Archives of Clinical Neuropsychology, 36*(5), 623–647.

CHAPTER 7

Achievement, Aptitude, Career and Functional Assessment

Learning Objectives

After working through this chapter, the reader should be able to:

- distinguish achievement, aptitude, adaptive behaviour and functional capacity as constructs;
- assess reading, writing and mathematics difficulties in a way that informs instruction;
- evaluate aptitude measures and understand their predictive limits;
- use interest and values inventories in career assessment without determinism;
- assess adaptive behaviour and functional capacity through multiple informants and methods;
- contribute psychological evidence to disability and accommodation decisions;
- write functional recommendations that services and employers can implement.

Key terms: achievement · aptitude · curriculum-based measurement · learning disorder · adaptive behaviour · functional capacity · work personality · interest–environment fit · reasonable accommodation · support needs · transferable skills

Introduction

The assessments described in this chapter share a focus on what a person can do: academically, occupationally and in the activities of everyday life.

They are frequently commissioned for decisions with immediate material consequences — examination access arrangements, special educational provision, disability benefits, occupational fitness, vocational rehabilitation — and they are therefore subject to a particular kind of pressure. The assessor is asked not only what the evidence shows but what conclusion would help.

Counselling psychologists encounter this work in educational settings, in occupational health, in vocational rehabilitation and in disability determination. The technical demands differ from clinical assessment, but the underlying discipline is the same: constructs must be defined, instruments matched to the question, norms checked for relevance, and conclusions tied to evidence. What is distinctive is the centrality of functioning and environment. A score describes a capacity; a decision requires an account of the demands the person faces and the support that would allow them to meet those demands. Figure 7.1 links capacity, demand and support, and locates the decision in the fit between them rather than in the capacity alone.




Figure 7.1. Functional assessment links capacity, demand and support. The decision concerns the fit between them, not the capacity alone.

7.1 Academic Achievement Assessment

Achievement assessment measures what a person has learned in specified domains relative to a reference group or a curriculum. Its purpose is usually to identify a learning difficulty, to establish a baseline for intervention, or to evaluate whether an intervention has worked.

Achievement and ability are different constructs

Achievement measures developed skill; ability measures developed capacity. The distinction matters because the two are highly correlated but not interchangeable, and because some measures described as achievement tests are in fact measures of reasoning applied to academic content. The assessor should know which construct a given instrument measures, since the interpretation differs: a low achievement score with average ability suggests a skill-specific difficulty, whereas a low achievement score with low ability suggests a general learning difficulty requiring a different response.

Curriculum-based and norm-referenced approaches

Norm-referenced achievement tests compare a student with a national or regional sample. They are useful for identifying significant under-attainment and for establishing eligibility for services, and they are insensitive to what a particular student has actually been taught. Curriculum-based measurement compares performance with expected progress through a specified curriculum and is more sensitive to short-term change and to instructional effects. The two approaches answer different questions and are complementary; an assessment that uses only one will have a blind spot.

Assessing the conditions of learning

Achievement scores describe performance under the conditions of testing. The assessor should record the conditions of learning that produced that performance: attendance, language of instruction, teaching quality, class size, disruption, vision and hearing, and the student's own account of what they find difficult. A student who has missed a third of the school year has

an attendance problem that no test can diagnose, and an assessment that fails to record this has produced a number without a meaning.

7.2 Reading, Writing and Mathematics

Each of the three core academic domains has a structure that determines what must be assessed and how findings translate into instruction.

Reading

Reading comprises word-level skills (phonological awareness, decoding, sight-word recognition, fluency) and comprehension (vocabulary, inference, background knowledge, working memory). Assessment must establish which component is impaired, because the interventions differ: a decoding difficulty requires systematic phonics instruction, whereas a comprehension difficulty in a fluent decoder requires vocabulary and strategy work. A composite reading score conceals the distinction, and reporting only a composite score is a common and consequential error.

Writing

Writing involves transcription (handwriting, spelling), text generation (idea production, organisation) and executive control (planning, revising). Difficulties at the transcription level consume resources that would otherwise serve composition, so a student with slow handwriting or poor spelling may produce weak written work despite adequate ideas. Assessment should therefore separate transcription from composition, and should include at least one task that allows the student to dictate or use a keyboard where that is the accommodation under consideration.

Mathematics

Mathematics comprises number sense, procedural fluency, fact retrieval, problem representation and reasoning. Difficulties in fact retrieval and in procedural fluency are distinguishable from difficulties in mathematical reasoning, and the distinction predicts response to intervention. Assessment should include untimed reasoning tasks as well as timed calculation,

because a student whose reasoning is intact but whose retrieval is slow requires a different accommodation from one whose reasoning is impaired. Table 7.1 relates academic domains to their component skills and to the assessment that follows from each.

Table 7.1. Academic domains, component skills and assessment implications

Domain	Components to assess	Distinguishing finding	Instructional implication
Reading — word level	Phonological awareness; decoding; fluency	Accurate but slow decoding; poor nonword reading	Systematic phonics; fluency practice
Reading — comprehension	Vocabulary; inference; background knowledge	Fluent decoding with weak comprehension	Vocabulary and strategy instruction
Writing — transcription	Handwriting fluency; spelling	Slow, effortful handwriting; poor spelling	Transcription intervention; keyboard access
Writing — composition	Planning; text generation; revision	Adequate transcription, weak organisation	Strategy instruction; planning scaffolds
Mathematics — fluency	Fact retrieval; procedural accuracy	Accurate but slow and effortful calculation	Timed practice; calculator access where appropriate
Mathematics — reasoning	Problem representation; multi-step reasoning	Adequate fluency, weak word-problem performance	Explicit reasoning instruction; language support
Cross-domain	Attention; working memory; language proficiency	Broadly depressed performance in one language only	Language assessment before diagnosis

7.3 Aptitude and Learning Potential

Aptitude measures predict the capacity to acquire skills under specified conditions of training or instruction. They are used in educational selection, in occupational settings and, in counselling psychology, in the assess-

ment of learning potential for people whose educational history does not permit a straightforward interpretation of achievement scores.

Aptitude, ability and achievement

The boundaries between the three constructs are partly conventional. A test of verbal reasoning used to predict academic success is an aptitude measure; the same test used to estimate current cognitive capacity is an ability measure. What distinguishes aptitude is the predictive purpose: the score is interpreted as a forecast rather than a description. Forecasts are probabilistic and depend on the criterion, the training conditions and the range of abilities in the group to which the forecast applies.

Dynamic assessment and learning potential

Dynamic assessment measures the degree to which a person benefits from structured mediation, usually by comparing performance before and after a teaching phase. Its rationale is that learning potential is a better predictor of response to instruction than current attainment, particularly for people whose prior opportunities to learn have been limited. The approach has a substantial literature and a modest evidence base for incremental prediction; its principal value in counselling psychology is in assessment of people with atypical educational histories, where static scores under-estimate capacity.

Cautions

Aptitude scores should not be used to foreclose opportunity. The prediction of a group's average performance is a poor basis for a decision about an individual, and the lower the score, the less reliable the prediction of what that individual can achieve given adequate support. Where aptitude scores are used in selection, the assessor should know the selection utility research for the specific instrument and setting, and should recommend the use of multiple predictors.

7.4 Career Interests and Values

Career assessment addresses the fit between a person's interests, values, abilities and the demands and rewards of occupations. It is used in career counselling, in vocational rehabilitation, in educational guidance and in occupational settings where career transitions are being planned.

Interest inventories

Interest inventories, most of which are built on Holland's (1997) RIASEC model of realistic, investigative, artistic, social, enterprising and conventional themes, measure the similarity between a person's pattern of interests and the patterns characteristic of occupational groups. Their predictive validity for occupational choice and satisfaction is moderate and well established. Their limitations are equally established: interests are shaped by opportunity and by gender and class socialisation; they describe preferences, not capacities; and they can be constrained by what a person knows about the world of work.

Work values and motivators

Values inventories assess what a person wants from work: security, autonomy, recognition, service, income, work–life balance, intellectual challenge. Values predict satisfaction and turnover better than interests predict performance, and they are particularly useful in mid-career transitions where the person's priorities have changed. The assessor should treat values as context-dependent and revisable rather than as fixed traits.

Interpreting career data

Career assessment is most useful when it broadens rather than narrows the client's options. Interpreting a profile as a prescription — "your profile indicates accountancy" — is a misuse. The appropriate interpretation identifies themes, explores how they have been expressed, considers the constraints of the local labour market, and generates options for exploration. The client's own knowledge of their circumstances should carry substantial weight.

7.5 Work Personality and Work Adjustment

Beyond interests and values, certain personal characteristics predict adjustment to work: conscientiousness, emotional stability, interpersonal style, tolerance for stress and capacity for co-operation. These are the substance of what is sometimes called work personality.

Assessment approaches

Work personality is assessed through broad personality inventories, through specialised measures of work-related behaviour, through interviews about work history, and through structured references. Work history is often the most informative source and the most neglected: a pattern of short tenures, repeated conflicts with supervisors, or rapid disengagement after promotion carries more predictive weight than a trait score, provided the pattern is examined for situational explanations.

Work adjustment and its determinants

Work adjustment is a function of the person, the job demands, the supervisory relationship, the organisational climate and the fit between them. Assessment that characterises the person without characterising the job is incomplete. Where possible, the assessor should obtain a description of the role's demands, the physical and interpersonal environment, and any changes that preceded the difficulty; occupational health services, job descriptions and supervisor accounts are the usual sources.

Reporting work-related findings

Reports for occupational audiences should be behavioural and practical. Statements about personality traits are of limited use to a manager; statements about the conditions under which the person performs effectively, and the accommodations that would support performance, are of direct use. This is also the form of reporting least likely to stigmatise.

7.6 Adaptive Behaviour

Adaptive behaviour describes the conceptual, social and practical skills required for everyday functioning. It is central to the diagnosis of intellectual disability, where significant limitations in adaptive functioning are a defining requirement, and it is relevant wherever functional capacity is at issue.

Conceptual, social and practical domains

Conceptual skills include literacy, numeracy, reasoning and self-direction. Social skills include interpersonal communication, social judgement, and the capacity to follow rules and avoid victimisation. Practical skills include personal care, domestic tasks, use of money, use of transport and occupational functioning. Assessment requires informant report, because self-report in this area is systematically unreliable, and it requires attention to the environments in which the person actually functions.

Instruments and methods

Standardised adaptive behaviour instruments, such as the Vineland Adaptive Behavior Scales (Sparrow, Cicchetti, & Saulnier, 2016) and the Adaptive Behavior Assessment System, are completed by an informant who knows the person well and yield standard scores by domain. Direct observation and task-based assessment supplement informant report, and are particularly useful where informants disagree or where the person lives in a highly structured setting that may mask or compensate for limitations.

Distinguishing adaptive behaviour from ability

Adaptive behaviour and intellectual ability are correlated but distinct, and the discrepancy between them is clinically important. A person with mild intellectual disability may function independently with support; a person with average ability may have severe adaptive limitations due to autism, mental illness or institutionalisation. Diagnosis of intellectual disability requires both, and assessment of only one is a recurring source of error.

7.7 Functional Capacity and Daily Activities

Functional capacity assessment evaluates what a person can do in the activities of daily living, usually for the purpose of a decision about support, accommodation or eligibility. It differs from adaptive behaviour assessment in its focus on specific tasks and specific environments rather than on developmental skill level.

Defining the activity

The first task is to define the activity precisely. "Can he manage his finances?" is not assessable; "can he pay household bills on time, keep track of a bank balance and avoid fraudulent transactions?" is. Domains commonly assessed include self-care, mobility, meal preparation, household management, medication management, financial management, communication, transport, social participation and work-related tasks.

Methods

Functional capacity is assessed through interview, informant report, direct observation and, where possible, task performance in a realistic environment. Standardised functional measures and structured checklists improve reliability; occupational therapy assessment is often the most thorough source. Self-report is the weakest method for this purpose, since people systematically over-estimate or under-estimate their capacity, sometimes for understandable reasons.

The capacity–performance distinction

A person may have the capacity to perform an activity but not perform it in practice, because of environmental barriers, mental state, motivation or lack of opportunity. Conversely, a person may perform an activity only because of extensive support that is invisible in the assessment. Reports should distinguish capacity, performance and support, because decisions about support depend on all three.

7.8 Disability and Accommodation Decisions

Psychological evidence frequently contributes to decisions about disability status, reasonable accommodations and eligibility for services. These decisions are legal and administrative, not clinical, and the assessor's role is to supply evidence relevant to the criteria rather than to make the determination.

Knowing the framework

Each jurisdiction and institution defines disability and accommodation differently. The assessor should know the relevant definitions, the evidence required, the standard of proof and the decision-maker's criteria. Producing a clinical report that does not address the criteria is a common failure, and it is avoidable by reading the guidance before conducting the assessment.

The accommodation question

Accommodation decisions turn on three questions: whether the person has a functional limitation relative to the demands of the setting; whether an adjustment would remove or reduce the barrier; and whether the adjustment would fundamentally alter the nature of the activity or impose disproportionate cost. The assessor can contribute evidence on the first two and should be cautious about the third, which is usually a legal or managerial judgement.

Evidence quality

Where the decision has significant consequences, the evidence should be convergent: standardised measures, functional observation, history and, where relevant, medical documentation. Single-measure evidence is weak, and the assessor should say so rather than overstate confidence. Where the evidence is genuinely ambiguous, the report should present the ambiguity rather than resolve it in whichever direction seems kinder.

7.9 Career Assessment with Adults in Transition

Career transitions — redundancy, injury, migration, caring responsibilities, mid-life reassessment — are among the most common reasons for functional and vocational assessment in counselling psychology. They require an approach that integrates capacity, interest, values, context and opportunity.

The assessment frame

Transition assessment begins with the person's own account of the change and its meaning. A forced exit from a long-held role involves loss and identity disruption that will affect how any assessment is received. The assessor should establish what the person wants, what constraints they face, what resources they have and what they have already tried, before introducing standardised measures.

Integrating data

The integration combines three sources: the person's history of what they have done and enjoyed; standardised measures of interest, values and aptitude; and information about the labour market and training opportunities available to them. Where these conflict, the conflict is the material for counselling rather than for a verdict. A person whose interests point towards work their health cannot support requires a conversation about adaptation, not a recommendation that ignores one side of the evidence.

Realistic optimism

The assessor's responsibility is to be realistic without being discouraging. Evidence about prognosis, labour market conditions and the effects of support should be presented honestly, together with the evidence that targeted support substantially improves return-to-work outcomes for many groups. A report that presents only constraints is as unhelpful as one that presents only encouragement.

7.10 Integrating Educational and Career Data

Where an assessment covers both educational and occupational domains, integration is required to prevent contradictory recommendations. The most common contradiction arises where academic recommendations assume a level of support that the occupational recommendations do not, or where career recommendations assume a capacity that the cognitive findings do not support.

A coherence check

Before finalising such a report, the assessor should check that the recommendations are consistent with each other, consistent with the evidence, and feasible in the settings concerned. Where a recommendation depends on an assumption — that a school will provide a reader, that an employer will permit flexible hours — the assumption should be stated so that the reader can judge whether it holds.

Involving the person and the setting

Integration is improved by involving the client and, where appropriate, the receiving setting in the planning of recommendations. A recommendation developed with a school's special educational needs coordinator, or with an employer's occupational health adviser, is more likely to be implemented than one written in isolation. This is not a compromise of independence; it is an application of the principle that assessment should be useful.

7.11 Ethical Use of Occupational Tests

Occupational testing raises ethical issues that are less prominent in clinical assessment because the test-taker is often not the client, the results affect selection, and the assessor may be retained by the organisation.

Consent, feedback and access

Candidates have a right to know what is being assessed, to receive feedback in a form they can understand, and to have their data handled confiden-

tially. These rights are frequently poorly met in selection contexts, where tests are administered at scale and results are reported only to the employer. The psychologist's obligations do not disappear because the organisation is the client; they require negotiation at the outset.

Fairness and adverse impact

Selection tests that produce substantially different pass rates for different groups require justification on grounds of job relevance. The assessor should know whether the instrument has evidence of validity for the specific role and whether adverse impact has been examined, and should advise against instruments and cut scores that have not been justified. This is both an ethical and a legal requirement in many jurisdictions.

Prediction, not prophecy

Finally, occupational tests predict probabilities, not destinies. A test score that predicts a 60 per cent chance of satisfactory performance says nothing definitive about an individual, and using it as a cut-off has consequences that the assessor should be prepared to defend. Where the assessor is asked to make an individual decision from group data, the appropriate response is to state the limits of the prediction and to recommend the use of additional evidence.

7.12 Writing Functional Recommendations

Functional recommendations are the practical output of this family of assessments, and their quality determines whether the assessment has any effect. Table 7.2 contrasts weak and strong recommendations across common domains. Table 7.2 contrasts weak and strong functional recommendations.

Table 7.2. Weak and strong functional recommendations

Domain	Weak formulation	Strong formulation
Examinations	"Needs extra time"	"Twenty-five per cent additional time in written examinations, reviewed after one term against timed writing samples"
Reading	"Struggles with reading"	"Access to audiobooks for set texts; phonics-based intervention three times weekly for twelve weeks"
Medication	"Needs help with medication"	"Weekly blister pack prepared by a pharmacist; daily check by a support worker; review in eight weeks"
Workload	"Reduce stress at work"	"Maximum of two concurrent projects; written specifications for each; fortnightly supervision for the first three months"
Transport	"Unable to travel independently"	"Door-to-door transport for appointments; travel training assessment after three months"
Review	"Review as needed"	"Review after twelve weeks, with repeat of the timed reading measure and feedback from the line manager"

Principles

A strong recommendation names the action, the agent, the setting and the review point. It distinguishes what is required from what is desirable. It is proportionate to the evidence, and it does not smuggle in clinical claims that the assessment did not establish. It is written in language the implementing party can act on without further translation.

Implementation and review

Recommendations should be reviewed. A recommendation that has not been implemented is not evidence that the assessment was wrong, but it is information that the assessor should seek, because the reasons for non-implementation — cost, feasibility, misunderstanding — are usually remediable. Follow-up of a sample of recommendations is one of the most effective ways for a service to improve its reports.

Advanced Case Conference

The referral. A vocational rehabilitation service asks for assessment of a 41-year-old man who sustained a moderate traumatic brain injury two years ago in a road traffic collision. He wishes to return to work as a site electrician. The question is what support he would need and whether a return is realistic.

The assessment. Cognitive assessment shows high-average verbal ability, average perceptual reasoning, low-average working memory and borderline processing speed. Memory is average on recognition but weak on free recall, improving with structure. Executive measures show difficulty with planning and with inhibiting responses under time pressure. Fatigue is marked: performance declines across the session, and he reports needing two hours of rest each afternoon. He has not worked since the injury and has completed a part-time retraining course with support. Performance validity is adequate.

The reasoning. His technical knowledge is preserved and his recognition memory is adequate, so a return to work involving familiar procedures with written reference materials is plausible. The limiting factors are processing speed under time pressure, planning under novel conditions, and fatigue, all of which are hazardous on a construction site. A return to the full role without adjustment would place him and others at risk; a return to a modified role with supervision, written procedures and reduced hours is consistent with the evidence.

The decision. The report recommends a phased return over sixteen weeks, with a maximum six-hour day initially, no work at height or on live equipment until reviewed, written job specifications and a named mentor. It recommends that a risk assessment be conducted jointly with the employer, and that fatigue be monitored with a simple daily log. It states that the prognosis for a return to the full role is uncertain, and that the review at sixteen weeks should determine whether the modification becomes permanent.

The teaching point. The assessment's value lay in the specificity of the recommendation and in its explicit engagement with risk. A report that had said "fit for light duties" would have been unusable, and possibly dangerous.

Chapter Summary

Achievement, aptitude, adaptive behaviour and functional capacity are distinct constructs, and the assessor must match the instrument to the construct the decision requires. Academic assessment should identify the component skill that is impaired, because the instructional implication differs by component. Interest and values inventories are useful for broadening career exploration and should not be used prescriptively. Adaptive behaviour requires informant report and is conceptually distinct from ability. Functional capacity assessment must define the activity, distinguish capacity from performance and support, and engage with the legal or administrative criteria that frame the decision. Recommendations are the practical output of this work, and their quality depends on specificity, proportionality and a named review point.

Review Questions

1. Distinguish achievement, aptitude and ability, and explain why the distinction affects interpretation.
2. Why should reading assessment separate decoding from comprehension?
3. What does dynamic assessment add to static testing, and what are its limits?
4. Why is self-report a weak method for assessing adaptive behaviour?
5. Identify the four elements of a strong functional recommendation.

Discussion Questions

1. A school asks you to assess a student to support an application for additional funding. How do you manage the potential conflict between the school's interest and the child's?
2. Should interest inventories be used to steer young people away from occupations? Defend your position.

3. How would you assess functional capacity for a client who lives alone and has no informant?
4. What are the ethical obligations of a psychologist retained by an employer to test candidates?
5. How much weight should an assessor give to a client's stated career goal that the evidence suggests is unrealistic?

Further Reading

American Educational Research Association, American Psychological Association, & National Council on Measurement in Education. (2014). *Standards for educational and psychological testing*. American Educational Research Association.

Holland, J. L. (1997). *Making vocational choices: A theory of vocational personalities and work environments* (3rd ed.). Psychological Assessment Resources.

Fletcher, J. M., Lyon, G. R., Fuchs, L. S., & Barnes, M. A. (2019). *Learning disabilities: From identification to intervention* (2nd ed.). Guilford Press.

Sparrow, S. S., Cicchetti, D. V., & Saulnier, C. A. (2016). *Vineland Adaptive Behavior Scales* (3rd ed.). Pearson.

Sternberg, R. J., & Grigorenko, E. L. (2002). *Dynamic testing: The nature and measurement of learning potential*. Cambridge University Press.

World Health Organization. (2001). *International classification of functioning, disability and health*. World Health Organization.

PART III

Assessing Clinical Presentations

Mood, anxiety, obsessive-compulsive, trauma-related, bipolar, psychotic, substance-related and enduring personality presentations.

Chapter 8 · Chapter 9 · Chapter 10 · Chapter 11

CHAPTER 8

Assessment of Mood, Anxiety, Obsessive-Compulsive, Trauma and Stress-Related Problems

Learning Objectives

After working through this chapter, the reader should be able to:

- structure the assessment of depressive and anxiety presentations around differential reasoning;
- distinguish panic, social anxiety, generalised anxiety and obsessive-compulsive presentations;
- assess trauma exposure and post-traumatic symptomatology without assuming aetiology;
- appraise the boundary between adjustment reactions and clinical disorder;
- select and interpret severity measures for monitoring rather than labelling;
- conduct a functional analysis of avoidance that informs treatment planning.

Key terms: internalising spectrum · anhedonia · panic attack · agoraphobic avoidance · obsession · compulsion · intrusion · hyperarousal · adjustment disorder · comorbidity · functional analysis · severity monitoring · reliable change

Introduction

The internalising disorders — depression, the anxiety disorders, obsessive-compulsive disorder and the trauma- and stressor-related disorders — account for a large share of presentations in counselling psychology services. They are also the group for which the evidence base for assessment is

strongest: there are well-validated diagnostic interviews, severity measures with published norms, and a substantial literature on measurement-based care.

That strength carries a risk. Because these conditions are familiar, assessment is often conducted by pattern recognition, and because validated questionnaires are widely available, scores are often used as diagnoses. This chapter argues for a more disciplined approach: structured differential reasoning that considers the neighbouring conditions, careful attention to the boundary between disorder and ordinary distress, and the use of severity measures for monitoring and comparison rather than for labelling. Figure 8.1 maps the internalising spectrum and shows why overlapping presentations require explicit discrimination.




Figure 8.1. Assessment across the internalising spectrum. Overlapping presentations require explicit discrimination rather than reliance on the most salient symptom.

8.1 Assessing Depressive Presentations

Depression is the most common presentation in most adult mental health services and the one most often assessed inadequately. The core features — persistent low mood and loss of interest or pleasure — are widely known; what distinguishes a competent assessment is attention to course, severity, subtype, differential and risk.

Core features and their assessment

Low mood must be distinguished from the reactive sadness of ordinary disappointment, and anhedonia from the temporary withdrawal that follows loss. The assessor establishes pervasiveness across contexts, persistence across the day, and the presence of biological features: early waking, appetite change, psychomotor change and diurnal variation. These features have diagnostic and prognostic significance: early waking with diurnal worsening of mood suggests a melancholic picture, which responds differently to treatment from a reactive depression with preserved reactivity.

Course and subtype

Course questions establish whether the presentation is a first episode, a recurrence or a chronic state. The distinction between a major depressive episode superimposed on persistent depressive disorder and a first episode matters for prognosis and for the length of treatment recommended. Subtype questions — melancholic, atypical with hypersomnia and leaden paralysis, psychotic, seasonal, peripartum, catatonic — carry implications for treatment choice and for risk.

Severity and functional impact

Severity should be established by symptom count, functional impact and risk, not by a questionnaire score alone. A client with moderate symptoms who has stopped working, is neglecting self-care and has begun drinking heavily has a severe presentation whatever the score suggests. Severity measures are useful as a baseline for monitoring and as a check on clinical impression; they are not a substitute for either.

Differential and comorbidity

The differential includes bipolar disorder, substance-induced mood disorder, adjustment disorder, grief, thyroid disease and anaemia, medication effects, and the negative symptoms of schizophrenia. Bipolar disorder is the most consequential item to miss, and missing it can lead to harmful treatment. Any history of elevated mood, decreased need for sleep, increased

goal-directed activity or a family history of bipolar disorder requires specific enquiry, ideally with informant corroboration and prospective mood charting.

8.2 Assessing Anxiety Presentations

Anxiety disorders are heterogeneous, frequently comorbid with each other, and easily confused in unstructured assessment. The assessor's task is to identify the specific fear structure rather than to record a general elevation of anxiety.

The specific phobic and anxiety presentations

Panic disorder is characterised by recurrent unexpected panic attacks and persistent concern about further attacks or their consequences. Agoraphobia is characterised by fear of situations from which escape might be difficult or help unavailable. Social anxiety disorder involves fear of negative evaluation in social or performance situations. Generalised anxiety disorder involves excessive, difficult-to-control worry across multiple domains, accompanied by arousal symptoms. Separation anxiety disorder and selective mutism are relevant in younger populations.

Establishing the fear structure

For each presentation, the assessor establishes what is feared, what triggers it, what the person does to prevent or escape it, and what the consequences are. This information is more useful than a severity score, because it determines the treatment target. A client who fears the physical sensations of panic requires interoceptive work; a client who fears negative evaluation requires behavioural experiments in social situations; a client who fears that worry prevents disaster requires metacognitive work.

Generalised anxiety and its boundary with worry

Generalised anxiety disorder is the most difficult of the anxiety disorders to assess reliably, because worry is a universal experience and the boundary between normal and pathological worry is quantitative rather than qualit-

ative. The discriminating features are uncontrollability, pervasiveness across domains, duration of at least six months, and associated symptoms. The assessor should also consider whether the worry is secondary to another condition, such as health anxiety, obsessive-compulsive disorder or a depressive episode with ruminative thinking.

8.3 Panic and Agoraphobic Symptoms

Panic attacks are discrete episodes of intense fear accompanied by somatic and cognitive symptoms that peak within minutes. They are a feature of several disorders and are not a diagnosis in themselves; the diagnostic question concerns the pattern and the person's response to it.

Assessing the attack

A careful description establishes the symptoms present, their speed of onset, their peak intensity, their duration and the person's interpretation of them. The interpretation is central: a person who believes that palpitations signify a heart attack has a different maintaining mechanism from one who believes they are going to faint. The assessor should also establish whether attacks are unexpected, situationally bound or situationally predisposed, since this distinction shapes diagnosis.

Panic disorder with and without agoraphobia

The distinction between panic disorder and agoraphobia is not merely a matter of symptom count. Agoraphobic avoidance can occur without panic, and panic can occur without avoidance. Where avoidance is present, the assessor should map the avoided situations, the safety behaviours used, and the beliefs that sustain them. This map is the treatment plan in embryo.

Medical differential

Panic symptoms overlap with cardiac, respiratory, endocrine and neurological conditions, and with the effects of caffeine, stimulants and withdrawal states. A first presentation of panic in later life, panic with atypical features, or panic unresponsive to treatment warrants medical review. The as-

sessor should record what medical evaluation has occurred and what remains outstanding.

8.4 Obsessions and Compulsions

Obsessive-compulsive disorder is defined by obsessions (intrusive, unwanted thoughts, images or urges) and compulsions (repetitive behaviours or mental acts performed to reduce distress or prevent a feared outcome). It is frequently misdiagnosed as generalised anxiety, as depression, or as a personality characteristic such as perfectionism.

Distinguishing obsessions from ordinary intrusive thoughts

Intrusive thoughts are near-universal; what distinguishes clinical obsessions is their frequency, their appraisal as significant and threatening, the distress they cause, and the effort expended to neutralise them. The assessor should ask whether the person believes the thought is meaningful about them (thought–action fusion), whether they attempt to suppress or neutralise it, and how much time it consumes.

Assessing compulsions, including mental rituals

Compulsions are not always visible. Mental rituals — counting, praying, reviewing, replacing a thought with a safe thought, mentally checking — are common and easily missed. The assessor should ask directly about covert rituals and should ask about avoidance, since avoidance is functionally equivalent to a compulsion and often more disabling.

Subtypes, insight and related presentations

Subtypes include contamination, symmetry and ordering, forbidden or taboo thoughts, and hoarding, which is classified separately. The assessor should record the degree of insight: many people with OCD recognise that their fears are excessive, and a minority do not, which affects both diagnosis and engagement. Body dysmorphic disorder, trichotillomania, skin-picking disorder and olfactory reference syndrome are related presentations that should be screened where relevant.

8.5 Trauma Exposure and Post-Traumatic Symptoms

Trauma-related assessment requires attention to what happened, how the person has responded, and what the current symptom profile is. It also requires a discipline that is often absent: distinguishing the presence of trauma from the presence of post-traumatic stress disorder, since most people who experience trauma do not develop the disorder.

Establishing exposure

Exposure is established by asking about specific categories of event — serious accidents, physical or sexual assault, combat, natural disaster, sudden bereavement, childhood abuse, witnessing violence, and events experienced in a professional capacity — with attention to the person's own definition of what was traumatic. The assessor should record the nature of the event, its duration, the person's age at the time, the degree of threat to life or bodily integrity, and whether the event was interpersonal, since interpersonal trauma carries different prognostic and relational implications.

The symptom clusters

DSM-5-TR and ICD-11 organise post-traumatic symptoms differently. The DSM-5-TR clusters are intrusion, avoidance, negative alterations in cognition and mood, and alterations in arousal and reactivity, with a dissociative subtype; ICD-11 uses a narrower set of core symptoms (re-experiencing, avoidance and a sense of current threat) with optional disturbances in affect regulation, self-concept and relationships. The assessor should know which framework is being applied, because the two produce different thresholds for the same presentation.

Differential and comorbidity

The differential includes acute stress disorder, adjustment disorder, complex post-traumatic stress disorder, dissociative disorders, borderline personality disorder, psychotic disorders with trauma-related content, and traumatic brain injury. Comorbidity with depression, substance use and

chronic pain is the rule. Assessment should establish which condition is primary for treatment purposes, rather than assuming that all symptoms are trauma-related because a trauma is present.

8.6 Stress and Adjustment Problems

Adjustment disorder describes a maladaptive response to an identifiable stressor, with symptoms that do not meet criteria for another disorder, beginning within three months of the stressor and resolving within six months of its termination. Its inclusion in both DSM-5-TR and ICD-11 has been controversial, and its boundaries are genuinely uncertain.

The clinical problem

The central difficulty is that adjustment disorder is defined by exclusion: it applies when symptoms are clinically significant but do not meet criteria for another condition. This makes it both common and vulnerable to over--use, particularly in services where a diagnosis is required for access and the presentation is subthreshold. The assessor should therefore be explicit about which criteria are met and which conditions have been excluded, rather than using adjustment disorder as a default.

Distinguishing disorder from distress

The distinction between an understandable reaction and a disorder rests on severity, functional impairment, duration and the presence of symptoms beyond those expected for the stressor. Grief is the paradigm case: the DSM-5-TR removed the former bereavement exclusion from major depression, while retaining a category of prolonged grief disorder for reactions that persist and impair. The assessor should not pathologise normal grief, and should not dismiss persistent, impairing grief as normal.

Assessment tasks

Assessment establishes the nature and timing of the stressor, the person's appraisal of it, the symptoms, the functional impact, the available supports, and the person's own understanding. It should also establish what the per-

son has already tried and what they believe would help, since adjustment difficulties often respond to brief, practical intervention.

8.7 Somatic Overlap and Medical Explanations

Many presentations in this chapter include prominent somatic symptoms, and some are better explained by a medical condition. The assessor's obligation is to consider medical explanations, to record what has been excluded, and to avoid attributing to psychology what has not been medically evaluated.

Somatic presentations

Somatic symptom disorder, illness anxiety disorder, functional neurological symptoms and pain syndromes overlap substantially with anxiety and depression. The assessor should establish the history of medical investigation, the person's beliefs about their symptoms, the degree of functional impairment, and the pattern of health-care use. Where symptoms are disproportionate to identifiable disease, the assessment should address the psychological maintaining factors without implying that the symptoms are imaginary.

Medical mimics and contributors

Thyroid disease, anaemia, vitamin deficiency, sleep apnoea, chronic pain, medication effects, substance withdrawal and neurological conditions can all present with depressive or anxiety symptoms. The assessor should ask about recent investigations and should recommend medical review where symptoms are atypical, refractory or associated with physical signs. A collaborative relationship with the referring physician is the most efficient safeguard.

8.8 Severity Measures and Symptom Monitoring

Standardised severity measures improve the reliability of monitoring and support measurement-based care, in which treatment decisions are in-

formed by repeated measurement rather than by clinical impression alone. Their value depends on using them correctly.

Selecting a measure

The instrument should match the construct, the population and the purpose. Widely used examples include the Patient Health Questionnaire-9 for depression (Kroenke, Spitzer, & Williams, 2001), the Generalised Anxiety Disorder-7 for anxiety (Spitzer, Kroenke, Williams, & Löwe, 2006), the Yale–Brown Obsessive Compulsive Scale for OCD, and the PTSD Checklist for DSM-5. Each has published norms, cut scores and, in some cases, reliable change indices. The assessor should know the instrument's accuracy in the population being assessed, which frequently differs from the population in which it was validated.

Using measures for monitoring

For monitoring, the relevant properties are sensitivity to change, test–retest reliability in stable clients, and a reliable change index. A change that exceeds the reliable change index is unlikely to be measurement error; a change that does not may still be clinically meaningful, and the assessor should combine the score with functional information. Weekly or fortnightly administration is typical in treatment monitoring; the same instrument should be used throughout to permit comparison.

Avoiding the score-as-diagnosis error

A severity score is not a diagnosis. Scores above a cut-off indicate probable caseness and warrant diagnostic assessment; scores below it do not exclude significant difficulty, particularly where the instrument does not cover the person's presentation. The assessor should report scores with their confidence intervals, their percentile or severity band, and their date, and should never present a score as the basis for a diagnosis without a diagnostic interview.

8.9 Functional Analysis of Avoidance

Avoidance is the most important maintaining process across the internalising disorders. A functional analysis of avoidance identifies the situations avoided, the behaviours used to avoid or escape them, the short-term consequences that reinforce the avoidance, and the long-term costs that sustain the disorder.

The analysis

The analysis proceeds through four questions. What is the feared outcome? In which situations is it expected? What does the person do to prevent or escape it? What happens afterwards? The answers yield a formulation in which the avoidance is not a symptom to be removed but a solution that has become the problem: it reduces anxiety immediately and prevents disconfirmation in the long run.

Safety behaviours and subtle avoidance

Avoidance includes not only overt non-participation but subtle safety behaviours: gripping a handrail, carrying medication, rehearsing sentences, sitting near the exit, drinking alcohol before social events. These behaviours are often not reported unless specifically asked about, because they are experienced as sensible precautions rather than as avoidance. Their identification is essential, since treatment requires them to be dropped.

From analysis to plan

The functional analysis translates directly into a treatment plan: graded exposure to the avoided situations, elimination of safety behaviours, behavioural experiments designed to test the feared outcome, and monitoring of the predictions and their outcomes. Where the analysis cannot be conducted — because the client is unable to describe the pattern, or because the presentation is too acute — the assessment should record that and specify what needs to be established before treatment planning can proceed.

8.10 Differential Diagnosis Across Internalising Problems

The internalising disorders overlap substantially in symptoms, in comorbidity and in underlying temperament. Distinguishing among them requires attention to the specific content of fear and to the temporal pattern, rather than to symptom counts.

The common differentials

The most frequently confused pairs are generalised anxiety and major depression (both characterised by worry, sleep disturbance and fatigue); panic disorder and generalised anxiety (both involve arousal symptoms); social anxiety and avoidant personality disorder (both involve social fear and avoidance); obsessive-compulsive disorder and generalised anxiety (both involve repetitive worry); and post-traumatic stress disorder and adjustment disorder (both follow stressors).

Discriminating features

The discriminating features are usually specific: the presence of unexpected panic attacks; the presence of obsessions and compulsions; the presence of re-experiencing and avoidance of trauma reminders; the presence of a stable, lifelong pattern of social fear beginning in adolescence; the temporal relationship to a stressor. Table 8.1 sets out the principal distinctions. Table 8.1 compares the discriminating features of the internalising presentations most often confused in practice.

Table 8.1. Discriminating features among commonly confused internalising presentations

Presentation	Distinguishing feature	Frequent confusions
Major depressive episode	**Pervasive anhedonia; biological features; episode duration of at least two weeks**	**Grief; bipolar depression; adjustment disorder**
Generalised anxiety disorder	**Uncontrollable worry across multiple domains for at least six months**	**Depression with rumination; OCD; health anxiety**
Panic disorder	**Recurrent unexpected attacks with persistent concern about further attacks**	**Medical conditions; PTSD hyperarousal; social anxiety**
Social anxiety disorder	**Fear of negative evaluation in social or performance situations; early onset**	**Avoidant personality disorder; agoraphobia; autism**
Obsessive-compulsive disorder	**Obsessions with attempts to neutralise; covert and overt rituals; time consumed**	**Generalised anxiety; perfectionism; psychotic phenomena**
Post-traumatic stress disorder	**Re-experiencing, avoidance and current-threat symptoms after a qualifying event**	**Adjustment disorder; complex PTSD; dissociative disorders**
Adjustment disorder	Symptoms within three months of an identifiable stressor, not meeting another disorder	Subthreshold depression or anxiety; normal stress response

Comorbidity and hierarchy

Where criteria for several disorders are met, the assessor should record all of them rather than choosing one, and should identify which is primary for treatment. Diagnostic hierarchies — rules that give one disorder precedence — have been largely removed from the current classifications because they obscured clinically important comorbidity, and their removal requires the assessor to reason about priority explicitly.

8.11 Comorbidity and Diagnostic Hierarchy

Comorbidity is the norm in this group. Depression with anxiety, anxiety with substance use, OCD with depression, and PTSD with all of the above are common patterns rather than exceptions. The assessor's task is not to reduce the diagnoses to one but to establish which condition should be treated first and why.

Reasons for comorbidity

Comorbidity arises from shared risk factors (neuroticism, childhood adversity, genetic liability), from causal relationships (anxiety leading to depression, trauma leading to substance use), from overlapping diagnostic criteria, and from help-seeking patterns that bring comorbid people into services. Distinguishing these mechanisms matters for treatment: where one condition causes another, treating the cause may resolve both; where they are independent, both may require treatment.

Establishing priority

Priority is established by severity, by functional impact, by the client's own goals, by the presence of risk, and by the evidence on sequencing. Where depression is severe and anxiety moderate, treating depression first is usually appropriate; where panic is preventing engagement in treatment, treating panic first may be necessary. The reasoning should be recorded, because the next clinician will need to know why the order was chosen.

The single-diagnosis temptation

Services that require a single diagnosis for access create pressure to record only one condition. The assessor should resist this where the evidence supports comorbidity, and should record the additional diagnoses in a way that the service can accommodate — for example, as secondary diagnoses or as clinical formulation. Deliberately omitting a diagnosis to satisfy an administrative category is a misrepresentation of the evidence.

8.12 Integrated Formulation and Feedback

The output of assessment in this group is a formulation that links the presentation to its development, its maintenance and its treatment. It should explain why this person, at this time, has developed this particular pattern, and it should identify the points at which intervention is most likely to be effective.

Structure of the formulation

A workable structure moves through predisposing, precipitating, perpetuating and protective factors, and then specifies the maintaining mechanisms. The mechanisms should be stated in a form that predicts treatment response: if avoidance is the principal maintaining process, exposure should reduce symptoms; if rumination is maintaining depression, rumination-focused work should help.

Feedback

Feedback should present the formulation as a shared account rather than a verdict, use the client's own language where possible, invite correction, and connect the formulation to the treatment options. Where the assessment has identified a condition the client did not expect — bipolar disorder, OCD, PTSD — the feedback should include information about the condition, its treatability and the rationale for the proposed approach. Where it has excluded a condition the client expected, the exclusion should be explained rather than simply recorded.

Monitoring and review

The assessment should end with a monitoring plan: which measures will be repeated, at what intervals, and what change would prompt a revision of the formulation or the treatment. Measurement-based care is only as good as the arrangement that sustains it, and the assessment report is the natural place to establish that arrangement.

> **Advanced Case Conference**

The referral. A 26-year-old postgraduate student is referred by her general practitioner with "anxiety and low mood". She reports six months of difficulty sleeping, poor concentration and reluctance to attend seminars.

The assessment. Interview establishes that the difficulty began after a panic attack in a lecture theatre eight months earlier. She now avoids lecture theatres, travels by a longer route that avoids the underground, and has stopped attending seminars. She carries water at all times and sits near exits. She has not had a second full panic attack, but experiences near-attacks several times a week. She describes low mood and anhedonia over the last three months, and scores in the moderately severe range on a depression measure and the moderate range on an anxiety measure. She reports no elevated mood, no obsessions or compulsions, and no trauma history. She drinks alcohol only socially.

The reasoning. The presentation is best explained by panic disorder with agoraphobic avoidance, with a secondary depressive episode that developed as the avoidance restricted her life. The reverse order — primary depression with secondary anxiety — is less consistent with the clear onset at a panic attack and the specific situational avoidance. The near-attacks and safety behaviours indicate that the panic disorder remains active despite the absence of full attacks. The depression is clinically significant and would need treatment in its own right if it persisted after the panic was addressed.

The decision. The report records panic disorder with agoraphobia and a moderate depressive episode, identifies the avoidance and safety behaviours as the principal maintaining processes, and recommends a course of cognitive behavioural therapy with interoceptive and situational exposure, alongside monitoring of mood. It recommends review at eight weeks, with a decision about separate treatment for depression if mood has not improved as the avoidance reduces.

The teaching point. The presenting complaint was "anxiety and low mood"; the assessment found a specific, treatable fear structure. The functional analysis of avoidance generated the treatment plan, and the diagnostic sequence determined which condition to treat first.

Chapter Summary

Assessment of the internalising disorders requires specific differential reasoning rather than general enquiry. Depression must be assessed for course, subtype, severity and bipolarity, and bipolar disorder must be actively excluded. Anxiety presentations are distinguished by their fear structure, which also determines the treatment target. Obsessive-compulsive disorder is defined by obsessions and by rituals that are frequently covert. Trauma exposure is not equivalent to post-traumatic stress disorder, and assessment must establish both. Adjustment disorder is defined by exclusion and is vulnerable to over-use. Severity measures support monitoring but do not establish diagnosis. The functional analysis of avoidance links assessment to treatment, and the integrated formulation should state maintaining mechanisms in a form that predicts response.

Review Questions

1. Why is a severity score insufficient to establish the diagnosis of a depressive episode?
2. Distinguish panic disorder from generalised anxiety disorder in terms of the fear structure.
3. What are covert compulsions, and why are they important to ask about?
4. Explain why trauma exposure does not establish post-traumatic stress disorder.
5. What is the difference between capacity and performance in a functional analysis of avoidance?

Discussion Questions

1. A client's depression score is in the mild range, but she has stopped working and is drinking heavily. How do you report severity?
2. How should an assessor respond when a service requires a single diagnosis for a client who meets criteria for three?

3. Is adjustment disorder a useful diagnosis? Argue both sides.
4. How would you assess a client whose panic symptoms might be cardiac in origin?
5. What are the risks of using a cut score to determine access to treatment?

Further Reading

American Psychiatric Association. (2022). *Diagnostic and statistical manual of mental disorders* (5th ed., text rev.). American Psychiatric Association Publishing.

Barlow, D. H. (2004). *Anxiety and its disorders: The nature and treatment of anxiety and panic* (2nd ed.). Guilford Press.

Kroenke, K., Spitzer, R. L., & Williams, J. B. W. (2001). The PHQ-9: Validity of a brief depression severity measure. *Journal of General Internal Medicine, 16*(9), 606–613.

Spitzer, R. L., Kroenke, K., Williams, J. B. W., & Löwe, B. (2006). A brief measure for assessing generalized anxiety disorder: The GAD-7. *Archives of Internal Medicine, 166*(10), 1092–1097.

World Health Organization. (2024). *Clinical descriptions and diagnostic requirements for ICD-11 mental, behavioural and neurodevelopmental disorders*. World Health Organization.

CHAPTER 9

Assessment of Bipolar, Psychotic and Other Severe Mental Disorders

Learning Objectives

After working through this chapter, the reader should be able to:

- recognise manic and hypomanic presentations and distinguish them from other elevated states;
- assess psychotic experiences systematically across sensory modality, content and form;
- evaluate thought form and thought content without conflating observation with inference;
- distinguish negative symptoms from depression, demoralisation and medication effects;
- appraise developmental and cultural explanations for unusual experiences;
- assess insight, judgement and decision-making capacity;
- communicate findings in severe presentations with appropriate attention to risk and uncertainty.

Key terms: mania · hypomania · psychosis · delusion · hallucination · thought disorder · negative symptoms · insight · capacity · first-episode psychosis · schizoaffective disorder · cultural formulation · provisional diagnosis

Introduction

Severe mental disorders present assessment challenges of a different order from those discussed in the previous chapter. Symptoms may be subtle, intermittently present, concealed or denied; the client may lack insight into the very experiences the assessor needs to describe; informants may be unavailable or may themselves be distressed; and the consequences of error — involuntary treatment, loss of liberty, misattributed psychosis — are substantial.

Assessment in this group is also where the distinction between description and inference is most consequential. "The client reports that the television is sending messages" is an observation. "The client has delusions of reference" is an inference, and it requires evidence about conviction, cultural explanations, context and the client's own understanding. This chapter develops the observational discipline that severe presentations demand, together with the reasoning required to place observations within a differential that includes medical, substance-related and cultural explanations. Figure 9.1 sets out the domains assessed in severe presentations and the way in which evidence from one domain bears on another.




Figure 9.1. Assessment of severe presentations. Each domain supplies evidence that may support or undermine the others, and no single domain is decisive.

9.1 Recognising Manic and Hypomanic Presentations

Mania and hypomania are defined by a distinct period of abnormally and persistently elevated, expansive or irritable mood, accompanied by increased energy and goal-directed activity, lasting at least one week for mania and at least four consecutive days for hypomania. Mania causes marked impairment, requires hospitalisation or includes psychotic features; hypomania does not.

The clinical features

The features to establish are elevated or irritable mood; inflated self-esteem or grandiosity; decreased need for sleep; pressured speech; flight of ideas or subjective experience of racing thoughts; distractibility; increased goal-directed activity or psychomotor agitation; and excessive involvement in activities with high potential for painful consequences. The assessor should establish the presence of each, its duration, its departure from the person's usual functioning and its consequences.

The diagnostic difficulty

Two difficulties dominate. The first is retrospective recall: clients in a euthymic state frequently do not recall elevated periods accurately, and may describe them as their normal self. Informant report and contemporaneous records are therefore essential, and prospective mood charting is often the only reliable method. The second is the boundary with normality: increased energy and reduced sleep in the context of a new relationship, a creative project or a stimulant are not necessarily hypomania, and the distinction depends on departure from the person's baseline, persistence and consequences.

Bipolar spectrum and its mimics

The differential includes bipolar I disorder, bipolar II disorder, cyclothymia, substance-induced mood disorder, mood disorder due to another medical condition, attention-deficit/hyperactivity disorder, borderline per-

sonality disorder and major depression with agitated features. Antidepressant-induced hypomania is a recognised phenomenon and should be recorded where it occurs, since it alters the treatment implications substantially.

9.2 Assessing Psychotic Experiences

Psychosis is a descriptive term for experiences such as hallucinations, delusions and disorganised thinking that indicate a loss of contact with consensual reality. Assessment requires systematic description of the experience rather than classification by label.

Hallucinations

The assessor establishes the modality (auditory, visual, tactile, olfactory, gustatory), the content, the location (inside or outside the head), the person's relationship to the voice or image, the degree of conviction, the frequency and the circumstances in which it occurs. Auditory verbal hallucinations are the most common in psychotic disorders; visual hallucinations are more often associated with medical and neurological conditions, substance use or delirium, and should prompt medical review.

Delusions

A delusion is a fixed false belief that is not amenable to change in the light of conflicting evidence and is not explicable by the person's cultural context. The assessor records the content, the onset, the degree of conviction, the extent to which the belief preoccupies the person, the emotional response to it, and the behaviours that follow from it. Beliefs should be recorded in the person's own words before being characterised.

Distinguishing psychotic from non-psychotic unusual experiences

Many people report unusual experiences without disorder: hearing one's name when falling asleep, sensing a presence, holding strongly held beliefs shared within a community. The discriminating features are frequency, distress, impairment, conviction despite disconfirmation, and the extent to

which the experiences dominate the person's life. The assessor should also consider dissociation, obsessive-compulsive phenomena with poor insight, and culturally normative experiences such as contact with the deceased in the context of bereavement.

9.3 Thought Form and Thought Content

Thought form concerns the structure and flow of speech and writing; thought content concerns what is thought about. The distinction is central to the assessment of severe presentations and is frequently blurred in reports.

Disorders of thought form

Thought form is assessed by observation of speech: rate, quantity, continuity, logical connection and goal direction. Descriptors include circumstantiality (over-inclusive but ultimately goal-directed), tangentiality (departing from the topic without returning), loosening of associations (connections between ideas that the listener cannot follow), derailment, incoherence or word salad, neologisms, clanging and perseveration. Each should be illustrated with a brief quoted example, since the descriptors are used inconsistently across examiners.

Disorders of thought content

Thought content includes delusions, overvalued ideas, obsessions, preoccupations and suicidal or homicidal ideation. The distinction between a delusion and an overvalued idea is a matter of degree of conviction and resistance to evidence, and the assessor should record the degree rather than assigning a category at the boundary. Somatic, persecutory, grandiose, referential, religious, erotomanic, jealous and nihilistic contents each carry different differential implications.

Recording accurately

The record should distinguish observation from inference explicitly. Quotation is the most reliable method: "He stated that his neighbours had in-

stalled equipment that 'reads my thoughts through the wall'" is more informative than "persecutory delusions". Where a quotation would identify the client or breach confidentiality, a close paraphrase should be used and marked as such.

9.4 Negative Symptoms and Functional Decline

Negative symptoms — blunted affect, alogia, avolition, anhedonia and asociality — predict functional outcome in psychotic disorders more strongly than positive symptoms do. They are also easily confused with depression, with medication effects and with demoralisation.

The distinction from depression

The overlap is substantial: both involve reduced motivation, reduced pleasure and social withdrawal. The discriminating features include the presence of depressed mood and guilt in depression, the presence of hopelessness and suicidality in depression, and the relative preservation of anticipatory pleasure in some negative symptom presentations. Structured instruments for negative symptoms improve reliability, but the distinction often requires longitudinal observation.

The distinction from medication effects

Antipsychotic medications, particularly at higher doses, produce parkinsonism, akathisia and sedation that mimic negative symptoms. The assessor should review the medication regimen, look for extrapyramidal signs, and consider whether the symptoms appeared or worsened after a dose change. A rating of negative symptoms obtained without this review is unreliable.

Functional decline

Functional decline is often the most consequential feature of severe disorders and the least well assessed. The assessor should establish the person's premorbid level of functioning, the trajectory of decline, the domains affected (work, relationships, self-care, independent living) and the extent to which the decline is attributable to symptoms, to medication, to stigma and

lost opportunity, or to the illness's effects on motivation. This distinction matters because the interventions differ.

9.5 Mood Disorders with Psychotic Features

Psychotic symptoms occurring in the context of a mood episode raise the differential between psychotic disorders with mood symptoms, mood disorders with psychotic features and schizoaffective disorder. The distinction rests on the temporal relationship between mood and psychotic symptoms.

The temporal rule

Where psychotic symptoms occur exclusively during mood episodes, a mood disorder with psychotic features is the more parsimonious diagnosis. Where psychotic symptoms persist for at least two weeks in the absence of a mood episode, the balance shifts towards a primary psychotic disorder. Where mood episodes are present for the majority of the total duration of illness and psychotic symptoms occur in their absence, schizoaffective disorder may be considered. These rules are applied to the longitudinal course, not to a single cross-section.

The assessment implication

The implication is that a single assessment cannot usually resolve the differential. The assessor should obtain a longitudinal history from the client and an informant, review records, and construct a timeline of mood and psychotic symptoms across the illness. Where the timeline cannot be established, the correct output is a provisional diagnosis with a stated review point.

Treatment implications

The distinction matters for treatment: mood stabilisers, antidepressants and antipsychotics are used differently, and the risk of antidepressant-induced mania or of relapse differs. The assessor's report should therefore state the differential explicitly and indicate what evidence would resolve it,

rather than recording a single diagnosis that implies a certainty the evidence does not support.

9.6 Substance-Induced and Medical Presentations

Substance use and medical conditions are among the most common causes of psychotic symptoms, and excluding them is a prerequisite for diagnosing a primary psychotic disorder.

Substance-induced psychosis

Stimulants, cannabis, hallucinogens, alcohol withdrawal and novel psychoactive substances can all produce psychotic symptoms. The assessor should establish the substance, the dose, the timing relative to symptom onset, the duration of symptoms after cessation, and whether previous episodes occurred in the absence of substance use. A first episode of psychosis in a heavy cannabis user requires a period of abstinence before a primary diagnosis can be made with confidence.

Medical causes

Delirium, temporal lobe epilepsy, autoimmune encephalitis, thyroid disease, vitamin B12 deficiency, Wilson's disease, HIV-related illness, neurosyphilis, brain tumours and prescribed medications can all produce psychotic symptoms. Certain features should prompt urgent medical referral: first episode in later life, fluctuating consciousness, focal neurological signs, visual or tactile hallucinations, and rapid deterioration. The assessor should not manage these presentations alone.

Recording the exclusion

The report should state what has been excluded, on what evidence and by whom. "Medical causes were considered; thyroid function and B12 were normal on testing reported by the general practitioner; no neuroimaging has been performed" is informative. Silence on the matter is not.

9.7 Developmental and Cultural Explanations

Unusual experiences occur in the context of developmental conditions and cultural frameworks, and both must be considered before a psychotic disorder is diagnosed.

Autism and unusual experiences

Autistic adults may report sensory experiences, idiosyncratic beliefs and difficulty distinguishing intended meaning that are misread as psychotic. The assessor should consider developmental history, the lifelong pattern of social communication differences, and the person's own account of their experience. Misattributing autism to psychosis is a well-recognised source of harm, particularly for people who have not previously been assessed.

Cultural and religious frameworks

Beliefs that would be delusional in one cultural context may be normative in another: spiritual possession, communication with ancestors, belief in the evil eye, and experiences interpreted within religious practice. The assessor must establish whether the belief is shared within the person's community, whether it is consistent with the person's cultural background, and whether it causes distress or impairment. The DSM-5-TR cultural formulation interview provides a structured method for this enquiry, and its use is appropriate whenever the assessor's cultural knowledge is limited.

The limits of cultural explanation

Cultural explanation should not be used to dismiss genuine psychopathology, nor should psychopathology be diagnosed because a belief is unfamiliar to the assessor. The appropriate procedure is to generate both explanations, to seek information from the client's community where possible, and to record the reasoning. Consultation with a cultural informant or a clinician familiar with the client's background is often the most efficient way to resolve the question.

9.8 Collateral History and Longitudinal Evidence

Severe disorders are chronic conditions whose diagnosis depends on course. A single interview, however thorough, samples a moment; the diagnosis requires a trajectory. Collateral history and longitudinal evidence are therefore not optional supplements but core methods.

Sources

Informants include partners, parents, siblings, friends, employers, landlords and clinicians who have known the person over time. Records include psychiatric admissions, general practice notes, school reports, occupational records and criminal justice records where lawful and relevant. Each source has its own perspective and its own limits, and the assessor should record who provided what and when.

Constructing a longitudinal timeline

The timeline should record the onset of each symptom domain, the pattern of episodes, the response to treatment, the level of functioning between episodes, and the occurrence of any periods of remission. This timeline is the single most useful document in the assessment of a severe disorder, and constructing it with the client and an informant is often more informative than any instrument.

When collateral is unavailable

Where collateral is refused or unavailable, the assessor should record the fact and its implications for confidence. In some circumstances — particularly where the client's account is the only evidence — the report should say so explicitly and should state what conclusions are and are not supported.

9.9 Insight, Judgement and Decision-Making Capacity

Insight and capacity are related but distinct concepts. Insight refers to the person's awareness and understanding of their condition; capacity refers to

their ability to make a specific decision at a specific time. Confusing the two leads to the erroneous conclusion that a person who lacks insight into their illness also lacks capacity to make treatment decisions.

Assessing insight

Insight is best assessed dimensionally: awareness of symptoms, attribution of symptoms to a condition, awareness of the need for treatment, and awareness of the likely consequences of non-treatment. Each dimension can be rated separately, and the pattern is often informative — a person may accept that they have an illness but reject medication, or deny the illness while complying with treatment for other reasons.

Assessing capacity

Capacity assessment follows a functional test defined by the relevant jurisdiction, typically requiring that the person can understand the relevant information, retain it, weigh it in the decision, and communicate their decision. The assessor should use the statutory framework where one exists, record the specific decision being assessed, present information in accessible form, and repeat the assessment if the person's condition fluctuates. A general statement that the client "lacks capacity" is uninformative and usually wrong.

The interface with risk

Where capacity is impaired and risk is significant, the legal framework for involuntary intervention will apply. The assessor's role is to provide the evidence on which that decision is made, not to make it. Documentation should distinguish the clinical findings from the legal determination.

9.10 Risk and Immediate Safety Needs

Risk assessment in severe presentations requires attention to suicide, self-neglect, violence, exploitation and vulnerability, each of which is treated in Chapter 15. The present section addresses the specific features of severe presentations that alter risk.

Elevated risk in psychotic and manic states

Risk is elevated during acute psychosis, particularly where command hallucinations, persecutory beliefs involving specific individuals, or disorganised behaviour are present. Mania carries risk of harm through impulsive behaviour, financial ruin, sexual risk-taking and accidents. Depression with psychotic features carries particularly high suicide risk, especially where the person believes they deserve punishment or that their family would be better off without them.

Assessment tasks

The assessor should establish ideation, intent, plan, means, previous attempts, protective factors, the person's beliefs about the future, and the availability of support. Where psychosis is present, the assessor should ask directly whether the voices or beliefs involve harming self or others, and whether the person feels they must comply. Where risk is elevated, the assessment should include a safety plan and clear arrangements for follow-up.

Documentation

Risk documentation should record what was asked, what was disclosed, what was observed, the assessor's judgement and the reasoning, the actions taken and the communication with other parties. It should be specific enough to withstand later scrutiny and clear enough to be acted upon by a colleague who reads it in an emergency.

9.11 Diagnostic Uncertainty and Provisional Conclusions

Severe presentations frequently generate diagnostic uncertainty that cannot be resolved at assessment. The professional response is not to select the most plausible category and present it as settled, but to record the uncertainty in usable form.

Forms of uncertainty

Uncertainty may concern the presence of a symptom (was that a hallucination or an intrusive thought?), the temporal relationship between symptom domains, the contribution of substances, the boundary with a personality disorder or a developmental condition, or the trajectory of the illness. Each form requires a different kind of evidence to resolve, and the report should specify which.

Provisional diagnoses

A provisional diagnosis should be stated as such, with the evidence supporting it, the alternatives considered, and the observations that would change it. This is not a failure of confidence but an accurate description of the state of the evidence, and it is more useful to the treating team than a premature certainty that later has to be reversed — a reversal that damages the client's trust and the assessor's credibility.

Review points

Every provisional conclusion should carry a review point: a date or a clinical event at which the diagnosis will be reconsidered. In early psychosis services, where diagnostic stability is low, this practice is standard; it is equally appropriate in general services.

9.12 Communicating Findings in Severe Presentations

Communication in severe presentations carries additional weight: the report may inform decisions about liberty, treatment and parenting, and may be read by the client at a time of considerable vulnerability.

Language and stigma

Reports should describe behaviour and experience rather than using diagnostic labels as adjectives for the person. "He described hearing a voice commenting on his actions" is preferable to "he is psychotic", both because

it is more informative and because it is less stigmatising. Terms such as "manipulative", "attention-seeking" and "non-compliant" should be avoided unless the behaviour is described and the inference justified.

Communication with the client

Feedback to a person in an acute episode must be adapted: shorter, concrete, checked for comprehension and repeated later. Where the client disagrees with the conclusions, the disagreement should be recorded rather than overridden, and the client's own account should appear in the report. This is both an ethical requirement and a source of information; clients often identify errors in the factual record.

Communication with other professionals

Reports should specify what the receiving team should do, what should be monitored, and what would constitute a deterioration. The most useful reports in severe presentations are those that a duty clinician can act on at two in the morning: clear, specific and prioritised.

Advanced Case Conference

The referral. A 23-year-old man is brought to a crisis service by his parents. He has stopped attending university, is sleeping three hours a night and has told his parents that his neighbours are "testing a device" on him. The question is whether he should be admitted.

The assessment. He is cooperative but guarded. Speech is rapid and pressured; he describes his thoughts as "moving faster than I can speak". He reports hearing a man's voice commenting on his behaviour, which he locates outside his head and attributes to the neighbours' device. He denies any mood elevation when asked directly, but his parents describe three weeks of unusually elevated mood, increased spending and uncharacteristic irritability, and report that he has not slept more than four hours in that period. He has used cannabis weekly for two years but not in the past month. He denies suicidal ideation and any intention to harm his neighbours, though he says he has considered "confronting them". He does not believe he is unwell and does not want treatment.

The reasoning. The presentation includes both psychotic and manic features. The temporal relationship matters: the elevated mood and reduced need for sleep preceded the persecutory beliefs by approximately two weeks. If the mood features are primary, a manic episode with psychotic features is the more parsimonious diagnosis; if the psychosis persists beyond the mood episode, the differential would broaden. Substance contribution is possible but he reports a month of abstinence, which reduces its likelihood without excluding it. Medical causes have not been investigated.

The decision. The report records a provisional diagnosis of a manic episode with psychotic features, recommends admission for assessment and treatment, and specifies that medical investigation should include thyroid function, a toxicology screen and neuroimaging if clinically indicated. It records that capacity to consent to treatment is impaired for the specific decision of accepting admission, with the reasoning, and that the statutory framework for involuntary assessment has been invoked. It notes that the diagnosis should be reviewed once the acute episode has resolved and once a period of abstinence has been confirmed.

The teaching point. The assessment did not settle the diagnosis, and saying so was correct. What it did settle was the immediate decision, the framework for it, and the observations that would resolve the diagnostic question later.

Chapter Summary

Mania and hypomania are defined by episode duration, departure from baseline and consequences, and their assessment depends on informant report and longitudinal evidence. Psychotic experiences should be described before they are classified, with attention to modality, content, conviction and context. Thought form and thought content are distinct, and both are best recorded with examples. Negative symptoms must be distinguished from depression, demoralisation and medication effects. Mood–psychosis timing determines the differential among mood disorders with psychotic features, primary psychotic disorders and schizoaffective disorder, and usually requires longitudinal data. Substance and medical causes must be excluded and the exclusions recorded. Developmental and cultural explanations must be considered without being used to dismiss genuine disorder.

Insight and capacity are distinct, and capacity is decision-specific. Uncertainty should be documented as provisional conclusions with review points, and communication should describe experience rather than label persons.

Review Questions

1. What distinguishes mania from hypomania, and why does the distinction matter for treatment?
2. Why should visual hallucinations prompt medical review?
3. Distinguish thought form from thought content, giving two examples of each.
4. Why are negative symptoms easily confused with depression, and how can the two be distinguished?
5. Explain the difference between insight and decision-making capacity.

Discussion Questions

1. A client denies any mood elevation but the informant describes clear hypomanic episodes. How do you proceed?
2. How should an assessor handle a religious belief that the family shares but that the assessor finds unusual?
3. What are the risks of diagnosing a primary psychotic disorder in a heavy cannabis user after a single assessment?
4. How would you give feedback about a diagnosis of schizophrenia to a client who does not believe they are unwell?
5. Should a provisional diagnosis ever be recorded as a definitive one to secure access to services?

Further Reading

American Psychiatric Association. (2022). *Diagnostic and statistical manual of mental disorders* (5th ed., text rev.). American Psychiatric Association Publishing.

Andreasen, N. C. (1984). *The Scale for the Assessment of Positive Symptoms (SAPS)*. University of Iowa.

First, M. B., Williams, J. B. W., Karg, R. S., & Spitzer, R. L. (2016). *Structured Clinical Interview for DSM-5 Disorders, Clinician Version (SCID-5-CV)*. American Psychiatric Association Publishing.

Lincoln, T. M., & Pedersen, A. (2019). *An overview of the psychosis continuum and its assessment*. In C. A. Essau & P. H. Oppen (Eds.), *Assessment of mental health problems*. Oxford University Press.

World Health Organization. (2024). *Clinical descriptions and diagnostic requirements for ICD-11 mental, behavioural and neurodevelopmental disorders*. World Health Organization.

CHAPTER 10

Assessment of Personality Disorders and Enduring Relational Patterns

Learning Objectives

After working through this chapter, the reader should be able to:

- define enduring personality patterns and the criteria that distinguish disorder from variation;
- compare trait-based and categorical approaches to personality disorder diagnosis;
- assess identity, self-direction, empathy and intimacy as dimensions of personality functioning;
- gather longitudinal and developmental evidence for stability;
- distinguish state effects, trauma responses and developmental conditions from personality disorder;
- conduct structured personality interviews with appropriate caution;
- provide feedback and formulation that reduce stigma rather than reinforcing it.

Key terms: personality disorder · level of personality functioning · trait domain · categorical diagnosis · state–trait confound · complex trauma · differential diagnosis · structured interview · labelling · iatrogenic harm · formulation

Introduction

Personality disorder diagnosis occupies a difficult position in mental health practice. It identifies a group of people with substantial and enduring difficulties who are often poorly served by services; it also carries a history of pejorative use that has caused measurable harm. The diagnosis can open access to specialist treatment or close it; it can support a formulation or replace one; it can be communicated respectfully or used as a description of a person's worth.

This chapter approaches the topic through two commitments. The first is that personality disorder is a disorder of functioning, not a defect of character: what is assessed is the severity of impairment in self and interpersonal functioning, together with the traits that characterise it. The second is that the assessment must be longitudinal, developmental and contextual. A personality disorder cannot be diagnosed from a single interview in an acute crisis, and much of the harm associated with the diagnosis has come from doing exactly that. Figure 10.1 shows how severity, traits, development and context must converge before a diagnosis of personality disorder is warranted.




Figure 10.1. Assessment of personality disorder. Severity, traits, development and context must converge before a diagnosis is warranted.

10.1 Understanding Enduring Personality Patterns

Personality refers to the relatively stable organisation of the psychological characteristics that make a person recognisable across time and situation. A personality pattern becomes a disorder when it is inflexible, pervasive, stable over time, and associated with clinically significant distress or impairment in social, occupational or other important areas of functioning.

The criteria for disorder

Four criteria do most of the work. The pattern must be enduring and pervasive rather than situation-specific; it must deviate markedly from cultural expectations in more than one domain; it must be stable and of long duration, with onset traceable to adolescence or early adulthood; and it must cause distress or impairment. The criterion of cultural deviation requires care: what is a disorder in one cultural setting may be conformity in another, and the assessor must know which expectations apply.

Stability and its limits

Longitudinal research has shown that personality disorder criteria are less stable than the diagnosis implies: many people who meet criteria in early adulthood no longer do so a decade later, and the remission is often substantial. Traits are more stable than symptoms, and impairment is more stable than either, which is one reason contemporary models emphasise functioning rather than criterion counts. The practical implication is that a diagnosis made in early adulthood should not be treated as a life sentence, and that reassessment over time is appropriate.

Enduring relational patterns

Much of what is clinically important about personality disorder is expressed in relationships: the expectation of abandonment, the alternation between idealisation and devaluation, the avoidance of intimacy, the pursuit of approval, the need for control. These patterns are more informative to assess than individual criteria, because they describe mechanism, and they translate directly into formulation and treatment.

10.2 Trait-Based and Categorical Approaches

Two broad approaches to classification coexist: categorical, in which disorders are defined by polythetic criteria; and dimensional, in which personality is described along continuous dimensions of functioning and traits.

The categorical approach

The categorical approach, exemplified by the DSM-5-TR criteria for the specific personality disorders, has the advantages of familiarity, clinical utility in communication and administrative recognition. It has well-documented disadvantages: extensive comorbidity and overlap among categories, arbitrary thresholds, heterogeneity within categories (two people with the same diagnosis may share no criteria), and poor coverage of presentations that do not fit a named category.

The dimensional approach

The dimensional approach describes severity of impairment in personality functioning and the particular maladaptive traits that characterise the person. Both DSM-5-TR, through its alternative model, and ICD-11, through its severity-based classification, adopt this structure. Its advantages are that it captures severity, reduces comorbidity artefacts, accommodates subthreshold presentations and aligns with the evidence on the continuous distribution of personality pathology. Its disadvantages are complexity, unfamiliarity and imperfect correspondence with administrative systems.

Combining them

For practical purposes, the assessor can combine the approaches: establish the severity of impairment dimensionally, describe the trait profile, and translate into a categorical diagnosis where one is required for communication or access. This produces reports that are both recognisable and accurate, and it avoids the choice between a system that is familiar and a system that is better.

10.3 Identity and Self-Functioning

The self domain of personality functioning comprises identity and self-direction. Both are assessed through interview and observation, and both are central to the severity judgement.

Identity

Identity refers to the experience of a coherent and differentiated sense of self, with stable self-esteem and an accurate appraisal of one's capacities and limitations. Impairment is evident in a self-concept that shifts markedly with circumstances or relationships, in self-esteem that fluctuates between extremes, in an inability to describe oneself beyond a few characteristics, and in a fragile sense of boundaries between self and others. The assessor can explore identity by asking the client to describe themselves, what they value, what they would be like without their current difficulties, and how they have changed over time; the coherence and stability of the answer is the data.

Self-direction

Self-direction refers to the pursuit of meaningful short- and longer-term goals, and the capacity to use self-reflection productively. Impairment is evident in goals that change unpredictably, in an absence of goals, in goals that are not connected to the person's capacities, and in an inability to learn from experience. Assessment requires enquiry into the person's plans, their history of pursuing them, and their explanation for what has not worked.

Assessment methods

Identity and self-direction are assessed primarily by interview, supported by self-report instruments designed for the dimensional model, by informants who know the person across contexts, and by observation of the person's capacity to reflect within the assessment session itself. A client who can describe their difficulties with nuance and connect them to their history demonstrates a level of self-functioning that a checklist cannot capture.

10.4 Interpersonal Functioning

The interpersonal domain comprises empathy and intimacy. These functions determine much of the person's relational life and much of the difficulty that brings them to services.

Empathy

Empathy comprises the capacity to understand and appreciate others' experiences and motives, and the capacity to consider alternative perspectives. Impairment ranges from a relative insensitivity to others' feelings, through an ability to understand intellectually but not to be moved, to a marked inability to consider others as separate psychological beings. Assessment is by interview, by exploration of specific relationships, and by observation of the client's behaviour in the session — including the client's response to the assessor's attempts to express a different perspective.

Intimacy

Intimacy refers to the capacity for enduring, close and mutually satisfying relationships. Impairment is evident in relationships that are shallow, unstable, exploitative or marked by fear; in an inability to tolerate closeness or to maintain connections across conflict; and in patterns of pursuing then withdrawing. Enquiry should cover the number and duration of close relationships, the pattern of their endings, the person's account of why they ended, and the account of an informant where available.

Relational patterns in the assessment relationship

The client's way of relating is enacted in the assessment. Idealisation of the assessor, devaluation, withdrawal, compliance, testing behaviour and seductiveness are all observable, and all are data. The assessor should record them descriptively, without interpretation in the moment, and use them in the formulation: what happens between assessor and client is often a sample of what happens elsewhere.

10.5 Longitudinal and Developmental Evidence

Personality disorder is by definition enduring, and the evidence for endurance must be longitudinal. A single cross-sectional assessment cannot establish that a pattern has been present since adolescence or that it is stable across contexts.

Historical sources

Sources include the person's own account of their adolescence and early adulthood, school reports, employment records, accounts of family and friends, and previous clinical records. The assessor should look for a pattern that predates the presenting problem and that appears across contexts: the difficulties at school, the repeated job losses, the friendships that ended for the same reason, the family's longstanding description of the person as "always like this".

The developmental trajectory

The trajectory matters: a pattern that appeared abruptly at 30 after a trauma is not a personality disorder, even if the current presentation resembles one. The assessor should establish the age at which the pattern was first evident, its consistency across development, and any periods of relative remission. Where the history is ambiguous, the diagnosis should be provisional and the ambiguity recorded.

The problem of retrospective reconstruction

Clients reconstruct their history in the light of their present understanding, and a person who has recently received a personality disorder diagnosis may describe their adolescence through that lens. The assessor should prefer contemporaneous evidence — records, informant accounts — and should treat retrospective accounts as informative about the person's current self-understanding as well as about their history.

10.6 Differentiating State from Trait

The most consequential differential in this area is between an enduring pattern and a current state. Depression, anxiety, psychosis, substance use, acute stress and physical illness can all produce behaviour that resembles personality pathology.

State effects on personality measurement

Acute depression inflates scores on scales measuring dependency, self-criticism, neuroticism and interpersonal sensitivity. Acute anxiety inflates scores on scales measuring avoidance and suspiciousness. Substance use inflates scores on scales measuring impulsivity and hostility. Psychosis distorts self-report entirely. Assessing personality during an acute episode therefore risks a diagnosis that describes the episode rather than the person.

Practical guidance

The practical guidance is to defer personality assessment until the acute state has resolved, or to interpret scores obtained during an acute state with explicit caution. Where deferral is impossible — because the assessment is required for an urgent decision — the assessor should use informant and historical data, record the state effects, and state the limits of the conclusion. This is one of the clearest cases in which "the assessment cannot answer this question now" is the correct professional output.

The differential with other conditions

The differential includes bipolar disorder (where mood instability may resemble affective instability), autism spectrum disorder (where social difficulties may resemble schizoid or avoidant patterns), complex post-traumatic stress disorder (where affect dysregulation and identity disturbance may resemble borderline patterns), attention-deficit/hyperactivity disorder (where impulsivity may resemble antisocial or borderline features), and substance use disorders. Each requires its own assessment rather than being subsumed under a personality diagnosis.

10.7 Personality and Trauma

The relationship between trauma and personality disorder is clinically important and conceptually contested. Many people with severe personality disorder have histories of significant adversity; many people with significant adversity do not develop personality disorder.

Complex trauma

The ICD-11 diagnosis of complex post-traumatic stress disorder describes a presentation arising after prolonged or repeated trauma, characterised by the core PTSD symptoms plus disturbances in affect regulation, self-concept and relational functioning. Its overlap with borderline personality disorder is substantial, and the two are often used interchangeably in practice despite being distinct constructs with different evidence bases. The assessor should determine whether the core PTSD symptoms are present; if they are, complex PTSD is the more specific diagnosis.

Trauma as an explanatory framework

Where trauma is present, it provides an explanatory framework for the pattern: hypervigilance, mistrust, emotional dysregulation, avoidance of intimacy and a diminished sense of self can all be understood as adaptations to an unsafe environment. This framing is more useful clinically than a trait description, because it identifies targets for intervention and conveys that the pattern made sense. It does not, however, remove the need for an accurate description of current functioning.

Avoiding false attribution

The converse error is attributing all difficulty to trauma and failing to consider other explanations, including conditions that require different treatment. A client with an autism spectrum condition and a trauma history may receive only a trauma formulation and miss the support that would address the developmental condition. The assessor should generate both explanations and test them.

10.8 Personality and Neurodevelopmental Conditions

Autism spectrum disorder and attention-deficit/hyperactivity disorder are frequently misdiagnosed as personality disorders, and vice versa, with serious consequences for treatment.

Autism

Autistic adults may present with social withdrawal, literalism, intense special interests, sensory sensitivities and difficulty understanding social expectations. These features may be read as schizoid, avoidant or obsessive-compulsive patterns. The distinguishing evidence is developmental: a lifelong pattern of social communication difference, sensory features, and a history of social difficulty that predates the onset of other symptoms. Assessment requires a developmental history, ideally with an informant, and consideration of structured instruments for autistic traits where indicated.

Attention-deficit/hyperactivity disorder

Adults with ADHD may present with impulsivity, emotional dysregulation and unstable relationships, features that overlap with borderline and antisocial patterns. The distinguishing evidence is again developmental — onset in childhood, pervasive inattention or hyperactivity, and a consistent pattern across contexts — together with response to treatment. Where both conditions are present, both should be diagnosed.

The implication

The implication is that a personality disorder diagnosis should not be made without a developmental history. Where the developmental history is unavailable, the diagnosis should be provisional, and the possibility of a neurodevelopmental condition should be recorded.

10.9 Personality and Substance Use

Substance use complicates personality assessment in three ways: it can produce behaviour that resembles personality pathology; it can be a consequence of personality difficulties; and it can be both.

Substance-induced behaviour

Intoxication and withdrawal produce impulsivity, irritability, affective instability, suspiciousness and interpersonal conflict. A personality assessment conducted during a period of active substance use is unreliable, and the assessor should establish the pattern of use, the periods of abstinence and the behaviour during abstinence.

Differential considerations

Antisocial and borderline features are common in people with substance use disorders, and the question is whether the personality features preceded the substance use and persist in its absence, or whether they are consequences of it. The answer requires a history that separates the two, and it usually requires a period of abstinence before a firm conclusion is possible.

Combined presentation

Where both are present, both should be diagnosed and treated. The historical practice of withholding treatment for personality difficulties until substance use has resolved has been challenged on both ethical and empirical grounds, and services increasingly offer integrated treatment. The assessor's report should support integrated planning rather than a sequential demand that the client may be unable to meet.

10.10 Structured Personality Interviews

Structured and semi-structured interviews for personality disorder improve the reliability of diagnosis and reduce the influence of the assessor's impressions. They are time-consuming, require training, and are under-used in routine practice.

Available instruments

The Structured Clinical Interview for DSM-5 Personality Disorders (SCID-5-PD; First, Williams, Benjamin, & Spitzer, 2016) assesses the categorical diagnoses. The Structured Clinical Interview for the DSM-5 Alternative Model for Personality Disorders (SCID-5-AMPD) assesses the level of personality functioning and the trait domains. The International Personality Disorder Examination and the Schedules for Clinical Assessment in Neuropsychiatry provide alternative approaches. Each has strengths and a training requirement; none replaces the need for developmental and collateral information.

Using them well

A structured personality interview should be used with a client who is not in an acute state, with sufficient time to cover the domains, and with the assessor's attention to the interpersonal process as well as the content. The interview's structure supports reliability, but the assessor still has to decide whether the reported pattern is enduring, pervasive and impairing, which requires judgement beyond the instrument.

Their limits

Structured interviews assess reported experience at a point in time. They do not establish the developmental history, they do not capture the interpersonal process of the assessment, and they cannot distinguish state from trait without additional information. Their output is a set of criteria met, which is the beginning rather than the end of the assessment.

10.11 Feedback without Stigma

Feedback on personality assessment is where the diagnosis either helps or harms. There is good evidence that the way a diagnosis is communicated affects how it is received, how the client engages with treatment and how other professionals treat the client.

Principles

Feedback should be explanatory rather than evaluative, describe patterns and their origins rather than traits as defects, be specific and behavioural, invite correction, and connect to treatment. It should acknowledge the difficulty of hearing the information and the client's own expertise about themselves. It should avoid words with a history of pejorative use where a descriptive alternative exists.

Discussing the diagnosis

Where a personality disorder diagnosis is given, the assessor should explain what it means and what it does not mean: that it describes a pattern of difficulty that developed in response to circumstances, that it is not a judgement of the person's worth, that it can change, and that effective treatments exist. The assessor should also explain why the diagnosis is being recorded, since clients often experience the diagnosis as a label applied without consent.

The record as a document the client may read

Clinical records are increasingly accessible to clients, and the language used in them has consequences. Descriptions should be written as though the client will read them, which improves both accuracy and respect. Pejorative terms, speculation presented as fact, and irrelevant personal detail should be excluded.

10.12 Formulating Enduring Relational Patterns

The formulation is the point at which assessment becomes useful. It should explain how the pattern developed, what it achieves for the person, what it costs, and what would need to change.

Structure

A useful structure describes the core pattern (for example, anticipating rejection and withdrawing pre-emptively), its developmental origins (a history in which expressing needs led to humiliation), its maintaining pro-

cesses (withdrawal produces relief and prevents disconfirmation), its costs (isolation, depression, lost opportunities) and its adaptive value (protection from further humiliation). It then identifies the point of intervention: the moment between the anticipation and the withdrawal.

Testability

The formulation should be testable: if it is right, then a specified intervention should produce a specified change, and a specified observation should disconfirm it. A formulation that cannot be wrong is not a formulation.

Sharing the formulation

The formulation should be shared with the client in accessible language and revised in the light of their response. Clients frequently improve a formulation by correcting the assessor's account of their history, and the process of discussing it can itself be therapeutic, since it models curiosity about the pattern rather than judgement of the person.

> **Advanced Case Conference**
>
> **The referral.** A 29-year-old woman is referred by her general practitioner after her third presentation at an emergency department in six months with selfharm. The general practitioner asks whether she has a personality disorder and what would help.
>
> **The evidence.** She describes a longstanding pattern of intense relationships that end abruptly, a self-concept that changes depending on who she is with, chronic feelings of emptiness, and recurrent self-harm in response to perceived rejection. The pattern began in adolescence and has been present across contexts. She has a history of childhood emotional abuse and neglect. She currently meets criteria for a moderate depressive episode and reports daily cannabis use. She has had two courses of therapy, both of which ended after a few sessions when she felt the therapist was "losing interest". A structured interview confirms impairment in identity, self-direction, empathy and intimacy, with prominent negative affectivity and disinhibition.

The reasoning. The pattern is enduring, pervasive and impairing, and it predates the current depressive episode. Complex PTSD must be considered: she describes hypervigilance and avoidance but does not report re-experiencing or a sense of current threat of the kind required. The cannabis use may be exacerbating the affective instability but does not explain the developmental pattern. The repeated treatment endings are the most important clinical fact in the assessment, because they predict what will happen with the next treatment.

The decision. The report records a personality disorder of moderate severity with a provisional complex PTSD differential, documents the depressive episode and the substance use as co-occurring conditions requiring attention, and recommends a structured treatment with an explicit frame, agreement about contact between sessions, and a single named coordinator. It specifies that the repeated endings should be anticipated and used as clinical material rather than treated as treatment failure. It records the client's own explanation of the endings and her goals for treatment.

The teaching point. The diagnosis was less important than the pattern it described, and the pattern's most useful expression was in the treatment history. The recommendation followed from that history, not from the label.

Chapter Summary

Personality disorder is a disorder of functioning rather than a defect of character, and its assessment requires evidence of endurance, pervasiveness and impairment. Contemporary models describe severity of impairment in self and interpersonal functioning together with maladaptive traits, which is more informative than categorical diagnosis alone. Identity, self-direction, empathy and intimacy are assessed by interview, informant report and observation of the assessment relationship. Longitudinal and developmental evidence is essential, and the differential with state effects, trauma, neurodevelopmental conditions and substance use must be worked through before a diagnosis is made. Structured interviews improve reliability without replacing judgement. Feedback and formulation determine whether the assessment helps, and both should be explanatory, specific and free of stigmatising language.

Review Questions

1. What four criteria distinguish a personality pattern from a personality disorder?
2. Why is severity of impairment more informative than the number of criteria met?
3. How would you distinguish complex post-traumatic stress disorder from borderline personality disorder?
4. What evidence would suggest that a personality diagnosis made in an acute episode is unreliable?
5. Identify three features of feedback that reduce stigma.

Discussion Questions

1. Should personality disorder diagnoses be given to people under eighteen? Argue both positions.
2. How do you assess a client whose developmental history is unavailable?
3. What are the risks of diagnosing personality disorder in an autistic adult, and how can they be avoided?
4. How should a service respond when a client's pattern repeatedly ends treatment?
5. Is it ethical to record a personality disorder diagnosis that the client does not accept?

Further Reading

American Psychiatric Association. (2022). *Diagnostic and statistical manual of mental disorders* (5th ed., text rev.). American Psychiatric Association Publishing.

First, M. B., Williams, J. B. W., Benjamin, L. S., & Spitzer, R. L. (2016). *Structured Clinical Interview for DSM-5 Personality Disorders (SCID-5-PD)*. American Psychiatric Association Publishing.

Livesley, W. J., & Larstone, R. (2018). *Handbook of personality disorders: Theory, research, and treatment* (2nd ed.). Guilford Press.

Paris, J. (2020). *Social factors in the personality disorders: Finding a niche* (2nd ed.). Cambridge University Press.

World Health Organization. (2024). *Clinical descriptions and diagnostic requirements for ICD-11 mental, behavioural and neurodevelopmental disorders*. World Health Organization.

CHAPTER 11

Assessment of Substance Use, Behavioural Addictions and Risk Behaviour

Learning Objectives

After working through this chapter, the reader should be able to:

- describe patterns of substance use using quantity, frequency and consequence measures;
- select and interpret screening instruments and understand their limitations;
- assess intoxication and withdrawal states and recognise when medical referral is required;
- evaluate severity and functional consequences using current diagnostic frameworks;
- distinguish substance-induced from independent mental symptoms;
- assess behavioural addictions without over-extending the concept;
- evaluate motivation and readiness for change without treating stages as fixed;
- integrate substance-related and other findings into a coherent formulation.

Key terms: harmful use · dependence · tolerance · withdrawal · polysubstance use · substance-induced disorder · behavioural addiction · motivation · readiness for change · harm reduction · biological markers · integrated formulation

Introduction

Substance use is simultaneously one of the most prevalent clinical issues and one of the most poorly assessed. It is under-detected in general services, under-reported by clients who fear judgement, and frequently recorded as a binary — "uses alcohol: yes/no" — in records that require far more detail to be useful. The consequences of poor assessment are substantial: missed diagnoses, inappropriate treatment, unsafe prescribing and avoidable deaths.

This chapter sets out a systematic approach. It begins with description: what is being used, how much, how often, with what consequences and with what pattern of control. It proceeds to screening and case finding, to the assessment of intoxication and withdrawal, to severity and functional consequences, and to the distinction between substance-induced and independent mental symptoms. It then addresses behavioural addictions, motivation, risk and harm reduction, and closes with integrated formulation. Throughout, the emphasis is on the practical questions that determine what should happen next. Figure 11.1 orders the assessment of substance use: description and consequence are established before context is weighed and a plan is made.




Figure 11.1. Assessment of substance use. Description, consequence and context must be established before diagnosis or planning.

11.1 Patterns of Substance Use

Adequate description requires four elements: substance, quantity, frequency and pattern. Each element carries information that the others do not.

Quantity and frequency

Quantity and frequency questions should be specific to the substance and expressed in units the client uses. For alcohol, standard units or drinks per week, together with the pattern of heavy episodic drinking, is more informative than "moderate" or "social". For cannabis, the quantity is often expressed in grams per week or joints per day, and the potency varies substantially. For stimulants, opioids and novel substances, the pattern of use — daily, binge, weekend — often matters more than the quantity.

Pattern and control

The pattern includes the time of day, the context, the triggers, the company, the duration of a typical episode, and the person's capacity to stop once started. Loss of control is a defining feature of dependence and is best assessed by asking about specific occasions rather than about general capacity: the number of times in the past month the person intended to have one drink and had more.

Consequences and their assessment

Consequences include health, family, occupational, financial, legal and psychological domains. The assessor should ask about each specifically, since clients tend to report the consequences they consider acceptable and to omit those that carry shame. Useful prompts include missed work, arguments, injuries, blackouts, driving after drinking, borrowing money, and symptoms on waking.

11.2 Screening and Case Finding

Screening identifies people who may have a substance problem and who warrant fuller assessment. It is not a diagnosis, and its value depends on the setting and on what follows a positive result.

Instruments

The Alcohol Use Disorders Identification Test (AUDIT; Saunders, Aasland, Babor, de la Fuente, & Grant, 1993) is the most widely validated alcohol screen and includes items on consumption, dependence symptoms and consequences. The AUDIT-C is a shorter consumption-only version suitable for high-volume settings. The Drug Abuse Screening Test provides a parallel instrument for other substances. Single-item screens are useful where time is very limited but have lower sensitivity, particularly for women and older adults.

Interpretation in context

Screening accuracy varies by setting, by population and by the threshold used. A positive screen in a general hospital population warrants a brief intervention and a fuller assessment; a positive screen in a substance treatment service is nearly uninformative, because almost everyone will screen positive. The assessor should know the prevalence of problematic use in the setting and should interpret the screen accordingly, in the manner described in Chapter 3.

What to do with a positive screen

A positive screen should lead to a structured assessment covering the four elements above, an assessment of risk, a brief intervention where appropriate, and a clear plan. Screening without follow-up is a waste of the client's time and can be actively harmful if it raises concerns that are not addressed.

11.3 Intoxication and Withdrawal

Intoxication and withdrawal are medical states with psychological consequences, and their assessment is a prerequisite for any psychological conclusion drawn during or shortly after them.

Intoxication

Intoxication impairs cognition, emotion regulation and judgement, and it distorts self-report. Assessment during intoxication should be limited to safety, orientation and the immediate presenting problem; a full psychiatric assessment conducted during intoxication is unreliable and should be repeated when the client is sober. The assessor should record the substances involved, the amount, the time of last use, and the observed signs.

Withdrawal

Withdrawal syndromes vary by substance: alcohol and benzodiazepine withdrawal can be life-threatening and require medical management; opioid withdrawal is extremely distressing but rarely fatal; stimulant withdrawal produces depression, anhedonia and fatigue that may be mistaken for a depressive disorder. The assessor should ask about the onset and pattern of withdrawal symptoms, the client's previous withdrawal experiences, and whether medical support is available.

Medical risk and referral

Certain situations require urgent medical referral: suspected alcohol withdrawal with tremor, sweating and confusion; benzodiazepine withdrawal after high-dose use; opioid overdose or recent overdose; chest pain or arrhythmia in a stimulant user; and any presentation with fever, rigidity or altered consciousness. The assessor's responsibility is to recognise these and to act, not to manage them.

11.4 Severity and Functional Consequences

Both major classifications have revised their approach to substance-related disorders. DSM-5-TR uses a single category of substance use disorder, graded as mild, moderate or severe according to the number of criteria met, and removes the former distinction between abuse and dependence. ICD-11 distinguishes harmful patterns of use from dependence, with dependence defined by a smaller set of core features including impaired control, increased priority, physiological features and continued use despite harm.

Assessing severity

Severity assessment should combine criteria counts with functional consequences, because the two are not perfectly correlated. A person meeting few criteria but experiencing severe social and occupational consequences has a serious problem. The assessor should record the criteria met, the consequences, and the client's own view of severity, which is often more conservative than the evidence warrants and sometimes more accurate.

Functional consequences

The domains to assess are health (including injuries, infections and chronic disease), mental health, relationships, parenting, employment and education, finances and housing, and legal status. Each should be recorded specifically: not "social problems" but "two relationships ended in the past year following arguments while drinking; currently living alone after partner left".

The social context

Substance use occurs in a context that shapes both the pattern and the options for change. Housing, employment, social networks, availability, criminal justice involvement and stigma all matter. An assessment that describes the individual without describing the context will produce recommendations that cannot be implemented.

11.5 Polysubstance Use

Most people in treatment for substance problems use more than one substance, and the combinations carry risks that single-substance assessment misses.

Patterns

Common patterns include alcohol with benzodiazepines (a particularly dangerous combination), alcohol with cocaine (where the alcohol prolongs and intensifies the cocaine effect), opioids with stimulants, cannabis with alcohol, and the use of prescribed medication with alcohol or illicit substances. The assessor should ask about each substance separately, including prescribed medication used outside its prescription and over-the-counter medication.

Assessment

A substance-by-substance grid recording substance, route, quantity, frequency, duration, last use and consequences is the most efficient method. The grid also reveals patterns that the narrative conceals, such as weekend stimulant use with weekday alcohol, and it is easy to share with the client for correction.

Risk

The principal risks of polysubstance use are pharmacokinetic interaction (particularly respiratory depression with alcohol and opioids or benzodiazepines), increased toxicity, more severe withdrawal, and greater difficulty in identifying which substance is producing which symptom. The assessor should record the combinations and flag the ones that carry medical risk.

11.6 Substance-Induced Mental Symptoms

Substances produce psychiatric symptoms that are often indistinguishable from primary mental disorders at a single assessment. The distinction mat-

ters because the treatment differs, and because a misattributed disorder can persist for years in the records.

Presentation

Substance-induced conditions include substance-induced depressive disorder, anxiety disorder, psychotic disorder and bipolar disorder, as well as substance intoxication delirium and substance withdrawal delirium. The temporal criteria require that symptoms develop during or shortly after intoxication or withdrawal, and that they are not better explained by an independent disorder.

Establishing the relationship

The assessor should establish the temporal sequence, the substances involved, the dose and duration, the persistence of symptoms after cessation, and whether similar symptoms have occurred without substance use. A period of abstinence is usually necessary before the diagnosis can be made with confidence; where abstinence is not feasible, the diagnosis should be provisional and the uncertainty recorded.

The reverse error

The reverse error is to attribute all symptoms to substance use when an independent disorder is present. Many people with severe mental illness use substances, and the substance use may be a consequence of the disorder, a form of self-medication, or an independent problem. The assessor should generate both explanations and look for the evidence that discriminates them, rather than defaulting to the substance explanation because it is simpler.

11.7 Behavioural Addictions

Behavioural addictions — gambling, gaming, problematic internet use, compulsive sexual behaviour, shopping and others — share features with substance use disorders but differ in important ways.

Gambling disorder and gaming disorder

Gambling disorder is recognised in DSM-5-TR as a behavioural addiction within the substance-related and addictive disorders chapter, supported by evidence on phenomenology, neurobiology and treatment. Gaming disorder is recognised in ICD-11, with a definition requiring impaired control, increasing priority and continuation despite negative consequences for at least twelve months. Both have structured assessment instruments and evidence-based treatments.

The boundaries of the concept

The extension of the addiction framework to other behaviours is contested. Criteria developed for substances do not map neatly onto behaviours that are, in moderation, normal and necessary, such as internet use, eating or sexual activity. The assessor should be cautious about applying an addiction label to behaviours where the evidence base is thin, and should focus instead on functional impairment and the pattern of the behaviour.

Assessment approach

Whatever the behaviour, the assessment should establish the pattern (frequency, duration, escalation), the function (what it does for the person), the consequences, the person's attempts to control it and their outcome, the co-occurring conditions, and the context. This functional approach is more robust than the application of a checklist, and it produces information that informs treatment.

11.8 Motivation and Readiness for Change

Motivation is not a fixed trait but a fluctuating state influenced by the person's circumstances, their experience of treatment, and their relationship with the practitioner. The assessment of motivation should be an assessment of the person's own reasons, not of their compliance with the assessor's goals.

Models and their status

The transtheoretical model of change, with its stages of precontemplation, contemplation, preparation, action and maintenance, has been enormously influential and is used in services throughout the world. Its empirical support as a predictive model is modest, and its stage categories are not reliably measurable; its practical value lies in reminding practitioners that change is a process and that interventions should match the person's current position. Motivational interviewing, which developed alongside the model, has much stronger evidence for effectiveness in substance misuse treatment.

Assessing motivation

Useful questions explore the person's own view: what they like about using, what concerns them, what would need to change for them to consider stopping or reducing, what they have tried before, and what happened. The balance of these considerations, in the client's own words, is more informative than a readiness score. Where the client has no concerns and no intention to change, that is a finding, and the appropriate response is to maintain engagement and reduce harm rather than to press for a commitment the client does not have.

The ethical dimension

Motivation assessment is easily corrupted into an assessment of whether the client will do what the service wants. The ethical position is that the client's goals set the frame, that the practitioner offers information and options, and that coercion — whether from the criminal justice system, an employer or a family — must be recognised explicitly and its effect on the assessment recorded.

11.9 Medical and Social Risk

Substance use carries risks beyond dependence, and these should be assessed systematically in every case.

Medical risk

Risks include overdose, infection (including blood-borne viruses from injecting), injuries (including road traffic collisions and falls), liver disease, cardiovascular disease, neurological damage, and interactions with prescribed medication. The assessor should establish injecting status and injecting practices, sharing of equipment, history of overdose, and current medical conditions, and should ensure that testing and vaccination are offered where relevant.

Social and legal risk

Risks include loss of employment or housing, relationship breakdown, child safeguarding concerns, involvement in acquisitive crime, exploitation and victimisation. Where children are present in the household, the assessor has an obligation to consider their welfare and to follow local safeguarding procedures. Where the client is involved in the criminal justice system, the assessment should record this and its implications for treatment options.

Suicide risk

Substance use is one of the strongest risk factors for suicide, both acutely during intoxication and chronically through its association with depression, impulsivity and social isolation. Suicide risk should be assessed in every substance use assessment, and the assessment should record what was asked and what was disclosed.

11.10 Collateral Data and Biological Measures

Because self-report of substance use is affected by memory, shame and fear of consequences, collateral and biological data are valuable supplements. Neither is a substitute for the clinical interview.

Collateral sources

Partners, family members, employers and treatment records can supply information that the client omits. Collateral should be obtained with consent and should focus on observable behaviour: what the informant has seen,

when, and with what consequences. Where the client declines collateral contact, the assessor should record the refusal and its effect on confidence.

Biological measures

Biological measures include blood alcohol concentration, breath testing, urine and hair drug testing, and biomarkers such as liver enzymes (gamma-glutamyl transferase, mean corpuscular volume) and carbohydrate-deficient transferrin. Each has a detection window, a sensitivity and a specificity, and each can be affected by factors unrelated to recent use. A positive test establishes exposure, not impairment, dependence or the pattern of use; a negative test does not establish abstinence over a long period, because the window may have closed.

Interpretation and consent

Biological testing requires consent, an explanation of what will be tested and why, and clarity about who will see the results. In medico-legal and employment contexts, the consequences of a positive result can be severe, and the assessor should be explicit about the limits of what the test establishes. Where testing is used to monitor treatment, the results should be interpreted alongside clinical information rather than as a verdict.

11.11 Assessment for Harm Reduction Planning

Harm reduction accepts that some people will continue to use substances and aims to reduce the harms associated with use rather than to require abstinence as a precondition of help. Its evidence base is strong for a range of interventions, and its principles are relevant to assessment even where the service's model is abstinence-oriented.

Assessment for harm reduction

The assessment identifies the specific harms the person is at risk of and the practical steps that would reduce them: overdose risk and the availability of naloxone; injecting practices and access to sterile equipment; driving and alcohol; mixing substances; sexual health; and the safety of the environments

in which use occurs. It also identifies the person's own priorities, which may be housing, money or relationships rather than substance use itself.

The clinical stance

Harm reduction requires a non-judgemental stance that nonetheless maintains accurate assessment. The practitioner should be honest about risk, specific about what can be done, and clear that any reduction in harm is a legitimate outcome. This stance is compatible with supporting abstinence where that is the client's goal; it is incompatible with withholding help from people who are not ready to stop.

Integration with treatment

Harm reduction planning should be integrated with the rest of the treatment plan, including mental health treatment, medical care and social support. A plan that addresses substance use in isolation from housing, employment and mental health is unlikely to succeed.

11.12 Integrated Diagnostic Formulation

The output of assessment is a formulation that explains the relationship between substance use, mental health, context and consequences, and that identifies the points at which intervention is likely to be effective.

The key questions

A useful formulation answers four questions. What is the pattern of use and what function does it serve? What are the co-occurring conditions, and how do they interact with the substance use? What maintains the pattern — dependence, social context, untreated symptoms, limited alternatives, or some combination? What would need to change for the pattern to change, and in what order?

Sequencing

The formulation should inform sequencing. Where withdrawal is medically risky, medical management comes first. Where a co-occurring disorder

is severe and the substance use is a form of self-medication, treating the disorder may reduce use. Where the substance use is primary and severe, substance treatment may need to precede psychological work. Where the pattern is maintained by housing instability or isolation, social intervention may be the most effective first step.

Recording uncertainty and integration

As elsewhere, the formulation should state what is known, what is inferred and what remains uncertain, and it should specify the review points at which the formulation will be tested. The most useful reports in this area are those that a client could read, recognise and use, and that a treatment team could act on.

Advanced Case Conference

The referral. A 38-year-old man is referred by his general practitioner with "depression and anxiety". He has been drinking heavily for two years and has had two short courses of antidepressants with no benefit.

The assessment. He drinks approximately sixty units of alcohol per week, mostly in the evening, with a pattern of heavy weekend drinking. He reports morning tremor relieved by drinking, has twice tried to stop and experienced sweating and palpitations, and has missed work on several days each month. He describes low mood, anhedonia and early waking, which he dates to the period after his divorce two years ago, and which he reports does not lift during periods of abstinence of a few weeks. He has panic symptoms in crowded places, which he manages by drinking before going out. His liver function tests are mildly abnormal. He reports no suicidal ideation but says he "would not mind not waking up".

The reasoning. Two explanations compete: a primary depressive and anxiety disorder with secondary alcohol use, and an alcohol-induced mood disorder with a dependence syndrome. The persistence of low mood during several weeks of abstinence and the onset after a major life event support the first. The morning drinking and withdrawal symptoms indicate dependence requiring medical management. The panic symptoms are situationally triggered and may be independent, exacerbated by alcohol, or a consequence of repeated cycles of intoxication and withdrawal.

The decision. The report records harmful alcohol use with dependence, a depressive episode that appears independent of drinking, and panic symptoms requiring separate assessment. It recommends medically supervised alcohol withdrawal before any change in antidepressant treatment, treatment for depression in parallel with substance treatment, and an assessment for panic disorder once drinking has stabilised. It records the suicide risk assessment and a safety plan.

The teaching point. The interaction between depression and alcohol is the whole assessment. The mistake would have been to treat either alone.

Chapter Summary

Substance use assessment requires description of substance, quantity, frequency and pattern, followed by consequences across health, social and occupational domains. Screening instruments identify probable cases and depend on the setting's prevalence for their interpretation. Intoxication and withdrawal are medical states that distort psychological assessment and may require urgent referral. Severity combines criteria counts with functional consequences, and both major classifications now describe a graded continuum rather than a categorical distinction between abuse and dependence. Polysubstance use requires a substance-by-substance approach. Substance-induced and independent mental symptoms must be distinguished, usually with a period of abstinence. Behavioural addictions are recognised where the evidence supports them and should not be extended beyond it. Motivation is a fluctuating state to be assessed from the client's own perspective, and harm reduction provides a framework for working with people who are not ready to stop. The integrated formulation should explain the relationships among use, mental health and context, and inform sequencing.

Review Questions

1. Why is "moderate" a poor description of alcohol consumption?

2. What does a positive AUDIT screen establish, and what does it not establish?
3. Why should a full psychiatric assessment not be conducted during intoxication?
4. How would you distinguish a substance-induced depressive disorder from major depression?
5. What are the limits of biological testing in establishing patterns of substance use?

Discussion Questions

1. A client is referred by a court and must abstain to avoid imprisonment. How does this affect the assessment of motivation?
2. How should an assessor respond when a client's self-report and a hair test give different pictures?
3. Should harm reduction be offered in a service with an abstinence-based policy?
4. What are the safeguarding issues when a client with dependent children uses substances?
5. How would you formulate a case where depression and alcohol use appear to maintain each other?

Further Reading

Babor, T. F., Higgins-Biddle, J. C., Saunders, J. B., & Monteiro, M. G. (2001). *AUDIT: The Alcohol Use Disorders Identification Test: Guidelines for use in primary care* (2nd ed.). World Health Organization.

Miller, W. R., & Rollnick, S. (2013). *Motivational interviewing: Helping people change* (3rd ed.). Guilford Press.

Nutt, D. J., King, L. A., Saulsbury, W., & Blakemore, C. (2007). Development of a rational scale to assess the harm of drugs of potential misuse. *The Lancet, 369*(9566), 1047–1053.

Saunders, J. B., Aasland, O. G., Babor, T. F., de la Fuente, J. R., & Grant, M. (1993). Development of the Alcohol Use Disorders Identification Test (AUDIT): WHO collaborative project on early detection of persons with harmful alcohol consumption—II. *Addiction, 88*(6), 791–804.

World Health Organization. (2024). *Clinical descriptions and diagnostic requirements for ICD-11 mental, behavioural and neurodevelopmental disorders*. World Health Organization.

PART IV

Development, Culture and Relational Systems

Children and adolescents, couples and families, and the cultural, linguistic and disability considerations that condition every interpretation.

Chapter 12 · Chapter 13 · Chapter 14

CHAPTER 12

Child and Adolescent Assessment

Learning Objectives

After working through this chapter, the reader should be able to:

- apply a developmental framework to assessment design and interpretation;
- gather and reconcile information from multiple informants across settings;
- interview children and adolescents in ways that are developmentally appropriate;
- use behavioural observation and school information systematically;
- assess neurodevelopmental presentations without over- or under-diagnosing;
- recognise and respond to safeguarding concerns arising during assessment;
- obtain consent and assent appropriately, and communicate findings to families.

Key terms: developmental framework · multi-informant assessment · informant discrepancy · assent · developmental history · school observation · neurodevelopmental assessment · functional impairment · safeguarding · family context

Introduction

Assessment of children and adolescents differs from adult assessment in ways that go beyond the substitution of child-normed instruments. The child is developing, so a finding that would be stable in an adult may be transient, and a presentation that is atypical now may be typical in two years. The child is embedded in a family and a school, so the relevant envir-

onment is larger and the informants are more numerous. The child is legally a minor, so consent, confidentiality and the child's own voice must be managed within a framework that gives parents authority and the child rights.

These differences are not obstacles to assessment; they define it. A child assessment that applies adult methods to a smaller person produces conclusions that are technically derived and developmentally naive. This chapter sets out a framework for assessment that takes development, multiple contexts and family systems seriously, and that gives appropriate weight to the child's own account. Figure 12.1 shows how developmental level, informants and settings are integrated in the assessment of a child.




Figure 12.1. Child assessment. Development, multiple informants and multiple settings must be integrated before conclusions are drawn.

12.1 Developmentally Informed Assessment

A developmental framework asks not only what the child is doing but what would be expected at this age, what the trajectory has been, and what the child is likely to do next.

Normative expectations and their limits

Developmental norms describe the range of typical functioning at a given age, and their use requires attention to the wide variation around the mean. A child who is at the fifteenth percentile for expressive language at three years may be entirely typical, or may be showing the first sign of a language disorder; the difference is established by the trajectory rather than the single point. The assessor should obtain information about earlier functioning wherever possible, because a single assessment cannot distinguish delay from variation.

Trajectory and change

The most informative developmental question is usually about change: has the child's functioning diverged from the expected trajectory, become more discrepant over time, or lost previously acquired skills? Regression is always significant and warrants urgent assessment. Equally, a difficulty that has been stable and proportionate to the child's developmental level may not require a diagnostic label, only monitoring.

The developmental context

Development occurs within relationships, and the child's functioning is inseparable from the caregiving environment. Attachment relationships, family stress, parental mental health, housing, poverty and exposure to adversity all shape development and all affect the presentation. The assessor should gather this context not as background but as explanatory information, while avoiding the twin errors of blaming families for difficulties that are neurodevelopmental and of ignoring family factors that are genuinely contributing.

12.2 Multi-Informant Assessment

Children behave differently in different settings, and the informants who observe them in each setting provide different information. Discrepancy among informants is the norm rather than the exception, and its pattern is informative.

Who informs

Parents or carers provide developmental history, family context, and behaviour at home. Teachers provide information about learning, peer relationships and behaviour in a structured group setting. The child provides their own account, which is often the only source for internal experience such as worry, sadness, intrusive thoughts and bullying. Other informants may include grandparents, childminders, sports coaches and, where relevant, social workers and health visitors.

Interpreting discrepancy

Discrepancies between home and school reports are common in attention-deficit/hyperactivity disorder, autism, anxiety and trauma-related presentations, and they carry diagnostic weight: a child who is highly symptomatic at home but unremarkable at school may be masking, may be exhausted by the effort of coping, or may be experiencing a difficulty specific to the home environment. The assessor should record each informant's account separately, note the settings in which each observes the child, and then interpret the pattern rather than averaging the reports.

Structured multi-informant measures

Standardised informant measures, completed by parents and teachers, quantify symptoms and permit comparison with norms. Their scores should be interpreted with attention to the informant's opportunity to observe, their own mental state, and the possibility of rater effects such as a parent's own anxiety inflating ratings of the child's anxiety. Discrepancy indices supplied by some instruments are useful but should be interpreted in the same way.

12.3 Parent and Caregiver Interviews

The parent interview is the principal source of developmental history and the principal opportunity to establish a working relationship with the family.

Content

The interview covers the presenting concern; pregnancy, birth and early development; milestones; health history; family composition and relationships; educational history; peer relationships; the child's strengths and interests; previous assessments and interventions; parental understanding of the difficulty; and the family's goals. It should also cover parental mental and physical health, since these affect both the child's environment and the parent's capacity to participate in treatment.

Process

The interview should be conducted with sensitivity to the parent's position. Many parents arrive feeling judged, having been told by schools or relatives that they are responsible for the child's difficulties. The assessor should convey that the purpose is understanding rather than blame, elicit the parent's own observations before offering any, and acknowledge the parent's expertise about their child. Where the parent's account is inconsistent with other evidence, the assessor should explore the inconsistency rather than confront it.

Where parents disagree

Disagreement between parents about the child's difficulties is common and clinically important. It may reflect genuine differences in the child's behaviour with each parent, differences in the parents' own thresholds, or conflict in the parental relationship. The assessor should record both accounts and consider whether the disagreement itself needs to be part of the work.

12.4 Interviewing Children and Adolescents

Children are competent witnesses to their own experience, and their accounts are frequently the most valuable information in the assessment. The interviewer's task is to make the conversation possible.

Developmental adaptation

The method must match the child's age, language and cognitive level. Younger children benefit from play-based methods, drawing, visual scales and concrete questions; adolescents prefer directness, respect for their autonomy and a clear explanation of confidentiality. Questions should be short, specific and free of abstraction. "Tell me about a time you felt worried this week" is more productive than "how would you rate your anxiety".

Establishing the frame

Children should be told, in terms they can understand, who the assessor is, why they are there, what will happen, and who will be told what. The limits of confidentiality should be explained honestly: that their parents will be given information, but that the assessor will discuss with them first what will be shared, except where there is a safety concern. Children who understand the frame are more likely to disclose.

Interviewing about sensitive topics

Disclosure of abuse, self-harm, suicidal thoughts and substance use requires a careful approach: open questions first, specific questions only where necessary, no leading questions, and accurate recording of the child's own words. Where a disclosure is made, the assessor should follow safeguarding procedures rather than investigating, and should not promise confidentiality that cannot be kept. The child's account should be recorded verbatim wherever possible, because it may become evidence.

The adolescent's position

Adolescents often have legitimate concerns about privacy, about being pathologised and about the consequences of disclosure. The assessor should acknowledge these concerns, negotiate what will be shared with parents, and support the young person's increasing autonomy while maintaining safety. Where the young person's wishes and the parents' authority con-

flict, the assessor's task is to work with both and to be transparent about the limits.

12.5 Behavioural Observation

Observation provides information that no informant can supply: the child's behaviour in real time, in interaction with an adult, under the conditions of the assessment.

Structured and unstructured observation

Structured observation uses standardised tasks that elicit the behaviour of interest, such as a parent–child interaction task or a structured play session. Unstructured observation records the child's spontaneous behaviour during the assessment: how they separate from the parent, how they respond to difficulty, how they manage transitions, how they interact with the assessor, and how they regulate their attention and emotion.

What to record

Records should be descriptive and behavioural: what the child did, in what context, and with what consequence. Interpretations should be recorded separately and identified as such. The observation of a child who cannot sit still during a twenty-minute task is more informative when it records, alongside the behaviour, the nature of the task, the time of day, the child's sleep the previous night and the assessor's own expectations.

Limitations

Observation in a clinic is observation in an unusual setting, and children often behave better or worse than usual there. The assessor should treat observation as one source among several and should be cautious about inferring typical behaviour from a single session. Where possible, observation in the natural setting — a home visit, a classroom observation — adds valuable information.

12.6 School Records and Teacher Reports

School is the setting in which most children are first identified as having difficulties, and school information is central to assessment.

Records

School records include attendance, attainment, reports, behaviour logs, special educational provision, and records of exclusions or fixed-term suspensions. They establish the trajectory of the difficulty, the school's previous response, and the child's functioning in a structured group setting. The assessor should request records for the period before the referral as well as the current year, since the trajectory is the most informative element.

Teacher reports

Teachers observe the child in a setting with specific demands: sustained attention, compliance with group norms, peer interaction and academic performance. Their reports are most useful when they are specific and behavioural rather than global. A structured teacher questionnaire supplies comparability; a brief conversation supplies detail. Where possible, the assessor should speak to more than one teacher, since behaviour varies by subject and by teacher.

Classroom observation

Where the question concerns attention, behaviour or social participation, a classroom observation can be decisive. It should be conducted systematically, with an agreed focus, a structured recording method and, ideally, a comparison child of similar age. Observations conducted without a structure tend to confirm whatever the observer expected.

12.7 Neurodevelopmental Assessment

Neurodevelopmental presentations — autism spectrum disorder, attention-deficit/hyperactivity disorder, developmental language disorder, intellectual disability, specific learning disorders, tic disorders and develop-

mental coordination disorder — are among the most common reasons for child assessment, and they are also among the most frequently misdiagnosed.

The developmental history

In every case the developmental history is the foundation. The assessor should establish the timing of milestones, the pattern of early social communication, the presence of restricted interests or sensory differences, the trajectory of attention and activity across settings, and the age at which difficulties were first noticed. Where the informant's recall is uncertain, contemporaneous records such as health visitor notes or nursery reports are valuable.

Assessment methods

Neurodevelopmental assessment combines interview, informant questionnaires, direct observation and, where indicated, standardised instruments such as the Autism Diagnostic Observation Schedule (Lord et al., 2012) for autism or a cognitive assessment for intellectual disability. No single instrument is sufficient, and the assessor should be familiar with the specific training requirements of the instruments used.

Diagnosis and its consequences

A neurodevelopmental diagnosis has consequences: access to support, explanation for the family, and implications for the child's self-understanding. It should therefore be made carefully, on converging evidence, with attention to differential explanations, and with a clear account of what the diagnosis does and does not mean. Where the evidence is insufficient, the assessor should say so and specify what further information would be needed, rather than making a diagnosis to secure services or withholding one to avoid labelling.

12.8 Emotional and Behavioural Problems

The most common presentations in child mental health are emotional and behavioural difficulties: anxiety, depression, oppositional behaviour, aggression, sleep problems, and difficulties following adverse experiences.

Developmental expression of distress

Children express distress differently from adults. Depression may present as irritability, somatic complaints, school refusal or behavioural regression rather than as reported sadness. Anxiety may present as avoidance, clinginess, aggression or physical symptoms. Trauma may present as dysregulation, hypervigilance, dissociation or re-enactment in play. The assessor must know these developmental expressions, because a literal application of adult criteria will miss the majority of affected children.

Differential considerations

The differential includes developmental conditions, family and environmental stressors, physical illness, and the effects of adversity. Behaviour that appears oppositional may be a response to an unsuitable classroom, a learning difficulty that makes school humiliating, or a symptom of anxiety. The assessor should generate these explanations and look for the evidence that discriminates them before concluding that the child has a behavioural disorder.

Assessment of the family context

The child's difficulties occur in a family context, and the assessment should include the family's strengths as well as its difficulties. Parental mental health, parental conflict, sibling relationships, housing and financial stress all affect the child, and all are amenable to intervention. The assessor's report should identify these factors without attributing blame, and should recommend support for the family where it is needed.

12.9 Trauma and Safeguarding in Youth Assessment

Children are referred for assessment after adversity more often than adults, and the assessment is frequently the first occasion on which the extent of the adversity becomes known.

Recognising adversity

The assessor should ask routinely about exposure to domestic abuse, physical and sexual abuse, neglect, parental substance use, parental mental illness, bereavement, separation, bullying, community violence and displacement. Routine enquiry is necessary because children rarely volunteer such information and because parents may not know or may not disclose it.

Responding to disclosure

Where a child discloses abuse, the assessor's responsibility is to listen, record accurately in the child's words, reassure the child that they are not to blame, explain what will happen next, and follow the safeguarding procedure. The assessor should not investigate, should not promise confidentiality, and should not repeatedly question the child, since repeated questioning can compromise both the child's wellbeing and any subsequent legal process.

Assessment after trauma

Where trauma is known, the assessment should establish the symptoms, the child's understanding, the current safety, the available support and the child's own coping. Trauma-focused assessment should be paced, should avoid unnecessary detailed re-telling, and should be conducted in a way that does not leave the child distressed and unsupported at the end of the session.

Safeguarding as an assessment finding

Safeguarding concerns are relevant to the formulation and to the recommendations, even where they are not the reason for referral. The assessor should record them, refer them appropriately, and consider their implica-

tions for the child's difficulties. A formulation that omits known adversity is incomplete.

12.10 Family and Cultural Context

The family is the child's primary environment, and culture shapes both the family's understanding of the child's difficulties and the meaning of the behaviour.

Family functioning

Assessment should include family composition, relationships, communication, conflict, discipline practices, and the family's strengths and supports. Where family functioning is a maintaining factor, the formulation should say so and the recommendations should include family-based intervention. Where the family is a source of support, the formulation should identify this as a resource to be mobilised.

Cultural context

Cultural expectations shape what is considered typical for a child's age, what behaviour is considered problematic, and what help is acceptable. In some communities, expectations of independence, obedience or academic achievement differ markedly from those of the assessor's own background, and behaviour that appears disordered against one set of expectations may be unremarkable against another. The assessor should ask about the family's expectations and their own understanding of the difficulty, and should be cautious about diagnosing a disorder on the basis of a cultural mismatch.

Language and interpretation

Where the family's first language differs from the language of assessment, the assessor should use a trained interpreter, should establish the child's language proficiency in both languages, and should be cautious about assessing the child in a language in which they are not fluent. Chapter 14 treats this in detail.

12.11 Consent, Assent and Confidentiality

Children cannot consent to assessment in most jurisdictions, but they have rights that the assessor must protect.

Parental consent

Consent is normally obtained from a person with parental responsibility. The assessor should explain the purpose, the methods, the likely duration, the use of the findings and the limits of confidentiality, and should record the consent obtained. Where parents disagree, or where the child is looked after by the state, the legal position should be clarified before the assessment proceeds.

The child's assent

Assent is the child's agreement to participate, given in a form appropriate to their understanding. It is not a legal substitute for parental consent, but it is ethically essential: a child who does not assent should not be assessed, except where the assessment is necessary to protect them. The assessor should explain the process in accessible language, check understanding, and respect refusal where possible.

Confidentiality and its limits

Children and adolescents need to know what will be shared with their parents, and the assessor should negotiate this explicitly. A workable approach is to agree that the assessor will share the main findings with parents, will discuss the content of that feedback with the young person first, and will not disclose specific sensitive information unless there is a safety concern. This approach respects the young person's privacy while maintaining the parents' legitimate involvement.

12.12 Integrated Youth Formulation and Feedback

The assessment concludes with a formulation that integrates developmental history, multiple informants, observation, school information and the child's own account.

Structure of the formulation

A youth formulation should describe the child's developmental trajectory, the current difficulties and their functional impact, the maintaining factors across home, school and peer contexts, the child's strengths and resources, and the family and cultural context. It should identify the points at which intervention is likely to be effective, and it should be written in language that parents and, where appropriate, the child can understand.

Feedback to parents

Feedback should begin with the child's strengths, present the findings in plain language, explain the diagnosis or formulation and what it means, invite questions, and connect the findings to specific recommendations. Where the findings are unwelcome — a diagnosis of autism, a recommendation for special provision, a safeguarding referral — the assessor should allow time, acknowledge the emotional response, and offer follow-up.

Feedback to the child

Children should receive feedback appropriate to their age, in language they can understand, with an emphasis on what is helpful rather than on what is wrong. A child who is told that their brain works differently and that there are things that will help is better served than one who is told they have a disorder and left to imagine what that means.

Feedback to school

Where the school is involved, feedback should be practical: what the child needs, what has been shown to help, and what the school can do. Recommendations should be specific enough to be implemented, and the school's constraints should be acknowledged. A report that recommends provision the school cannot make is unlikely to change anything.

Advanced Case Conference

The referral. An 8-year-old boy is referred by his general practitioner at his mother's request. The school has reported that he is "not coping" and has suggested he may have attention-deficit/hyperactivity disorder. His mother reports that he is "fine at home" but that he cries before school and has started refusing to go.

The evidence. The developmental history is unremarkable: milestones were met on time, early social communication was typical, and there were no concerns before starting school. Teacher reports describe inattention and frequent trips to the toilet during lessons; a structured teacher questionnaire is elevated on attention problems. A parent questionnaire on the same instrument is within normal limits. Observation shows a quiet, cooperative boy who is anxious on separation from his mother and who asks repeatedly whether he is doing the task correctly. Cognitive assessment is in the average range. On direct enquiry he describes being teased about his reading and says he "feels sick" in reading lessons. A reading assessment shows word-level reading well below the level expected for his age, with average comprehension when the text is read to him.

The reasoning. The teacher-reported attention problems and the school's hypothesis of ADHD are plausible but not supported by the full picture. The onset of difficulties coincided with the introduction of formal reading, the behaviour is situation-specific, and the child's own account identifies reading lessons as the source of distress. The apparent inattention is consistent with avoidance of a task he finds humiliating, and the trips to the toilet are consistent with escape behaviour. The discrepancy between home and school reports is explained by the fact that reading demands occur only at school.

The decision. The report identifies a specific word-reading difficulty, with secondary anxiety and school avoidance, and declines to diagnose ADHD on the current evidence while noting that the question could be revisited if difficulties persisted after reading support. It recommends a structured phonics intervention, reasonable adjustments in reading lessons, and a graded return-to-school plan with the school. It recommends that the child's anxiety be monitored and treated if it does not reduce once the reading difficulty is addressed.

> **The teaching point.** The referral question was ADHD; the assessment found a reading difficulty and an understandable avoidance. The multi-informant discrepancy was the clue, and the child's own account supplied the explanation.

Chapter Summary

Child and adolescent assessment requires a developmental framework that considers trajectory, normative variation and the caregiving environment. Multiple informants are essential, and discrepancy among them is informative rather than problematic. The parent interview supplies developmental history and the opportunity to build a working relationship, while the child's own account supplies information available from no other source. Observation and school information add the contexts in which the child actually functions. Neurodevelopmental assessment rests on developmental history and converging evidence, and diagnoses should be made on evidence rather than to secure services. Emotional and behavioural difficulties present developmentally, and the differential must include learning difficulties, family context and adversity. Safeguarding concerns arising during assessment require immediate procedural response. Consent, assent and confidentiality must be managed within a framework that respects both parental authority and the child's rights.

Review Questions

1. Why is a single developmental assessment insufficient to distinguish delay from variation?
2. How should discrepancy between parent and teacher reports be interpreted?
3. What are the limits of confidentiality when assessing an adolescent?
4. Why might inattention in the classroom indicate a reading difficulty rather than ADHD?
5. What is assent, and how does it differ from consent?

Discussion Questions

1. A parent asks you not to tell the child about a diagnosis of autism. How do you respond?
2. How would you assess a child whose family speaks a different language at home?
3. What are the risks of diagnosing ADHD in a child who is being bullied at school?
4. How should an assessor respond to a disclosure of abuse made during an assessment?
5. Should a diagnosis ever be given to secure access to educational support? Defend your position.

Further Reading

American Psychiatric Association. (2022). *Diagnostic and statistical manual of mental disorders* (5th ed., text rev.). American Psychiatric Association Publishing.

Lord, C., Rutter, M., DiLavore, P. C., Risi, S., Gotham, K., & Bishop, S. L. (2012). *Autism Diagnostic Observation Schedule* (2nd ed.). Western Psychological Services.

Sattler, J. M. (2018). *Assessment of children: Cognitive foundations and applications* (6th ed.). Jerome M. Sattler.

World Health Organization. (2024). *Clinical descriptions and diagnostic requirements for ICD-11 mental, behavioural and neurodevelopmental disorders*. World Health Organization.

CHAPTER 13

Couples, Family and Systemic Assessment

Learning Objectives

After working through this chapter, the reader should be able to:

- identify the appropriate unit of assessment in relational work;
- gather relationship history and present concerns from multiple participants;
- assess dyadic interaction, communication and conflict patterns;
- evaluate attachment and relationship security in a systemic frame;
- assess family structure, boundaries and parenting without allocating blame;
- screen for violence, coercion and safety before relational work begins;
- formulate systemically and deliver feedback that involves all participants.

Key terms: unit of assessment · dyadic interaction · demand–withdraw pattern · negative reciprocity · repair · boundaries · triangulation · coalitions · coercive control · systemic formulation · multi-person feedback

Introduction

Relational assessment asks different questions from individual assessment. The object of assessment is not a person's internal state but a pattern of interaction between people, and the relevant evidence is what happens between them rather than what each reports about themselves. This shift in the unit of analysis changes the methods, the ethics and the risks.

The risks deserve particular attention. Relational assessment may bring to light violence, abuse or coercive control that was not disclosed in individual sessions; it may place a participant at risk by inviting disclosure in

the presence of a partner; and it may be used, consciously or not, by one participant to establish that the other is the problem. The assessor's first obligations are therefore safety screening and clarity about the purpose and the limits of the assessment. This chapter sets out a framework for relational assessment that is both systematic and safe. Figure 13.1 places safety screening ahead of the relational enquiry and shows formulation turning from individuals to patterns between people.




Figure 13.1. Relational assessment. Safety screening precedes all other assessment; formulation concerns patterns between people, not deficits within one.

13.1 The Unit of Assessment in Relational Work

The first decision in relational assessment is what is being assessed: an individual within a relationship, a couple, a family, or a wider system. Each unit requires a different method and produces different conclusions.

Individual within relationship

Where the referral concerns one person but the difficulty is relational, the assessment may focus on the person's experience of the relationship, their contribution to the pattern, and their options. This is common where a partner declines to attend. The assessor should be explicit that the resulting

formulation is one-sided by design, and should avoid conclusions about the absent partner that cannot be evidenced.

Couple and family

Where the unit is the couple or the family, assessment requires the participation of all relevant members, ideally in a combination of joint and individual sessions. Joint sessions reveal interaction; individual sessions allow disclosure that cannot occur in front of others. The balance between the two is a clinical decision, and the arrangements should be agreed at the outset with all participants.

Wider systems

Some presentations require assessment of wider systems: the family and school together, a family and a social care team, or a multi-agency network around a child or an adult at risk. Systemic assessment then includes the relationships among professionals, the circulation of information, and the way the network itself may be maintaining the difficulty. This is demanding work and requires explicit agreement about roles and confidentiality.

13.2 Relationship History and Presenting Concerns

The relationship history provides the context against which present difficulties are understood. It should be gathered in a way that gives each participant a voice and that records disagreement rather than resolving it prematurely.

Content

The history includes how the couple met, the early phase of the relationship, significant transitions (cohabitation, marriage, children, migration, illness, bereavement, retirement), previous difficulties and how they were resolved, previous help-seeking, and each partner's hopes for the relationship. Where children are present, the parenting history and the children's needs are part of the picture.

Presenting concerns

Each participant should be asked separately what they see as the problem, what they want to change, and what they fear would happen if nothing changed. The differences among these accounts are the material for the assessment, and the assessor should not attempt to reconcile them at the first session.

The referral relationship

The assessor should establish who initiated the referral, who is attending willingly, and whether there is any external pressure — from a court, a social worker, a family member. Where one partner attends under duress, the assessment will be affected, and the assessor should acknowledge this openly rather than pretending to a neutrality that the participants do not share.

13.3 Dyadic Interaction and Communication

Observing how a couple communicates in the session is often more informative than anything they say about their communication.

What to observe

The assessor attends to turn-taking, interruption, escalation, repair, the ratio of positive to negative exchanges, non-verbal signals, and the way each partner responds when the other expresses distress. These observations should be recorded descriptively, without interpretation, and should be treated as data rather than as evidence of a partner's character.

Demand–withdraw and negative reciprocity

Two patterns recur across the relational literature. The demand–withdraw pattern describes a cycle in which one partner pursues engagement while the other withdraws, and each responds to the other in a way that intensifies the pattern. Negative reciprocity describes the escalation of negative responses, in which hostility from one partner elicits hostility from the other and the exchange spirals. Both patterns are self-maintaining, and both are

more usefully formulated as properties of the system than as deficits of either person.

Repair

The most discriminating feature of distressed and non-distressed relationships is not the frequency of conflict but the capacity for repair. The assessor should observe whether conflict is followed by reconnection, whether humour or apology is available, and whether either partner can de-escalate. Where repair is absent, the prognosis for the relationship is poorer, and the assessment should note this without using it as a prediction about the couple's future.

13.4 Conflict Patterns and Repair

Conflict is not itself a sign of dysfunction. The assessment concerns the pattern of conflict: what it is about, how it starts, how it escalates, how it ends, and what it leaves behind.

Mapping the conflict

The assessor should map a recent, specific conflict from beginning to end: the trigger, each partner's interpretation, the behaviour that followed, the escalation, the ending, and the aftermath. A specific episode is more informative than general descriptions, which tend to be shaped by each partner's global narrative about the other.

Underlying issues

Conflicts about practical matters frequently encode conflicts about recognition, autonomy, fairness or belonging. A dispute about the division of household labour may be about exhaustion, about being taken for granted, or about a partner's relationship with their family of origin. The assessor should explore what the conflict means to each partner rather than treating the surface topic as the issue.

Repair and its conditions

Repair requires that both partners can recognise the other's perspective, that at least one can de-escalate, and that there is a shared commitment to the relationship's continuation. Where these conditions are absent, the assessment should consider whether the couple's goal is to improve the relationship or to manage its ending, since the two require different work.

13.5 Attachment and Relationship Security

Attachment theory provides a framework for understanding how partners' expectations about availability and responsiveness shape their behaviour in the relationship.

Attachment in the couple

Partners differ in their tolerance of closeness and distance, in their response to conflict, and in their expectations of the other's availability. These differences often produce the demand–withdraw cycle: an anxiously attached partner pursues, an avoidantly attached partner withdraws, and each confirms the other's expectation. The assessment should identify these patterns without assigning either partner a diagnostic label.

Assessment methods

Attachment security in couples can be assessed by interview, by self-report questionnaires measuring attachment anxiety and avoidance, and by observation of the couple's interaction, particularly during a discussion of a disagreement. Self-report and observational methods assess different things and may disagree; the assessor should use both where possible and interpret the disagreement rather than choosing one.

Caution

Attachment language is easily used to explain everything and to absolve anyone. The assessor should use it as a framework for understanding patterns rather than as a diagnosis of a partner, and should avoid the inference

that a partner's attachment style means they cannot change. Where the pattern is used to justify harmful behaviour, the assessor should say so plainly.

13.6 Family Structure and Boundaries

Family assessment examines the organisation of the family: its structure, its boundaries, its hierarchy of authority and the alliances within it.

Structure and boundaries

Boundaries may be diffuse, with insufficient separation between members and a loss of individual identity, or rigid, with insufficient communication and support. Healthy functioning requires boundaries that permit both closeness and autonomy, and that can change in response to developmental transitions such as a child entering adolescence or an adult child leaving home.

Coalitions and triangulation

Coalitions occur when family members align against another member, and triangulation occurs when a two-person conflict is displaced onto a third. A child may be drawn into the parents' conflict, a grandparent may be recruited into a dispute, or a child's symptoms may serve to hold the family together. These patterns are often invisible in individual assessment and visible in family sessions.

Authority and discipline

Where children are present, the assessment examines who holds authority, whether the adults are consistent with each other, and whether discipline is proportionate and safe. Parental disagreement about discipline is extremely common and often reflects a difference in temperament or in the parents' own upbringing; the assessment should identify it and, where appropriate, include parenting work in the recommendations.

13.7 Parenting and Co-Parenting

Parenting and co-parenting are distinct constructs. Parenting concerns the interaction between a parent and a child; co-parenting concerns the way the adults in a child's life co-ordinate their parenting, whether they live together or apart.

Parenting assessment

The assessment of parenting includes the parent's capacity to recognise and respond to the child's needs, to provide appropriate structure and warmth, and to manage the child's behaviour without physical or emotional harm. Where the question is about parenting capacity — often in the context of child protection proceedings — the assessment requires direct observation of interaction, a parenting assessment instrument, and information about the parent's own history and current circumstances.

Co-parenting after separation

Where parents are separated, co-parenting assessment concerns the quality of communication between them, the consistency of routines, the child's exposure to conflict, and the parents' support for the child's relationship with the other parent. A structured co-parenting programme or mediation may be more appropriate than psychological intervention, and the assessor should know when to recommend it.

Parenting and the assessing system

Where an assessment is commissioned by a court or a social care team, the assessor should be clear about the question, the standard of evidence, the limits of the assessment and the potential consequences for the parent and the child. The parent should understand these from the outset. Assessment of parenting capacity is a specialised area, and it lies beyond the competence of general practice unless the assessor has specific training and supervision.

13.8 Violence, Coercion and Safety Screening

Safety screening is the first substantive assessment task in relational work, and it must precede any joint session or relational formulation.

Why routine screening

Violence and coercive control occur in a substantial minority of relationships, and they are frequently not disclosed. The risk is concentrated where assessment involves joint sessions, because a partner may be at risk from disclosure, and because conflict in the session may escalate outside it. Routine screening, conducted with each participant individually at the outset, is therefore a standard of safe practice.

Screening questions

Screening should be direct and specific: questions about fear, about physical violence, about threats, about economic and sexual control, about threats related to children or immigration status, and about escalation. A structured instrument such as the Relationship Assessment Tool or the HITS screening tool supports reliability, but the assessor's own direct enquiry matters more than the instrument.

What follows a disclosure

Where violence or coercive control is disclosed, the assessment plan must change. Joint sessions are contraindicated where one partner is violent or controlling; the safety of the victim is the first priority; specialist domestic abuse services should be involved with consent where possible and without consent where required by law; and the assessor should record the disclosure, the actions taken, and the reasoning. The safety of any children in the household must be considered.

The limits of couple therapy

Couple therapy is not appropriate where there is violence, coercion, active untreated substance dependence, untreated psychosis, or where one partner is being controlled. This is not a moral judgement but a safety and ef-

fectiveness judgement, and it should be recorded explicitly when a decision against relational work is made.

13.9 Individual Symptoms in Relational Context

Individual symptoms — depression, anxiety, substance use, chronic illness, neurodevelopmental conditions — occur within relationships and are affected by them. The assessment should capture that interaction without over-attributing the symptom to the relationship.

Circular causality

The relationship between symptoms and relational patterns is usually circular: a partner's depression reduces engagement, which the other experiences as rejection, which leads to criticism, which worsens the depression. Formulating the pattern in this way is more useful than determining who started it, and it identifies multiple points for intervention.

Avoiding blame

The risk in systemic formulation is that the identification of patterns is experienced as allocation of blame. The assessor should be explicit that the patterns described are not the fault of any individual, while also being honest where one person's behaviour is harmful. The distinction between a pattern that maintains difficulty and a behaviour that is abusive must be maintained: coercion is not a circular pattern.

Symptoms as communication

Some symptoms carry meaning within the system: a child's behaviour that draws the parents together, a partner's symptoms that provide an acceptable way of expressing distress. The assessor should consider these meanings without over-interpreting, and should test interpretations with the family rather than presenting them as facts.

13.10 Cultural and Socioeconomic Context

Relational patterns are culturally patterned, and the assessor's own cultural assumptions are part of the assessment instrument.

Cultural variation in family and couple norms

Expectations regarding gender roles, intergenerational cohabitation, obligations to family of origin, marital conflict, privacy and emotional expression vary widely. A pattern that appears enmeshed within one cultural frame may be normative within another, and a pattern that appears unproblematic within one frame may be harmful within another. The assessor should ask about the family's own expectations and should treat the family's frame as the starting point.

Migration and family process

Migration creates relational patterns of its own: separation and reunification, differences in acculturation between generations, responsibilities placed on children as translators, and the loss of extended family support. The assessment should establish the migration history, the current family composition, and the distribution of roles, which often differ from the family's ideal.

Socioeconomic context

Housing insecurity, poverty, shift work, unemployment and caring responsibilities shape relational life. A couple whose conflict arises from overcrowding and financial strain requires material intervention as well as relational work, and a formulation that ignores this will be both inaccurate and condescending.

13.11 Measures of Relationship Functioning

Standardised measures provide a comparison with norms, a baseline and a method for monitoring change. They supplement, and never replace, the interactional observation that is the core of relational assessment.

Instruments in common use

The Dyadic Adjustment Scale and the Couples Satisfaction Index measure relationship satisfaction. The Oral History Interview is an observation-based method for assessing the couple's narrative of their relationship. Family assessment measures include the Family Assessment Device and observational coding systems for family interaction. Each has different evidence, different administration requirements and different purposes, and the assessor should match the instrument to the question.

Multi-informant scoring

Relational measures should normally be completed by all participating members, and the discrepancy between them is itself informative. A couple in which one partner reports high satisfaction and the other reports low satisfaction is in a different position from one in which both report low satisfaction, and the formulation should reflect the difference.

Monitoring

Where relational therapy is being conducted, repeated measures of satisfaction and of the specific problem can inform the therapist about progress. As with individual monitoring, the measure should be one with demonstrated sensitivity to change, and the score should be interpreted alongside the couple's own account.

13.12 Systemic Formulation and Feedback

The systemic formulation integrates interactional patterns, developmental history, individual symptoms, cultural context and the family's own understanding into an account that explains why this difficulty is occurring now and what would need to change.

Structure

A useful systemic formulation describes the presenting pattern, the cycle that maintains it, the developmental and historical antecedents, the strengths and resources of the system, the wider context, and the possible

points of intervention. It should be stated in language all participants can follow, and it should be presented as a hypothesis for the family to test rather than as a verdict delivered to them.

Multi-person feedback

Feedback to a couple or family requires different skills from feedback to an individual. The assessor should manage the conversational turn-taking, ensure each person's account is reflected, avoid attributing blame, acknowledge disagreement, and keep the session safe. Where the assessment has identified a pattern that participants have not recognised, the assessor should present it tentatively and invite their view.

Written reports

Written relational reports should describe patterns rather than persons, should balance strengths with difficulties, and should avoid allocating responsibility in ways that the report cannot evidence. Where a report will be read in a legal context, the assessor should be especially careful about the difference between observation, inference and opinion, and should state the limits of the assessment.

> **Advanced Case Conference**
>
> **The referral.** A couple in their forties are referred by their general practitioner after the wife's treatment for depression failed to improve. The referral describes "relationship difficulties" and asks for couple therapy.
>
> **The assessment.** Each partner is seen individually first. The wife describes exhaustion, low mood and a sense that her husband is "not there" for her. The husband describes feeling criticised and says he "keeps the peace" by withdrawing. Both deny violence, but on direct screening the wife discloses that her husband has pushed her twice during arguments in the past year, has prevented her from seeing a friend, and controls all the household money. She says she is afraid of his reaction if he knew she had disclosed. In the joint session, the demand–withdraw cycle is visible: she raises a concern, he becomes silent and looks away, she escalates, he leaves the room.

The reasoning. The demands of the referral — couple therapy for relationship difficulties — cannot safely be met. The presence of physical violence and economic control is a contraindication to joint work. The individual presentations (depression in the wife, withdrawal and defensiveness in the husband) are embedded in a pattern that includes coercive control, and the circular formulation that would describe as mutual is not appropriate where one partner is afraid.

The decision. The report declines couple therapy, records the safety concerns and the contraindication, and refers to a specialist domestic abuse service with the wife's consent. It offers the husband an individual assessment with a focus on his use of control, and records that work with the couple could be reconsidered only if the violence and control were addressed and the wife wished it. It records the wife's account, her fear, and the safety plan agreed.

The teaching point. The routine individual screening changed the entire assessment. A couple formulation built on the joint session alone would have described a mutual cycle and missed the pattern of control.

Chapter Summary

Relational assessment examines patterns between people, and the unit of assessment must be decided explicitly. Relationship history and presenting concerns should be gathered from each participant separately as well as jointly, and discrepancy among accounts is informative. Dyadic interaction is observed directly, with attention to demand–withdraw cycles, negative reciprocity and repair. Family structure, boundaries, coalitions and parenting are assessed in the family session, with attention to cultural and socioeconomic context. Safety screening is the first substantive task, and violence or coercive control contraindicates joint work. Individual symptoms are formulated within the relational system without attributing blame or obscuring harmful behaviour. Standardised measures supplement observation and should be completed by all participants. Systemic formulation and multi-person feedback should be presented as hypotheses that the family can test.

Review Questions

1. Why is the unit of assessment a decision rather than a given?
2. What is the demand–withdraw pattern, and why is it formulated systemically?
3. Why are joint sessions contraindicated where there is coercive control?
4. What is the difference between parenting and co-parenting?
5. How should a systemic formulation avoid allocating blame while still identifying harmful behaviour?

Discussion Questions

1. One partner refuses to attend. How does this change the assessment and the formulation?
2. A couple asks you not to raise the issue of violence because "it would make things worse". What do you do?
3. How would you assess a family in which a child's behaviour is the presenting problem but the parents' conflict is the underlying issue?
4. What are the limits of couple therapy, and how would you explain them to a couple who want it?
5. How should a relational report be written when it may be read in court?

Further Reading

Epstein, N. B., Baldwin, L. M., & Bishop, D. S. (1983). The McMaster Family Assessment Device. *Journal of Marital and Family Therapy, 9*(2), 171–180.

Gottman, J. M. (1999). *The marriage clinic: A scientifically based marital therapy*. W. W. Norton.

Minuchin, S. (1974). *Families and family therapy*. Harvard University Press.

Spanier, G. B. (1976). Measuring dyadic adjustment: New scales for assessing the quality of marriage and similar dyads. *Journal of Marriage and the Family, 38*(1), 15–28.

Stark, E. (2007). *Coercive control: How men entrap women in personal life*. Oxford University Press.

CHAPTER 14

Multicultural, Language, Disability and Fairness Considerations in Assessment

Learning Objectives

After working through this chapter, the reader should be able to:

- explain how culture shapes the expression, interpretation and reporting of symptoms;
- assess language proficiency and use interpreters appropriately;
- evaluate translated and adapted instruments against the standards for equivalence;
- appraise bias and fairness at the level of construct, method and use;
- identify the barriers created by disability and the accommodations that address them;
- incorporate migration, acculturation, socioeconomic conditions and intersecting social positions into formulation;
- produce culturally responsible formulations that are explicit about their limits.

Key terms: cultural formulation · idioms of distress · language proficiency · interpreter-mediated assessment · translation equivalence · measurement invariance · construct bias · method bias · reasonable accommodation · acculturation · intersectionality · epistemic humility

Introduction

Every assessment is cultural. The constructs it measures, the instruments it uses, the norms against which it compares, the language in which it is conducted and the assumptions it makes about what constitutes healthy functioning are all products of particular cultural and historical settings. When assessor and client share those settings, the assumptions are invisible; when they do not, they become the substance of the assessment.

This chapter treats cultural and linguistic competence not as a supplementary courtesy but as a condition of valid assessment. It addresses the specific technical problems — translation, equivalence, invariance, language proficiency — and the broader interpretive problems that arise when a client's presentation is understood through a framework that was not designed for them. It also addresses disability, which raises structurally similar questions about whether an instrument measures the construct or the barrier, and it considers how multiple social positions interact. Figure 14.1 traces culture and language through every stage of the assessment, from construct definition to the feedback session.




Figure 14.1. Culturally responsible assessment. Culture and language condition every stage, from construct definition to feedback.

14.1 Culture and the Meaning of Symptoms

Culture shapes what distress feels like, how it is expressed, what it is attributed to, who is consulted and what help is acceptable. An assessment that ignores these influences will misinterpret both the presence and the severity of difficulty.

Idioms of distress

Different cultural settings provide different vocabularies for distress. Somatic complaints, spiritual attributions, complaints about family relationships, and descriptions of "thinking too much" are all recognised idioms through which distress is expressed. The DSM-5-TR cultural concepts of distress — cultural syndromes, cultural idioms of distress and cultural explanations — provide a vocabulary for describing these patterns without treating them as exotic. The assessor's task is to establish what the client's experience means within their own framework, and then to determine whether it corresponds to a recognised clinical construct.

Expression and threshold

Cultures differ in the expression of emotion, the acceptability of disclosing distress, and the threshold at which a difficulty becomes a problem. A client from a setting in which emotional restraint is valued may under-report symptoms; a client from a setting in which expressive disclosure is normative may appear more distressed than their functional status warrants. Neither pattern is a distortion; both are culturally patterned response styles that the assessor must interpret.

Attribution and help-seeking

Beliefs about causation — spiritual, interpersonal, biomedical, moral — shape what the client expects from assessment and treatment. A client who believes their difficulty is a spiritual affliction may not accept a psychological formulation, and a client who believes it is a moral failing may feel judged by any diagnosis. The assessor should elicit the client's explanation and work with it, rather than treating it as a barrier to be overcome.

14.2 Language Proficiency and Interpreter Use

Language is the medium of most psychological assessment, and limited proficiency in the language of assessment is a direct threat to validity.

Assessing proficiency

The assessor should establish the client's proficiency in the language of assessment and in their first language, using self-report, observation and, where possible, a structured measure. Self-report is unreliable: clients frequently over-estimate their proficiency, particularly in high-stakes settings where admitting limited proficiency feels risky. The assessor should observe comprehension directly — for example, by asking the client to explain a task in their own words — and should consider whether the client's presentation differs across languages.

Working with interpreters

Where an interpreter is required, the assessment should use a trained interpreter rather than a family member or a bilingual colleague. The interpreter should be briefed on the purpose of the assessment, the instruments to be used, the style of interpretation required (first-person, verbatim, without editing), and the confidentiality obligations. The assessor should speak to the client rather than to the interpreter, should allow extra time, and should record that the assessment was interpreter-mediated.

The effects of interpretation

Interpretation changes the assessment in ways that should be documented. Nuance is lost, idioms may be translated into clinical vocabulary or left opaque, and the interpreter's presence alters disclosure, particularly for sensitive topics and where the interpreter is a member of the client's community. The assessor should record the language of administration, the interpreter's role, and the resulting limits on interpretation. Where standardised instruments are administered through an interpreter, the norms no longer apply, and the scores should be reported descriptively rather than normatively.

14.3 Test Translation and Adaptation

Translated instruments are not equivalent to their originals by virtue of translation. Equivalence is an empirical claim requiring evidence.

Standards for adaptation

The International Test Commission's guidelines for translating and adapting tests specify the required process: documented forward and backward translation by independent translators, reconciliation by a committee, pilot testing with the target population, cognitive interviews to check item comprehension, and empirical evidence of equivalence. Adaptation also requires attention to item content that may be culturally inappropriate — references to unfamiliar foods, activities, holidays or social situations — and to response formats that may be unfamiliar.

Evidence of equivalence

Evidence of equivalence includes confirmatory factor analysis demonstrating the same structure in each group, tests of measurement invariance at configural, metric and scalar levels, and analyses of differential item functioning. Where scalar invariance is not demonstrated, mean comparisons between groups are not interpretable, and the assessor should not compare a client's score with norms derived from a different linguistic or cultural group.

Practical guidance

Where a translated instrument has documented equivalence, it can be used with the same interpretive rules as the original. Where it has documented translation but no equivalence evidence, the scores should be interpreted with explicit caution and preferably descriptively. Where the instrument has not been adapted at all, and administration proceeds through an interpreter, the score is not a score in any norm-referenced sense, and the report should say so.

14.4 Bias and Fairness

Bias in assessment refers to systematic error in the estimation of a construct for members of a particular group. It is distinct from group differences in the construct itself, and distinguishing the two is the central technical problem of fair assessment.

Construct bias

Construct bias occurs where the construct itself is defined differently across groups, or where the instrument samples the construct differently. A measure of "social competence" developed in one cultural setting may sample behaviours that are valued there and irrelevant or inappropriate elsewhere. The practical implication is that construct definition must be examined before instruments are chosen, and that the assessor should ask whether the construct, as operationalised, means the same thing for this client.

Method bias

Method bias arises from the procedure rather than the construct: differential familiarity with testing, differential response styles, differential item familiarity, and differential examiner effects. Examples include the use of timed tests with clients from educational settings where speed is not emphasised, and the use of Likert scales with clients unfamiliar with the format. Method bias can be reduced by adaptation, by practice items, by alternative formats, and by interpreting scores in the context of the client's testing history.

Fairness in use

Fairness in use concerns the consequences of score interpretation: whether a decision rule produces systematically different outcomes for groups of equal standing on the construct. The assessor should know whether the instrument's cut scores have been evaluated for differential impact, and should be cautious about applying cut scores derived from one population

to another. The professional standards treat fairness as integral to validity, not as a separate consideration.

14.5 Normative Samples and Representativeness

Norms are comparisons, and a comparison is only meaningful if the reference group is relevant.

The relevance question

The assessor should ask whether the normative sample resembles the client on the characteristics that affect the construct: age, education, language, culture, disability status, and the clinical or non-clinical nature of the sample. A clinical sample norm is not appropriate for a community client, and a norm collected in one country may not represent a client in another even when both speak the same language.

Local norms

Where local norms exist, they may be more appropriate than the publisher's norms, provided they are of adequate quality. Local norms derived from a small or unrepresentative sample can be worse than no local norms, because they convey a false precision. The assessor should evaluate the sample size, the recruitment method and the stratification before adopting local norms.

Interpretation without appropriate norms

Where no adequate norms exist, the assessor has three options: interpret the score descriptively rather than normatively; use within-person comparisons (for example, comparing the client's performance across domains rather than across people); and rely on functional and behavioural evidence. The report should state which approach was used and why.

14.6 Disability and Reasonable Accommodations

Disability raises a structural question analogous to culture: does the instrument measure the construct, or does it measure the barrier?

The social and medical models

The medical model locates disability in the individual's impairment; the social model locates it in the interaction between impairment and an environment that fails to accommodate it. Contemporary frameworks, including the World Health Organization's International Classification of Functioning, Disability and Health, integrate both: disability is the outcome of the interaction between a health condition, personal factors and environmental barriers. For assessment, this means that a low score may reflect the construct, the barrier, or both, and that the assessor must determine which.

Accommodations and their evidence

Accommodations remove barriers without changing the construct. The evidence that a given accommodation preserves score meaning varies by instrument and by accommodation; the assessor should know this evidence rather than assuming that all accommodations are equivalent. Where an accommodation has been applied without validation, the score should be interpreted descriptively.

Disability and diagnostic overshadowing

A recurring problem is diagnostic overshadowing: attributing all difficulties to a known disability and failing to assess for additional conditions. A person with a learning disability may have depression that is untreated because their low mood is attributed to the disability; a person with a sensory impairment may have anxiety that is missed because their presentation is attributed to the impairment. The assessor should assess for comorbidity actively and should use instruments validated for the population where available.

14.7 Migration, Acculturation and Context

Migration produces a set of contextual factors that shape both the presentation and its interpretation.

The migration history

The assessor should establish the reason for migration, the circumstances of the journey, the time since arrival, the client's legal status, the presence or absence of family, the loss of status and social role, and the experience of discrimination. Each of these is a potential contributor to distress and a potential resource for recovery.

Acculturation

Acculturation describes the process of change in values, practices and identifications that follows contact between cultural groups. It is not a single dimension of "integration" but a set of strategies that vary across domains: a person may adopt the language of the host society while retaining the family's religious practice and gender norms. The assessor should not assume that a longer period of residence implies greater acculturation, nor that acculturation is desirable in itself.

Intergenerational and family dimensions

Migration frequently produces differences in acculturation between generations, which can be a source of family conflict and of individual distress. A young person may be more acculturated than their parents and experience the difference as a conflict of loyalty. The assessor should consider these dynamics, particularly in family and child assessments.

14.8 Socioeconomic Conditions and Opportunity

Socioeconomic conditions shape both the presence of difficulty and the resources available to address it. They are also frequently confounded with the constructs that assessment measures.

Poverty and assessment

Poverty affects cognitive development, school attainment, mental health and the practical capacity to attend appointments and adhere to treatment. A child's low achievement score may reflect the quality of their schooling, the availability of books, food insecurity or chronic stress rather than a learning disorder. The assessor should gather information about material circumstances and should consider them as explanatory factors rather than as background.

Access to services

Access to assessment and treatment is unevenly distributed. Clients from disadvantaged backgrounds are more likely to be assessed in crisis, less likely to receive specialist assessment, and more likely to receive a diagnosis that carries stigma. The assessor should be aware of these patterns, not as a matter of individual guilt but as a reason to be particularly careful about the evidence base for conclusions about clients who have had limited access.

The limits of individual formulation

Some difficulties are primarily structural: unemployment, discrimination, housing insecurity and violence are not individual pathologies. Formulating them as individual difficulties is both inaccurate and unjust. The assessor should distinguish between what the person can change and what requires collective or political response, and should say so in the formulation.

14.9 Community Values and Cultural Context

The assessor's own cultural framework is part of the instrument, and recognising it is a prerequisite for fair assessment.

The assessor's position

Every assessor brings assumptions about family structure, autonomy, emotional expression, gender roles and the appropriate relationship between individual and community. These assumptions shape what is noticed, what is judged problematic and what is recommended. The assessor should identi-

fy their own position, seek supervision or consultation where it is likely to distort the assessment, and be explicit with the client about the limits of their cultural knowledge.

Consulting cultural knowledge

Where the assessor lacks knowledge of the client's cultural context, several resources are available: consultation with a clinician from that background, the client's own account, family and community informants (with consent), and the published literature on cultural concepts of distress. None of these is definitive, and the assessor should treat cultural knowledge as a set of hypotheses to be tested with the client rather than as a set of facts about them.

Avoiding both culturalism and colour-blindness

Two errors are common. Culturalism attributes all difficulty to culture and thereby fails to assess for disorder. Colour-blindness ignores cultural difference and applies a universal framework that may not fit. The appropriate position treats culture as one explanatory framework among several, to be tested against the evidence in the same way as any other.

14.10 Gender and Sexuality in Assessment

Gender and sexuality shape both the prevalence and the presentation of psychological difficulties, and they shape the assessment process itself.

Gendered patterns and their interpretation

Many conditions show marked differences in prevalence between men and women, and these differences are partly artefactual: they reflect differences in help-seeking, in symptom reporting, in diagnostic practice and in the application of criteria. The assessor should be cautious about using prevalence differences as evidence in an individual case, and should consider whether the presentation has been shaped by gendered expectations — for example, the under-recognition of depression in men and of autism in women.

Sexuality and gender identity

Lesbian, gay, bisexual, trans and gender-diverse clients experience elevated rates of mental distress, largely through minority stress: discrimination, stigma, internalised negativity and the anticipation of rejection. The assessor should not pathologise identity, should distinguish distress related to identity from distress related to minority stress, and should be aware of the history of psychiatric classification of homosexuality and of gender diversity as disorders. Assessment should be conducted in language that respects the client's own terms.

Assessment content

Where relevant, the assessment should include relationship history, experiences of discrimination and violence, and the client's own understanding of the relationship between their identity and their difficulties. These topics should be raised without assumption, and the client's decision not to discuss them should be respected.

14.11 Intersection of Multiple Social Positions

Clients occupy multiple social positions simultaneously, and the effects of those positions are not additive. A Black woman with a disability, a gay man from a rural area, a migrant woman with limited language proficiency — each faces a configuration of advantage and disadvantage that cannot be understood by considering each characteristic separately.

Intersectionality in assessment

Intersectionality, as developed in Black feminist scholarship and applied in psychology, directs attention to the ways in which systems of disadvantage interact. For assessment, the practical implications are: to gather information about the specific configuration of the client's circumstances; to avoid assuming that one characteristic explains the presentation; to consider how the client's own account reflects their experience of multiple positions; and to be alert to the possibility that the assessor's own assumptions are shaped by stereotypes about particular combinations.

The limits of categories

Categories such as "ethnic minority" or "disabled" are administratively useful and analytically crude. Their use in assessment should be accompanied by attention to the specific circumstances of the individual, and the assessor should avoid treating a category as an explanation. The category is a starting point for enquiry, not a finding.

14.12 Culturally Responsible Formulation

The output of culturally responsible assessment is a formulation that integrates cultural, linguistic and structural factors with clinical reasoning, and that is explicit about its own limits.

Structure

A culturally informed formulation addresses: the client's own explanation of the difficulty; the cultural and religious frameworks that shape it; the migration, acculturation and family context; the structural factors — discrimination, poverty, legal status — that contribute; the ways in which the assessor's framework may differ from the client's; and the points at which the formulation is uncertain.

The cultural formulation interview

The DSM-5-TR cultural formulation interview provides a structured method for eliciting the client's explanatory model, the cultural identity of the client, the stressors and supports, the role of cultural factors in the current difficulty, and the relationship between the client and the clinician. Its use is appropriate whenever the assessor's cultural knowledge is limited, and it has the additional benefit of signalling to the client that their framework is taken seriously.

Feedback across cultural difference

Feedback should be given in language the client can use, with attention to the client's explanatory model, to the role of family in decision-making, and to the practical constraints the client faces. Where the assessment's conclu-

sions conflict with the client's or family's understanding, the assessor should present the findings as a perspective rather than as a verdict, invite discussion, and record the disagreement.

Advanced Case Conference

The referral. A 45-year-old woman, who migrated eight years ago from West Africa and works as a care assistant, is referred by her general practitioner with "medically unexplained symptoms". She reports episodes of palpitations, heat in the chest, and a sensation of something moving upwards to her throat, which she attributes to a spiritual attack. She has been seen by a cardiologist and a gastroenterologist, with normal results.

The assessment. She speaks English as a second language and, although fluent in conversation, struggles with written questionnaires; she completed several with help from her daughter, which she did not initially disclose. The episodes occur in the evenings, often after arguments with her husband, and she describes feeling trapped and unsupported. She reports low mood, poor sleep and loss of interest. She does not drink alcohol and takes no medication. She describes her church community as her main support. On direct enquiry she discloses that her husband has threatened to send her back to her country of origin if she leaves him, and that her immigration status depends on the marriage.

The reasoning. The presentation includes a culturally recognised idiom of distress that overlaps with panic attacks, and the questionnaire scores cannot be interpreted normatively because of the language and assistance issues. Medical causes have been excluded by specialists. The pattern is temporally related to marital conflict, the client is in a coercive relationship with an immigration-related power imbalance, and she has limited social support outside her church. Depression is present and clinically significant.

The decision. The report describes the presentation as panic attacks occurring in the context of relational distress and coercive control, and documents the questionnaire limitations explicitly. It records the safeguarding concerns relating to coercion and immigration status, refers to a specialist service with the client's consent, and recommends treatment for depression delivered in her first language where possible. It recommends that the church community be engaged as a support, with the client's agreement, and that no joint couple work be undertaken.

> **The teaching point.** The "unexplained symptoms" were explained by a combination of a culturally shaped presentation, a relational context of coercion, and a methodological problem with the questionnaires. None of the three would have been identified without asking.

Chapter Summary

Culture shapes the expression, interpretation and reporting of distress, and assessment that ignores it misinterprets both presence and severity. Language proficiency must be assessed rather than assumed, and interpreter-mediated assessment requires briefing, documentation and interpretive caution. Translated instruments require empirical evidence of equivalence before their scores can be interpreted normatively. Bias operates at the level of construct, method and use, and fairness is integral to validity. Norms are comparisons whose relevance must be established, and where no adequate norms exist the assessor should interpret descriptively and functionally. Disability requires attention to whether the instrument measures the construct or the barrier, and accommodations require evidence that they preserve score meaning. Migration, acculturation, socioeconomic conditions and intersecting social positions shape both the presentation and its interpretation. Culturally responsible formulation integrates these factors and is explicit about its limits.

Review Questions

1. What is an idiom of distress, and why does it matter for assessment?
2. Why is self-reported language proficiency unreliable?
3. Distinguish construct bias from method bias, giving an example of each.
4. Why does scalar invariance matter for comparing group means?
5. What is diagnostic overshadowing, and how can it be avoided?

Discussion Questions

1. A client's family offers to interpret for the assessment. How do you respond?
2. How do you interpret a standardised score obtained through an interpreter?
3. What should an assessor do when the client's explanatory model conflicts with the clinical formulation?
4. How can an assessor distinguish a culturally normative belief from a delusion?
5. What are the limits of individual formulation for difficulties that are primarily structural?

Further Reading

American Psychiatric Association. (2022). *Diagnostic and statistical manual of mental disorders* (5th ed., text rev.). American Psychiatric Association Publishing.

International Test Commission. (2017). *The ITC guidelines for translating and adapting tests* (2nd ed.). International Test Commission.

Kirmayer, L. J. (2012). Cultural competence and evidence-based practice in mental health: Epistemic communities and the politics of pluralism. *Social Science & Medicine, 75*(2), 249–256.

Lewis-Fernández, R., Aggarwal, N. K., Hinton, L., Hinton, D. E., & Kirmayer, L. J. (Eds.). (2016). *The DSM-5 handbook on the cultural formulation interview*. American Psychiatric Publishing.

World Health Organization. (2001). *International classification of functioning, disability and health*. World Health Organization.

PART V

Risk, Integration and Communication

Risk assessment and safeguarding, and the integration of multimethod evidence into formulation, reports and feedback.

Chapter 15 · Chapter 16

CHAPTER 15

Risk Assessment: Suicide, Self-Harm, Violence, Abuse and Safeguarding

Learning Objectives

After working through this chapter, the reader should be able to:

- describe the principles that govern risk assessment and distinguish it from risk prediction;
- conduct a structured assessment of suicidal ideation, intent, plan and means;
- assess non-suicidal self-injury and distinguish it from suicidal behaviour;
- appraise the risk of violence and aggression using structured professional judgement;
- recognise domestic abuse and coercive control, and respond appropriately;
- follow safeguarding procedures for children and vulnerable adults;
- integrate static and dynamic risk factors with protective factors;
- document risk and communicate it in a form that supports action.

Key terms: risk assessment · risk prediction · structured professional judgement · static factor · dynamic factor · protective factor · safety planning · means restriction · self-harm · coercive control · safeguarding · duty to warn · continuity of care

Introduction

Risk assessment occupies a peculiar position in professional practice. It is the area in which the consequences of error are most severe, the evidence base is most contested, and the pressure to produce certainty is greatest.

Practitioners are asked to forecast events that are statistically rare, for individuals about whom they have limited information, in circumstances where the outcome will be reviewed in hindsight by people who know what happened.

This chapter begins from a position that is now well established in the risk literature: the aim of clinical risk assessment is not prediction but formulation, planning and mitigation. The assessor cannot reliably predict whether a particular person will attempt suicide next month. The assessor can identify the factors that elevate and reduce risk, describe the circumstances in which risk is likely to increase, specify what should happen if it does, and ensure that the person and the system around them are prepared. That is what good risk assessment delivers, and it is what the client is entitled to receive. Figure 15.1 presents risk assessment as a process in which formulation, planning and review carry more weight than a summary judgement.




Figure 15.1. Risk assessment as a process. Information, formulation, plan and review matter more than a summary judgement.

15.1 Principles of Risk Assessment

Several principles distinguish contemporary risk practice from earlier approaches that attempted to classify people as high or low risk.

Assessment is not prediction

Actuarial instruments can rank order groups by risk with modest accuracy, but their application to individuals is limited: most people in a high-risk group do not experience the outcome, and many who do were not in the high-risk group. The clinical task is to understand the particular person's risk in their particular circumstances, and to act on that understanding, rather than to assign a category that implies a forecast.

Risk is dynamic and contextual

Risk fluctuates with mental state, substance use, relationships, finances, housing and access to means. A person assessed as low risk in a stable period may become high risk within hours after a loss. Assessment should therefore identify the conditions under which risk rises, which is more useful than a summary rating.

Risk and protective factors interact

Protective factors are not simply the absence of risk factors. Reasons for living, responsibility to dependants, connection to community, engagement with treatment, and future orientation are independent contributors, and their identification is central to safety planning.

Unstructured judgement is unreliable but necessary

Research on clinical judgement has shown that unstructured risk assessment is less accurate than structured methods, and that clinicians are overconfident in their predictions. Structured professional judgement instruments improve consistency without removing the need for clinical formulation. The appropriate position combines structure, evidence and formulation.

15.2 Suicidal Thoughts and Behaviour

Suicide risk assessment is the most common risk task in mental health practice and the one most often conducted superficially.

Asking about suicidal ideation

Direct, specific questions are required: whether the person has thought about ending their life, whether they have thought about how, whether they have taken any steps, and whether they have made preparations. Asking does not increase risk; the evidence on this point is consistent and the myth that it does has cost lives. Questions should be asked in a way that invites disclosure rather than endorsement: "when things have been at their worst, have you thought about not being here?" rather than "you're not thinking of doing anything silly, are you?"

Assessing intent, plan and means

Ideation alone is of limited predictive value; the combination of intent, a specific plan, preparation, access to means and a recent attempt carries substantially more risk. The assessor should establish whether the person wants to die or wants the pain to stop, whether they have made a plan, whether they have acquired means, whether they have written a note, and whether they have told anyone. Each element modifies the formulation and the plan.

Previous attempts

A previous attempt is among the strongest predictors of a subsequent attempt, and the assessor should establish the number, method, medical severity, circumstances and aftermath of previous attempts. An attempt that the person describes as "a cry for help" is not thereby less significant; the intent of the attempt and its lethality are different dimensions.

Warning signs and acute risk

Acute risk is elevated by agitation, severe insomnia, recent loss, intoxication, access to lethal means, withdrawal from support, a sense of being a burden, hopelessness and the capacity to act on a plan. The assessor should ask about each and should record the pattern rather than a single rating.

15.3 Non-Suicidal Self-Injury

Non-suicidal self-injury is intentional self-inflicted damage to the body without suicidal intent, most commonly cutting, burning, hitting and interfering with wound healing. It is distinct from suicidal behaviour and the distinction matters for assessment and treatment.

Distinguishing the two

The functions differ: self-injury commonly serves to regulate emotion, to punish the self, to communicate distress or to feel real, whereas suicidal behaviour is oriented towards ending life. The methods differ in lethality and in body site. The two can co-occur, and self-injury is a risk factor for subsequent suicide, but treating them as equivalent leads to both over-reaction and under-recognition.

Assessing self-injury

The assessment establishes the methods, frequency, function, contexts, injuries requiring medical attention, the person's understanding of the behaviour, and its relationship to suicidal ideation. The function is the key to treatment: a person who self-injures to reduce overwhelming emotion requires emotion regulation work; a person who self-injures to communicate distress requires attention to the relational context.

Responding

The response should be non-judgemental and practical: medical care where needed, an explanation of the function of the behaviour, a plan for alternative strategies, and clear arrangements for what to do if the urge becomes overwhelming. Contracts for safety, historically used, are not evidence-based; safety planning, which is collaborative and specifies coping strategies and sources of support, is preferable.

15.4 Violence and Aggression Risk

Risk of violence arises in psychiatric, forensic, occupational and family settings, and its assessment requires a different structure from suicide risk assessment.

Structured professional judgement

The dominant approach is structured professional judgement, exemplified by instruments such as the Historical-Clinical-Risk Management-20 (HCR-20) and the Short-Term Assessment of Risk and Treatability (START). These instruments guide the assessor through a set of empirically supported factors, require a judgement about risk rather than a score, and produce a risk formulation and management plan. Their value lies in consistency, transparency and the integration of static and dynamic factors.

Historical and dynamic factors

Historical factors, such as previous violence, young age at first violence, substance use and childhood maltreatment, establish a baseline level of risk. Dynamic factors, such as current substance use, psychotic symptoms, hostility, impulsivity, lack of insight and unstable living situation, determine the current level. The assessment should identify which dynamic factors are present and modifiable.

The formulation

A violence risk formulation describes the person's typical pattern of violence (if any), the circumstances that trigger it, the likely targets, the factors that would escalate it, and the factors that would reduce it. This formulation is more useful than a risk level, because it implies what to do.

15.5 Domestic Abuse and Coercive Control

Domestic abuse is a pattern of controlling behaviour that may include physical, sexual, psychological, economic and immigration-related abuse. Coercive control is the ongoing pattern of domination that underlies much

domestic abuse and that causes severe psychological harm even in the absence of physical violence.

Recognition

Recognition requires routine, direct enquiry, conducted in private and in a way that allows disclosure. Useful questions address fear, control over money, control over contact with friends and family, threats, and escalation. Indicators include injuries with inconsistent explanations, frequent appointments with vague complaints, a partner who insists on being present, and a client who seems anxious about the partner's reaction.

Response

Where domestic abuse is disclosed, the assessment must change: the safety of the client and any children becomes the first priority; specialist services should be involved; and joint sessions or couple work are contraindicated. The assessor should record the disclosure, the actions taken and the reasoning, and should be aware of the legal framework for disclosure of information to protect a person at risk.

Risk of homicide and escalation

Separation, pregnancy, threats to kill, strangulation, access to weapons and a history of violence are established risk markers for severe harm. Where these are present, the response should be immediate and should involve specialist domestic abuse services and, where the law permits, the police.

15.6 Child and Vulnerable Adult Safeguarding

Safeguarding is the process of protecting children and adults at risk from abuse and neglect. It is governed by law and by local procedures, and it applies to all practitioners regardless of their professional role.

Children

Child safeguarding concerns include physical, sexual and emotional abuse, neglect, domestic abuse in the household, and exploitation. The assessor's

obligation is to recognise indicators, to record them factually, and to refer to the local authority. The assessor does not investigate; the assessor reports. Where a child makes a disclosure, the response should be to listen, to reassure, to record in the child's words, and to explain what will happen next.

Adults at risk

Adults may be at risk because of learning disability, mental illness, physical frailty, sensory impairment, substance dependence or social isolation. Safeguarding concerns include physical and sexual abuse, financial exploitation, neglect by carers, and self-neglect. The assessor should be familiar with the local framework, which in many jurisdictions includes a duty to make enquiries where an adult with care and support needs is at risk.

Recording and referral

Records should be factual, specific and contemporaneous, and should distinguish observation from inference. Referrals should be made within the timescales specified by local procedures. The assessor should inform the client of the referral unless doing so would place them or another person at risk.

15.7 Static and Dynamic Risk Factors

The distinction between static and dynamic factors organises risk formulation and identifies what can be changed.

Static factors

Static factors are historical and unchangeable: age at first offence, number of previous attempts, history of violence, childhood adversity, and previous admissions. They establish a baseline and are useful for stratifying risk, but they offer no points of intervention.

Dynamic factors

Dynamic factors are current and modifiable: substance use, symptoms, employment, housing, relationships, treatment engagement and hopelessness. They are the targets of intervention and the elements that change between assessments. The assessor should identify which dynamic factors are present, which are modifiable, and which are priorities.

Acute and stable dynamic factors

Dynamic factors may themselves be distinguished into stable factors that change over months (employment, relationships) and acute factors that change over hours or days (intoxication, agitation, recent loss). Acute factors are the ones that determine whether the person is safe today, and they are the ones most often omitted from risk summaries.

15.8 Protective Factors and Reasons for Living

Protective factors reduce the likelihood of an outcome even in the presence of risk, and they are the foundation of safety planning.

Identifying protective factors

Protective factors include reasons for living, responsibility to children or dependants, religious or moral objections to suicide, connection to community, engagement with treatment, future orientation, problem-solving capacity, and social support. The assessor should elicit these explicitly, since clients often do not volunteer them and since their identification is itself therapeutic.

Their limits

Protective factors do not cancel risk, and their presence should not be used to justify inaction. A person with strong reasons for living may still attempt suicide during an acute crisis. The assessor should record protective factors as resources to be mobilised, not as reasons that risk can be discounted.

Using protective factors in formulation

Protective factors belong in the formulation as conditions that make certain plans feasible: a parent who is committed to their children may be more likely to engage with a plan that involves them, and a person with strong community ties may be more likely to use a support that is available through that community.

15.9 Structured Professional Judgement

Structured professional judgement combines the use of evidence-based risk factors, the assessor's clinical judgement and the involvement of the client in the formulation and plan.

The method

The method proceeds in five steps: gather information from multiple sources; identify the relevant risk factors using a structured framework; formulate the risk in terms of pattern, circumstances, triggers and likely escalation; develop a management plan that addresses the modifiable factors; and record the reasoning and the review arrangements.

The role of instruments

Instruments structure the process and improve consistency. They do not replace formulation, and their scores should not be reported as risk levels without interpretation. An instrument that identifies twelve risk factors present tells the assessor nothing unless it also tells them which factors matter for this person and what to do about them.

The client's involvement

Where possible, the client should be involved in the risk formulation and the safety plan. Involvement improves the plan's feasibility, respects the client's autonomy, and provides information that the assessor would not otherwise have. Where the client cannot be involved — because of acute psychosis, intoxication or coercive control — the reason should be recorded.

15.10 Safety Planning and Immediate Intervention

Safety planning is a collaborative process that produces a written plan for what the person will do when risk escalates.

Components of a safety plan

A safety plan typically includes: the person's warning signs; internal coping strategies; people and places that provide distraction; people the person can contact for help; professionals and services to contact in a crisis; and steps to make the environment safer, including means restriction. The plan should be written, should be in the person's own words where possible, and should be reviewed and updated.

Means restriction

Access to means is one of the few modifiable factors with strong evidence for reducing suicide deaths. The assessor should discuss means restriction directly — medication, firearms, pesticides, ligature points — and should involve family members where the person consents and where their involvement is safe. Means restriction is more effective than contracts for safety, which have no evidence base.

Immediate intervention

Where risk is imminent, the response should be immediate: continuous observation where the setting permits, urgent referral to crisis services or emergency department, involvement of emergency services, and removal of means. The assessor should record what was done, by whom, and what the client was told.

15.11 Documentation and Communication of Risk

Risk documentation is read in emergencies, in reviews and, occasionally, in courts. Its purpose is to support action.

What to record

Records should state what was asked, what was disclosed, what was observed, the assessor's formulation, the reasoning behind it, the actions taken, the communication with others, and the review arrangements. They should distinguish fact from inference and should record uncertainty rather than concealing it.

Communication with other parties

Risk information should be shared with relevant professionals, with the client's consent where possible and without it where necessary to protect life. The legal framework varies by jurisdiction, and the assessor should know the local rules on confidentiality and disclosure. Where information is shared without consent, the decision and its justification should be recorded.

Communicating with the client

Clients should be told what the assessor is concerned about, what will happen next and why. This is both an ethical requirement and a clinical one: a client who understands the plan is more likely to engage with it. Where the assessor is obliged to act against the client's wishes, the client should be told what is happening and why, in language they can understand.

15.12 Reassessment and Continuity of Care

Risk assessment is not a single event. It should be repeated when circumstances change, when the person moves between services, and at specified intervals.

Triggers for reassessment

Reassessment is triggered by a change in mental state, a new loss or stressor, a change in substance use, discharge from hospital, a change in living situation, a new relationship, and any incident of self-harm or aggression. Services should specify these triggers in their procedures, and individual plans should name them.

Transitions of care

The period after discharge from inpatient care is a period of elevated risk, and it requires specific planning: an appointment within a defined period, contact details, a named professional, and a plan for what to do if the person cannot be reached. Transitions between services are similarly high-risk, and the receiving service should be given the risk formulation, not merely the risk level.

Review and learning

Services should review serious incidents and near misses, not to allocate blame but to identify what could have been done differently. Individual practitioners should review their own risk assessments when outcomes differ from expectations, since this is the most effective form of calibration available.

Advanced Case Conference

The referral. A 52-year-old man is referred by his general practitioner after a relationship breakdown. He has a history of two previous suicide attempts, both by overdose, the most recent eight years ago. He lives alone, has recently lost his job, and drinks heavily.

The assessment. He describes passive suicidal ideation — "I wouldn't mind not waking up" — but denies intent or plan. He reports that his ex-partner has stopped contact and that he has not seen his children for three weeks. He has a stock of prescribed medication at home, including a tricyclic antidepressant that is dangerous in overdose. He reports drinking a bottle of spirits daily and has had one episode of alcohol withdrawal. He describes his dog as "the only reason I get up". He says he would not want his children to find him.

The formulation. Static risk factors include two previous attempts and male sex; dynamic factors include recent loss, unemployment, social isolation, heavy drinking, access to a lethal means and a sense of burdensomeness. Protective factors include his children, his dog and his expressed wish not to be found by his children. Acute risk is elevated by intoxication and by the recent loss, but intent is currently low. The combination of a dangerous means, heavy drinking and social isolation means that risk could escalate rapidly with little warning.

The decision. The safety plan includes: removal of the tricyclic medication with the general practitioner's agreement and substitution with a safer alternative; a plan for the dog to be cared for by a neighbour if he is admitted; daily contact with a named professional for two weeks; an appointment with the substance service within a week; and a written crisis plan with the number of the local crisis line. The report records the formulation, the reasoning, the actions taken and the review date.

The teaching point. No prediction was made. The assessment identified the factors that would make escalation likely, modified the one with the strongest evidence — access to means — and built a plan around the factors that mattered to him.

Chapter Summary

Risk assessment is a process of formulation, planning and mitigation rather than prediction. Suicidal risk requires direct enquiry about ideation, intent, plan, means and previous attempts, and acute risk is elevated by agitation, insomnia, intoxication, loss and access to means. Non-suicidal self-injury is distinct from suicidal behaviour and requires assessment of function. Violence risk is best assessed through structured professional judgement, combining historical and dynamic factors in a formulation that specifies circumstances and targets. Domestic abuse and coercive control require routine enquiry, immediate safety planning and a prohibition on joint work. Safeguarding procedures apply to children and adults at risk and require factual recording and timely referral. Static factors establish baseline risk, dynamic factors identify what can change, and protective factors are resources to be mobilised rather than reasons to discount risk. Safety planning and means restriction are the interventions with the strongest evidence, and documentation should support action, continuity and review.

Review Questions

1. Why is risk assessment better described as formulation than prediction?
2. What distinguishes non-suicidal self-injury from suicidal behaviour?

3. Why are contracts for safety no longer recommended?
4. What are the advantages of structured professional judgement over unstructured judgement?
5. What triggers should prompt a reassessment of risk?

Discussion Questions

1. A client denies suicidal ideation but has recently given away possessions. What do you do?
2. How should an assessor respond when a client discloses domestic abuse but asks that nothing be done?
3. What are the ethical issues in sharing risk information with a partner or family member?
4. How would you plan the discharge of a client who has been admitted after a serious attempt?
5. Should risk assessment instruments be used to make decisions about detention? Why or why not?

Further Reading

Douglas, K. S., Hart, S. D., Webster, C. D., & Belfrage, H. (2013). *HCR-20 V3: Assessing risk for violence*. Mental Health, Law, and Policy Institute, Simon Fraser University.

Large, M., Kaneson, M., Myles, N., Myles, H., Gunaratne, P., & Ryan, C. (2016). Meta-analysis of longitudinal cohort studies of suicide risk assessment among psychiatric patients: Heterogeneity in results and lack of improvement over time. *PLOS ONE, 11*(6), e0156322.

Stanley, B., & Brown, G. K. (2012). Safety planning intervention: A brief intervention to mitigate suicide risk. *Cognitive and Behavioral Practice, 19*(2), 256–264.

Stark, E. (2007). *Coercive control: How men entrap women in personal life*. Oxford University Press.

World Health Organization. (2021). *Live life: An implementation guide for suicide prevention in countries*. World Health Organization.

CHAPTER 16

Integrated Case Formulation, Differential Diagnosis, Report Writing and Feedback

Learning Objectives

After working through this chapter, the reader should be able to:

- integrate multimethod evidence using an explicit and auditable procedure;
- weigh conflicting findings by examining their provenance and quality;
- treat differential diagnosis as hypothesis testing rather than pattern matching;
- construct formulations that go beyond diagnostic labels and predict treatment response;
- write psychological reports that answer the referral question for each audience;
- communicate uncertainty in ways that support rather than undermine decisions;
- use feedback as a clinical intervention and as a source of calibration;
- appraise digital tools and artificial intelligence in assessment with appropriate scepticism.

Key terms: integration · conflicting evidence · hypothesis testing · formulation · report structure · uncertainty communication · collaborative feedback · quality assurance · peer consultation · algorithmic interpretation · professional accountability

Introduction

The preceding chapters have addressed the components of advanced assessment: questioning, interviewing, measurement, instrument-specific methods and particular clinical populations. This final chapter addresses the activity that binds them — integration — and the products through which integration reaches other people: the formulation, the report and the feedback conversation.

Integration is the point at which technical competence becomes clinical judgement, and it is the point at which most assessments either succeed or fail. An assessment that produces accurate scores but no coherent account of the person has not done its job; so has one that produces a coherent account unsupported by the evidence. The discipline required is to hold both: to construct a formulation that explains, predicts and can be tested, while remaining accountable to the data that produced it. Figure 16.1 follows the evidence from integration through formulation and writing to the feedback discussion.




Figure 16.1. Integration and communication. The evidence is weighed, formulated, written and discussed; each stage is an opportunity to lose or gain accuracy.

16.1 Integrating Multimethod Evidence

Integration is not the accumulation of findings but the construction of an argument. The assessor arrays the evidence, weighs it and states a conclusion whose confidence is proportionate to the evidence.

The integration matrix

A practical device is a matrix in which the rows are the hypotheses under consideration and the columns are the sources of evidence: interview, observation, informant report, records, test scores and functional information. Each cell records whether the source supports, contradicts or is silent on the hypothesis. The matrix makes reasoning visible, exposes gaps, and identifies which hypotheses rest on a single source. It also prevents the common error of treating the most memorable finding as the most important one.

Weighing evidence

Weighting depends on four considerations: the quality of the source (a well-validated instrument administered correctly versus an impression formed in a single interview); its independence (two sources that derive from the same informant are not independent); its relevance (evidence about a construct that is adjacent to the hypothesis is weaker than evidence about the construct itself); and its recency (for questions about current state, recent evidence is stronger).

Reaching a conclusion

The conclusion should identify the best-supported hypothesis, the alternatives that remain open, the evidence that would change the conclusion, and the confidence with which it is held. Where the evidence does not support any hypothesis, that is a conclusion and should be stated. Where the evidence supports several, the conclusion should state which is primary for the purpose at hand — treatment, risk management, accommodation — since the priority may differ by purpose.

16.2 Weighing Conflicting Findings

Conflict among sources is the norm rather than the exception, and the response to conflict distinguishes competent from incompetent integration.

Investigating rather than averaging

Averaging incompatible findings produces a conclusion that no source supports. The correct response is to investigate why the sources disagree: differences in setting, in informant perspective, in the conditions of administration, in the construct measured, or in the honesty of reporting. The investigation usually resolves the conflict, and when it does not, the unresolved conflict is itself a finding to be reported.

Common patterns of conflict

Common patterns include self-report that is more severe than observed functioning (which may indicate concealment in the session, situational variation, or over-reporting), informant report that is more severe than self-report (which may indicate limited insight, concealment from the assessor, or an informant with their own investment in the severity), and test scores that are lower than functional performance (which may indicate invalid performance, an unfamiliar testing format, or genuine compensation).

Reporting conflict

Where conflict remains unresolved, the report should present it, describe the competing explanations and their implications, and state which explanation the assessor considers more probable and why. A report that conceals the conflict in order to present a coherent narrative is less honest and less useful than one that presents it.

16.3 Differential Diagnosis as Hypothesis Testing

Differential diagnosis is the application of scientific reasoning to a clinical question. The assessor generates hypotheses, identifies the observations

that would discriminate among them, gathers those observations, and revises the hypotheses accordingly.

Generating the hypotheses

The hypothesis set should include the most likely explanation, the most consequential explanation that must not be missed, and the explanation that the client or referrer favours. The set should also include explanations that are not diagnoses: developmental conditions, substance effects, medical conditions, contextual and relational factors, and normal variation.

Specifying the discriminating evidence

For each pair of hypotheses, the assessor specifies the findings that would separate them. This converts the assessment plan into a set of targeted questions and observations, and it makes the assessment auditable: a reader can see which discriminations were attempted and which were not.

Revising rather than confirming

Hypotheses should be revised as evidence accumulates, and the assessor should record the revision. A record that shows a single hypothesis from beginning to end, with all evidence supporting it, is a record of confirmation bias rather than of assessment. The most valuable records show what was considered and discarded, and why.

16.4 Formulation beyond Diagnostic Labels

A diagnosis classifies; a formulation explains. The formulation is what makes the assessment useful for treatment, and it is the part of the report most often missing or perfunctory.

Requirements of a formulation

A good formulation is explanatory (it accounts for why this presentation developed and persists), individual (it is specific to this person rather than a generic account of the disorder), testable (it predicts what will happen un-

der specified conditions), useful (it identifies points of intervention) and collaborative (it can be discussed with the client).

Structure

A workable structure addresses: the presenting problem and its development; predisposing factors; precipitating factors; maintaining factors; protective factors; the current context; the formulation itself as a narrative account; and the implications for intervention. The maintaining factors carry most of the clinical weight, because they are the most modifiable.

Formulation in different traditions

Cognitive behavioural formulations identify maintaining cycles of thought, emotion and behaviour; psychodynamic formulations identify repeating relational patterns and defences; systemic formulations identify interactional patterns within relationships; narrative formulations identify the stories through which the person understands their difficulties. The assessor need not be committed to one tradition, but should be explicit about the one being used, since different traditions generate different interventions.

16.5 Linking Assessment to Treatment Planning

The link between assessment and treatment is the recommendation, and recommendations are where assessment is most often wasted.

Specifying the target

Recommendations should identify what is to be changed, not merely what is to be done. “Cognitive behavioural therapy” is a treatment; “cognitive behavioural therapy targeting avoidance of social situations and the belief that others will judge him as incompetent” is a plan. The target follows from the formulation, and the formulation should make it obvious.

Sequencing

Recommendations should be sequenced. Some targets must be addressed before others: substance use before trauma-focused work where the substance use prevents engagement; medical stabilisation before psychological intervention where a medical condition is contributing; safety planning before any intervention that might increase distress. The reasoning for the sequence should be recorded.

Feasibility

Recommendations should be feasible in the setting where they will be implemented. Waiting lists, funding, the client's caring responsibilities, transport and language all constrain what is possible. A recommendation that cannot be implemented is not neutral; it can damage the client's trust and the referrer's confidence in assessment.

Specifying what would count as progress

A plan should specify how progress will be recognised and what would prompt a revision. This is the practical expression of the formulation's testability, and it converts the assessment into something that can be evaluated.

16.6 Writing Clear Psychological Reports

The report is the assessment's public form. It is read by referrers, clients, families, tribunals and courts, and its quality determines whether the assessment has any effect.

Structure

A conventional structure includes: identifying information; reason for referral; sources of information; background; behavioural observations and mental status; assessment methods; results by domain; formulation; diagnostic conclusions where justified; strengths and protective factors; recommendations; and limitations. The structure can be varied, but the elements should all be present, and the report should answer the referral question explicitly and early.

Writing for the reader

Different audiences need different things. A general practitioner needs a clear summary, a diagnosis if one is warranted, and specific recommendations. A tribunal needs the evidence, the reasoning and the limits. A client needs language they can understand and a formulation they recognise. Where a report serves several audiences, a summary at the beginning and a clearly labelled section for the client can meet most needs.

Language

Reports should be written in plain, precise professional English. Jargon should be explained or avoided. Diagnostic terms should be used consistently and defined at first use. Pejorative terms should be excluded. Sentences should be short enough to be understood on one reading, and the report should be free of unnecessary hedging and of unjustified certainty.

Length and proportionality

The report should be as long as the question requires and no longer. A short report that answers the question is more useful than a long one that documents the process. Where an assessment has been extensive, the detail can be placed in appendices so that the main report remains readable.

16.7 Communicating Uncertainty

Uncertainty is inherent in assessment, and its communication is a professional skill rather than an admission of inadequacy.

Why uncertainty must be communicated

Decisions made on the basis of overstated certainty can harm clients and mislead referrers. A report that presents a provisional conclusion as settled may lead to a treatment that is inappropriate, or to a decision — about custody, employment or liberty — that would have been different had the uncertainty been visible.

How to communicate it

Uncertainty should be stated specifically: what is uncertain, why, how much it matters and what would resolve it. "The diagnosis is uncertain" is uninformative; "the evidence supports a moderate depressive episode, but the duration depends on the client's dating of onset, which conflicts with the general practitioner's record; a review in six weeks with a symptom diary would resolve it" is useful.

The limits of hedging

Excessive hedging is also a failure. A report that hedges every statement leaves the reader unable to act. The appropriate balance is to be decisive where the evidence permits and explicit about uncertainty where it does not, and to distinguish clearly between the two.

16.8 Feedback as a Clinical Intervention

Feedback is not the delivery of a verdict but a structured conversation in which the findings are discussed, tested and connected to action.

Principles

Feedback should be collaborative, specific, developmental and connected to the client's goals. It should begin with what the assessment found that is positive or resourceful, present the difficulties in behavioural terms, invite the client's perspective, and end with a plan that the client has contributed to.

The evidence base

Research on therapeutic assessment has shown that collaborative feedback can reduce symptoms and improve engagement, particularly when the client is involved in interpreting the findings. The mechanism appears to involve the restoration of a coherent self-narrative and the experience of being understood. Feedback that is delivered as a lecture has no such effect and may be harmful.

Handling disagreement

Where the client disagrees with the findings, the disagreement should be explored rather than dismissed. The client may be right; the assessment may have missed context; or the finding may be correct but premature. The assessor should record the client's response and any revision that follows.

Feedback to families and systems

Where the assessment concerns a child, a couple or a family, feedback must be managed across multiple participants, with attention to safety, confidentiality and the relationships among them. Where the assessment has identified harm within the system, feedback must be handled with particular care and with reference to safeguarding procedures.

16.9 Ethical and Legal Responsibilities

The final chapter of a textbook on assessment is the appropriate place to state the responsibilities that frame everything else.

Competence

The assessor should practise within their competence, seek supervision where the presentation or the question lies outside it, and decline referrals that require expertise they do not hold. Competence includes cultural competence, which requires ongoing learning rather than a fixed body of knowledge.

Consent and confidentiality

Consent should be informed, specific and recorded. Confidentiality should be explained, including its limits. Where information must be disclosed without consent, the decision and its reasoning should be recorded.

Duties to third parties

In most jurisdictions, the assessor owes duties to people other than the client: to warn or protect potential victims of violence, to report child abuse,

to report risk to the public. The precise duties vary by jurisdiction, and the assessor should know the local framework.

Record keeping

Records should be accurate, contemporaneous, legible and stored securely. They should be sufficient for another professional to understand what was done and why. They are increasingly accessible to clients and may be disclosed in legal proceedings.

The limits of the role

The assessor is not an investigator, a judge or a police officer. The role is to assess, formulate and communicate, and to act within the legal and ethical framework when risk or harm is identified. Recognising the limits of the role is part of competence.

16.10 Digital Assessment and Artificial Intelligence

Digital tools are transforming assessment, and their use raises questions that the profession has not fully resolved.

Current applications

Applications include online administration of questionnaires, computer-adaptive testing, automated scoring and interpretation, ecological momentary assessment, digital phenotyping through smartphone sensors, and machine learning models trained on clinical data to predict outcomes. Each has potential benefits: accessibility, frequency of measurement, reduced scoring error and the detection of patterns that clinicians miss.

Risks and limitations

The risks include validation gaps (a tool validated in one population or format may not generalise), opacity (machine learning models whose reasoning cannot be inspected), automation bias (clinicians deferring to algorithmic output), data protection and privacy, unequal access, and the possibility that a model's predictions encode existing inequities. Interpreta-

tion generated automatically cannot know the client, the context or the purpose of the assessment.

Professional responsibility

The professional obligation to justify conclusions in terms of evidence about this client cannot be delegated to software. Where digital tools are used, the assessor should know their validation, record their use, verify their output, and remain accountable for the interpretation. Regulatory frameworks for medical devices and for automated decision-making are developing, and practitioners should keep abreast of the requirements in their jurisdiction.

16.11 Quality Assurance and Peer Consultation

Individual competence is necessary but not sufficient; the quality of assessment depends also on the systems within which it is conducted.

Individual practices

Individual quality assurance includes routine use of scoring checks, confidence intervals and base rates; recording of hypotheses and their revision; review of assessments in which the outcome differed from the prediction; and participation in continuing professional development that includes assessment specifically.

Peer consultation

Peer consultation — the routine discussion of assessments with a colleague — is the most effective single practice for improving judgement. It exposes reasoning to challenge, identifies blind spots, and provides the calibration that individual reflection cannot. It should be routine rather than reserved for difficult cases, and it should include the cases that went well, since these are where overconfidence develops.

Service-level practices

Services can support quality through audit of reports against standards, review of serious incidents, monitoring of assessment outcomes against later information, training in specific instruments, and supervision arrangements that include assessment. Where services measure the quality of their reports, the quality improves; where they do not, it varies with the individual practitioner.

16.12 Advanced Case Conference and Final Synthesis

The final section of the final chapter returns to the case conference format used throughout the book, this time as a synthesis of the whole.

The method

A case conference presents the referral question, the evidence, the reasoning, the formulation, the conclusions and the recommendations, and invites challenge. Its purpose is to expose the reasoning to informed scrutiny before the report is finalised, and to give the assessor the benefit of perspectives they do not have.

The discipline

The discipline of presenting a case to colleagues requires the assessor to make their reasoning explicit, which is the same discipline required by a well-written report. The case conference is therefore both a quality assurance mechanism and a training method, and services that hold them regularly produce better assessments.

Closing

Advanced assessment is a craft that improves with deliberate practice, supervision and honest review. The instruments will change; the diagnostic systems will be revised; the digital tools will become more capable. What will not change is the requirement to reason carefully from evidence to con-

clusion, to state the limits of that conclusion, and to communicate it in a way that helps the person it concerns. That requirement is the subject of this book, and meeting it is the mark of the advanced practitioner.

Advanced Case Conference

The referral. A 61-year-old woman is referred by her general practitioner for assessment before a decision about whether she can return to work as a primary school teacher. She has been absent for five months with what was initially diagnosed as depression, and then as "possible early dementia" after she reported memory difficulties. Two cognitive screens have been borderline. The question is whether she has a cognitive impairment and whether she can return to teaching.

The evidence. The interview establishes that she has been profoundly depressed since her husband's death eighteen months ago, with early waking, weight loss of ten kilograms, and pervasive anhedonia. Her memory complaints began at the same time and are worse when she is low. Cognitive assessment shows high-average verbal knowledge, average perceptual reasoning, low-average working memory and processing speed, and memory scores in the low-average range with a strong benefit from cueing. Performance validity is adequate. She slept four hours the night before the assessment and had not eaten. Two informants describe her as "not herself" since the bereavement but "sharp as anything" when discussing her grandchildren. A dementia screen completed by her daughter is in the normal range. There is no history of cognitive decline before the bereavement.

The reasoning. The presentation is consistent with a severe depressive episode with cognitive impairment, a well-recognised phenomenon sometimes described as pseudodementia, and inconsistent with a neurodegenerative process: the onset was abrupt and coincident with bereavement, the memory pattern is one of retrieval difficulty rather than encoding failure, verbal knowledge is preserved, informants describe preserved function in engaging contexts, and there is no progressive trajectory. The "possible early dementia" diagnosis appears to have been based on borderline screens obtained during the depressive episode, without premorbid comparison or informant data.

The decision. The report declines to diagnose a neurocognitive disorder, explains the basis for that conclusion, and recommends treatment for depression before any determination of cognitive status. On fitness to return to teaching, it states that a return is not currently indicated, that the prognosis is likely to be favourable with treatment, and that a repeat cognitive assessment should be conducted when the depression has remitted. It recommends that the "possible dementia" label be removed from the primary care record, and states why.

The teaching point. The most consequential intervention in this assessment was a negative conclusion: removing a diagnosis that was inaccurate, stigmatising and likely to follow the client for years. Advanced assessment is not only the production of findings; it is also the correction of conclusions that were reached without adequate evidence.

Chapter Summary

Integration is the construction of an argument from evidence, conducted through an explicit procedure that arrays hypotheses against sources, weighs evidence by quality, independence, relevance and recency, and states a conclusion with proportionate confidence. Conflicting findings should be investigated rather than averaged, and unresolved conflict should be reported. Differential diagnosis is hypothesis testing, and the record should show which hypotheses were considered and discarded. Formulations must explain, individualise, predict and identify points of intervention. Recommendations should specify targets, sequence, feasibility and what would count as progress. Reports should answer the referral question for their audiences, in plain professional prose and with explicit and specific statements of uncertainty. Feedback is a clinical intervention when it is collaborative. Ethical and legal responsibilities frame the whole enterprise, and digital tools change its mechanics without transferring professional accountability. Quality assurance and peer consultation are the practices that sustain competence over time.

Review Questions

1. What four considerations determine the weight given to a piece of assessment evidence?
2. Why should conflicting findings be investigated rather than averaged?
3. What are the five requirements of a good formulation?
4. How should uncertainty be communicated in a report?
5. Why is collaborative feedback more effective than a summary of findings?

Discussion Questions

1. A referrer asks for a diagnosis that you believe is not supported by the evidence. How do you respond?
2. How would you write a report that serves a general practitioner, a tribunal and the client?
3. What are the risks of using an automated interpretive report in a medico-legal assessment?
4. How should a service organise peer consultation so that it improves rather than audits practice?
5. Reflecting on this book, which single change to your practice would most improve the quality of your assessments?

Further Reading

American Educational Research Association, American Psychological Association, & National Council on Measurement in Education. (2014). *Standards for educational and psychological testing*. American Educational Research Association.

Finn, S. E. (2007). *In our clients' shoes: Theory and techniques of therapeutic assessment*. Lawrence Erlbaum.

Groth-Marnat, G., & Wright, A. J. (2016). *Handbook of psychological assessment* (6th ed.). Wiley.

Kahneman, D. (2011). *Thinking, fast and slow*. Farrar, Straus and Giroux.

Ownby, R. L., & Wallbrown, F. H. (2018). *Psychological reports: A guide to report writing in professional psychology* (5th ed.). Wiley.

World Health Organization. (2024). *Clinical descriptions and diagnostic requirements for ICD-11 mental, behavioural and neurodevelopmental disorders*. World Health Organization.

References

This list contains every work cited in the text and in the further reading at the end of each chapter. Entries follow APA 7th edition and are listed once, even where they are cited in several chapters.

American Educational Research Association, American Psychological Association, & National Council on Measurement in Education. (2014). *Standards for educational and psychological testing*. American Educational Research Association.

American Psychiatric Association. (2022). *Diagnostic and statistical manual of mental disorders* (5th ed., text rev.). American Psychiatric Association Publishing.

Andreasen, N. C. (1984). *The Scale for the Assessment of Positive Symptoms (SAPS)*. University of Iowa.

Babor, T. F., Higgins-Biddle, J. C., Saunders, J. B., & Monteiro, M. G. (2001). *AUDIT: The Alcohol Use Disorders Identification Test: Guidelines for use in primary care* (2nd ed.). World Health Organization.

Barlow, D. H. (2004). *Anxiety and its disorders: The nature and treatment of anxiety and panic* (2nd ed.). Guilford Press.

Ben-Porath, Y. S., & Tellegen, A. (2008). *MMPI-2-RF: Manual for administration, scoring, and interpretation*. University of Minnesota Press.

Brennan, K. A., Clark, C. L., & Shaver, P. R. (1998). Self-report measurement of adult attachment: An integrative overview. In J. A. Simpson & W. S. Rholes (Eds.), *Attachment theory and close relationships* (pp. 46–76). Guilford Press.

Cronbach, L. J., & Meehl, P. E. (1955). Construct validity in psychological tests. *Psychological Bulletin, 52*(4), 281–302.

Croskerry, P. (2003). The importance of cognitive errors in diagnosis and strategies to minimize them. *Academic Medicine, 78*(8), 775–780.

Douglas, K. S., Hart, S. D., Webster, C. D., & Belfrage, H. (2013). *HCR-20 V3: Assessing risk for violence*. Mental Health, Law, and Policy Institute, Simon Fraser University.

Dunn, T. J., Baguley, T., & Brunsden, V. (2014). From alpha to omega: A practical solution to the pervasive problem of internal consistency estimation. *British Journal of Psychology, 105*(3), 399–412.

Epstein, N. B., Baldwin, L. M., & Bishop, D. S. (1983). The McMaster Family Assessment Device. *Journal of Marital and Family Therapy, 9*(2), 171–180.

Finn, S. E. (2007). *In our clients' shoes: Theory and techniques of therapeutic assessment*. Lawrence Erlbaum.

Finn, S. E., & Tonsager, M. E. (1997). Information-gathering and therapeutic models of assessment: Complementary paradigms. *Psychological Assessment, 9*(4), 374–385.

First, M. B., Williams, J. B. W., Benjamin, L. S., & Spitzer, R. L. (2016). *Structured Clinical Interview for DSM-5 Personality Disorders (SCID-5-PD)*. American Psychiatric Association Publishing.

First, M. B., Williams, J. B. W., Karg, R. S., & Spitzer, R. L. (2016). *Structured Clinical Interview for DSM-5 Disorders, Clinician Version (SCID-5-CV)*. American Psychiatric Association Publishing.

Fletcher, J. M., Lyon, G. R., Fuchs, L. S., & Barnes, M. A. (2019). *Learning disabilities: From identification to intervention* (2nd ed.). Guilford Press.

Flynn, J. R. (1987). Massive IQ gains in 14 nations: What IQ tests really measure. *Psychological Bulletin, 101*(2), 171–191.

Folstein, M. F., Folstein, S. E., & McHugh, P. R. (1975). "Mini-mental state": A practical method for grading the cognitive state of patients for the clinician. *Journal of Psychiatric Research, 12*(3), 189–198.

George, C., Kaplan, N., & Main, M. (1985). *Adult Attachment Interview* [Unpublished manuscript]. Department of Psychology, University of California, Berkeley.

Gottman, J. M. (1999). *The marriage clinic: A scientifically based marital therapy*. W. W. Norton.

Groth-Marnat, G., & Wright, A. J. (2016). *Handbook of psychological assessment* (6th ed.). Wiley.

Grove, W. M., Zald, D. H., Lebow, B. S., Snitz, B. E., & Nelson, C. (2000). Clinical versus mechanical prediction: A meta-analysis. *Psychological Assessment, 12*(1), 19–30.

Holland, J. L. (1997). *Making vocational choices: A theory of vocational personalities and work environments* (3rd ed.). Psychological Assessment Resources.

International Test Commission. (2017). *The ITC guidelines for translating and adapting tests* (2nd ed.). International Test Commission.

Kahneman, D. (2011). *Thinking, fast and slow*. Farrar, Straus and Giroux.

Kane, M. T. (2013). Validating the interpretations and uses of test scores. *Journal of Educational Measurement, 50*(1), 1–73.

Kirmayer, L. J. (2012). Cultural competence and evidence-based practice in mental health: Epistemic communities and the politics of pluralism. *Social Science & Medicine, 75*(2), 249–256.

Kovacs, K., & Conway, A. R. A. (2016). Process overlap theory: A unified account of the general factor of intelligence. *Psychological Inquiry, 27*(3), 151–177.

Kroenke, K., Spitzer, R. L., & Williams, J. B. W. (2001). The PHQ-9: Validity of a brief depression severity measure. *Journal of General Internal Medicine, 16*(9), 606–613.

Landis, J. R., & Koch, G. G. (1977). The measurement of observer agreement for categorical data. *Biometrics, 33*(1), 159–174.

Large, M., Kaneson, M., Myles, N., Myles, H., Gunaratne, P., & Ryan, C. (2016). Meta-analysis of longitudinal cohort studies of suicide risk assessment among psychiatric patients: Heterogeneity in results and lack of improvement over time. *PLOS ONE, 11*(6), e0156322.

Lewis-Fernández, R., Aggarwal, N. K., Hinton, L., Hinton, D. E., & Kirmayer, L. J. (Eds.). (2016). *The DSM-5 handbook on the cultural formulation interview*. American Psychiatric Publishing.

Lezak, M. D., Howieson, D. B., Bigler, E. D., & Tranel, D. (2012). *Neuropsychological assessment* (5th ed.). Oxford University Press.

Lincoln, T. M., & Pedersen, A. (2019). *An overview of the psychosis continuum and its assessment*. In C. A. Essau & P. H. Oppen (Eds.), *Assessment of mental health problems*. Oxford University Press.

Livesley, W. J., & Larstone, R. (2018). *Handbook of personality disorders: Theory, research, and treatment* (2nd ed.). Guilford Press.

Lord, C., Rutter, M., DiLavore, P. C., Risi, S., Gotham, K., & Bishop, S. L. (2012). *Autism Diagnostic Observation Schedule* (2nd ed.). Western Psychological Services.

McCrae, R. R., Costa, P. T., Jr., & Martin, T. A. (2005). The NEO-PI-3: A more readable revised NEO Personality Inventory. *Journal of Personality Assessment, 84*(3), 261–270.

McNeish, D. (2018). Thanks coefficient alpha, we'll take it from here. *Psychological Methods, 23*(3), 412–433.

Meredith, W. (1993). Measurement invariance, factor analysis and factorial invariance. *Psychometrika, 58*(4), 525–543.

Messick, S. (1995). Validity of psychological assessment: Validation of inferences from persons' responses and performances as scientific inquiry into score meaning. *American Psychologist, 50*(9), 741–749.

Meyer, G. J., Finn, S. E., Eyde, L. D., Kay, G. G., Moreland, K. L., Dies, R. R., Eisman, E. J., Kubiszyn, T. W., & Reed, G. M. (2001). Psychological testing and psychological assessment: A review of evidence and issues. *American Psychologist, 56*(2), 128–165.

Mihura, J. L., Meyer, G. J., Dumitrascu, N., & Bombel, G. (2013). The validity of individual Rorschach variables: Systematic reviews and meta-analyses of the Comprehensive System. *Psychological Bulletin, 139*(3), 548–605.

Miller, W. R., & Rollnick, S. (2013). *Motivational interviewing: Helping people change* (3rd ed.). Guilford Press.

Minuchin, S. (1974). *Families and family therapy*. Harvard University Press.

Morey, L. C. (2007). *Personality Assessment Inventory professional manual* (2nd ed.). Psychological Assessment Resources.

Nasreddine, Z. S., Phillips, N. A., Bédirian, V., Charbonneau, S., Whitehead, V., Collin, I., Cummings, J. L., & Chertkow, H. (2005). The Montreal Cognitive Assessment, MoCA: A brief screening tool for mild cognitive impairment. *Journal of the American Geriatrics Society, 53*(4), 695–699.

Nordgaard, J., Sass, L. A., & Parnas, J. (2013). The psychiatric interview: Validity, structure, and subjectivity. *European Archives of Psychiatry and Clinical Neuroscience, 263*(4), 353–364.

Nutt, D. J., King, L. A., Saulsbury, W., & Blakemore, C. (2007). Development of a rational scale to assess the harm of drugs of potential misuse. *The Lancet, 369*(9566), 1047–1053.

Ownby, R. L., & Wallbrown, F. H. (2018). *Psychological reports: A guide to report writing in professional psychology* (5th ed.). Wiley.

Paris, J. (2020). *Social factors in the personality disorders: Finding a niche* (2nd ed.). Cambridge University Press.

Robins, E., & Guze, S. B. (1970). Establishment of diagnostic validity in psychiatric illness: Its application to schizophrenia. *American Journal of Psychiatry, 126*(7), 983–987.

Sattler, J. M. (2018). *Assessment of children: Cognitive foundations and applications* (6th ed.). Jerome M. Sattler.

Saunders, J. B., Aasland, O. G., Babor, T. F., de la Fuente, J. R., & Grant, M. (1993). Development of the Alcohol Use Disorders Identification Test (AUDIT): WHO collaborative project on early detection of persons with harmful alcohol consumption—II. *Addiction, 88*(6), 791–804.

Schneider, W. J., & McGrew, K. S. (2018). The Cattell–Horn–Cattell theory of cognitive abilities. In D. P. Flanagan & E. M. McDonough (Eds.), *Contemporary intellectual assessment: Theories, tests, and issues* (4th ed., pp. 73–163). Guilford Press.

Sheehan, D. V., Lecrubier, Y., Sheehan, K. H., Amorim, P., Janavs, J., Weiller, E., Hergueta, T., Baker, R., & Dunbar, G. C. (1998). The Mini-International Neuropsychiatric Interview (M.I.N.I.): The development and validation of a structured diagnostic psychiatric interview for DSM-IV and ICD-10. *Journal of Clinical Psychiatry, 59*(Suppl. 20), 22–33.

Sijtsma, K. (2009). On the use, the misuse, and the very limited usefulness of Cronbach's alpha. *Psychometrika, 74*(1), 107–120.

Spanier, G. B. (1976). Measuring dyadic adjustment: New scales for assessing the quality of marriage and similar dyads. *Journal of Marriage and the Family, 38*(1), 15–28.

Sparrow, S. S., Cicchetti, D. V., & Saulnier, C. A. (2016). *Vineland Adaptive Behavior Scales* (3rd ed.). Pearson.

Spitzer, R. L., Kroenke, K., Williams, J. B. W., & Löwe, B. (2006). A brief measure for assessing generalized anxiety disorder: The GAD-7. *Archives of Internal Medicine, 166*(10), 1092–1097.

Stanley, B., & Brown, G. K. (2012). Safety planning intervention: A brief intervention to mitigate suicide risk. *Cognitive and Behavioral Practice, 19*(2), 256–264.

Stark, E. (2007). *Coercive control: How men entrap women in personal life*. Oxford University Press.

Sternberg, R. J., & Grigorenko, E. L. (2002). *Dynamic testing: The nature and measurement of learning potential*. Cambridge University Press.

Sweet, J. J., Heilbronner, R. L., Morgan, J. E., Larrabee, G. J., Rohling, M. L., Boone, K. B., Kirkwood, M. W., Schroeder, R. W., & Suhr, J. A. (2021). American Academy of Clinical Neuropsychology (AACN) 2021 consensus statement on validity assessment. *Archives of Clinical Neuropsychology, 36*(5), 623–647.

World Health Organization. (2001). *International classification of functioning, disability and health*. World Health Organization.

World Health Organization. (2021). *Live life: An implementation guide for suicide prevention in countries*. World Health Organization.

World Health Organization. (2024). *Clinical descriptions and diagnostic requirements for ICD-11 mental, behavioural and neurodevelopmental disorders*. World Health Organization.

Glossary

Definitions are given for the sense in which each term is used in this book. Where a term has a different technical meaning in another tradition, the difference is noted.

Accommodation. A change to the conditions of assessment or of an activity that removes a barrier unrelated to the construct being measured, without altering the construct itself. Distinguished from a modification, which changes what is measured.

Acculturation. The process of change in values, practices and identifications that follows sustained contact between cultural groups; treated here as domain-specific rather than as a single dimension.

Adaptive behaviour. The conceptual, social and practical skills required for everyday functioning. A defining component of the diagnosis of intellectual disability.

Adjustment disorder. A maladaptive response to an identifiable stressor, with symptoms that do not meet criteria for another disorder, beginning within three months of the stressor.

Anchoring. A judgement bias in which an early piece of information, such as a previous diagnosis in the records, exerts disproportionate influence on subsequent reasoning.

Anhedonia. Loss of interest or pleasure in activities that were previously rewarding; a core feature of depressive episodes.

Aptitude. The capacity to acquire a skill or knowledge under specified conditions of training; interpreted as a forecast rather than a description of current ability.

Assessment. The broad process of answering a question about a person through the integration of interview, observation, informant report, records, testing and functional information. Not synonymous with testing.

Base rate. The prevalence of a condition in the setting in which the assessment takes place. Governs the interpretation of predictive values and the appropriate placement of decision thresholds.

Behavioural addiction. A pattern of repetitive behaviour, such as gambling or gaming, that shares phenomenological and neurobiological features with substance de-

pendence. The concept is well established for some behaviours and contested for others.

Broad-band inventory. A personality or symptom measure that assesses multiple domains in a single administration.

Capacity. The ability to make a specific decision at a specific time, assessed by a functional test defined in the relevant jurisdiction. Distinct from insight.

Case formulation. An explanatory account of why this person, at this time, in this context, has developed and maintained these difficulties; testable and predictive.

Coercive control. An ongoing pattern of domination in an intimate relationship, encompassing physical, sexual, psychological, economic and immigration-related control, and harmful even in the absence of physical violence.

Collateral information. Evidence supplied by someone other than the client, or documented before the current assessment.

Comorbidity. The co-occurrence of two or more disorders in one person. The rule rather than the exception in clinical populations.

Competing hypotheses. The practice of holding several explanations in view simultaneously and seeking the evidence that discriminates among them.

Compulsion. A repetitive behaviour or mental act performed in response to an obsession, or according to rigid rules, in order to reduce distress or prevent a feared outcome.

Construct validity. The degree to which evidence and theory support the interpretation of scores as measures of a specified construct; in contemporary usage, the whole of the validity argument rather than one of its types.

Cultural formulation. A structured account of the client's explanatory model, cultural identity, stressors and supports, and the relationship between cultural factors and the presenting difficulty.

Cut score. The value on a score scale at which a decision changes; the operational expression of a decision rule.

Differential diagnosis. The disciplined comparison of competing explanations, conducted by identifying the evidence that would separate them.

Differential item functioning. A form of measurement bias in which respondents of equal standing on the construct but from different groups have different probabilities of endorsing a particular item.

Ecological validity. The degree to which performance on a test predicts functioning in the person's everyday environment.

Evidence-based assessment. The selection, interpretation and use of assessment methods justified by research evidence, clinical expertise and the client's characteristics, culture and preferences.

Executive function. The supervisory processes that organise goal-directed behaviour, including inhibition, shifting, updating and planning. Poorly captured by laboratory tasks in isolation.

Formulation. See case formulation.

Functional analysis. The identification of the antecedents, behaviour and consequences that maintain a presenting pattern, used particularly in the analysis of avoidance.

Functional capacity. What a person can do in specified activities of daily living, distinguished from what they actually do and from the support that makes performance possible.

g factor. The general factor that accounts for a substantial proportion of variance across diverse cognitive tasks.

Hypomania. A distinct period of abnormally elevated, expansive or irritable mood with increased energy, lasting at least four days, without the marked impairment or psychosis that characterises mania.

Idiom of distress. A culturally patterned way of expressing and communicating distress, such as somatic complaint or spiritual attribution.

Impairment. The effect of a condition on the person's capacity to function in specified domains; distinguished from symptom severity.

Incremental validity. The degree to which a measure improves prediction or decision accuracy beyond information already available.

Insight. Awareness and understanding of one's condition, best assessed dimensionally (awareness of symptoms, attribution, need for treatment, awareness of consequences). Distinct from capacity.

Interrater reliability. The consistency of scores or judgements across independent raters.

Intersectionality. The interaction of multiple social positions in shaping experience and disadvantage; treated in assessment as a reason to examine specific configurations rather than to assume that one characteristic explains a presentation.

Level of personality functioning. The severity of impairment in self (identity, self-direction) and interpersonal (empathy, intimacy) functioning, used to grade personality disorder.

Likelihood ratio. The ratio of the probability of a test result in people with a condition to its probability in people without it; used to revise a pre-test probability.

Measurement invariance. The degree to which an instrument measures the same construct in the same metric across groups; a precondition for comparing group means.

Mental status examination. The structured description of a client's current psychological functioning, covering appearance, speech, mood and affect, thought form and content, perception, cognition, insight and judgement.

Multi-informant assessment. The collection of information from several people who observe the client in different settings; discrepancy among informants is treated as informative rather than as error.

Negative symptoms. Reductions in normal functions — blunted affect, alogia, avolition, anhedonia and asociality — that predict functional outcome in psychotic disorders.

Norms. A description of the distribution of scores in a defined reference sample; a comparison, not a standard of health.

Obsession. A recurrent and persistent intrusive thought, image or urge that is experienced as unwanted and that the person attempts to ignore, suppress or neutralise.

Performance validity. The extent to which performance on cognitive testing reflects the person's true ability, assessed through dedicated and embedded measures.

Premorbid functioning. The level of cognitive or functional ability that a person is estimated to have had before the onset of a condition; estimated demographically, by reading-based measures or by best previous performance.

Percentile rank. The proportion of a reference sample scoring at or below an obtained score.

Positive predictive value. The proportion of positive test results that are true positives in a given setting; dependent on prevalence.

Private events. Internal experiences such as thoughts, images and sensations, which are accessible only through the client's report.

Protective factor. A characteristic or circumstance that reduces the likelihood of a harmful outcome, independently of risk factors.

Provisional diagnosis. A diagnosis offered on the available evidence with an explicit statement of its uncertainty and the observations that would confirm or refute it.

Psychometrics. The discipline concerned with the theory and technique of psychological measurement, including reliability, validity, norms and measurement error.

Reification. The treatment of a score, label or construct as a concrete entity; a recurring error in personality and cognitive reporting.

Reliability. The consistency of scores across replications of a measurement procedure; meaningful only in relation to the source of error addressed.

Responsivity. The extent to which a measure detects change when change occurs.

Safeguarding. The process of protecting children and adults at risk from abuse, neglect and exploitation, governed by law and local procedure.

Safety planning. A collaborative, written plan specifying the person's warning signs, coping strategies, sources of support and steps to reduce access to means.

Scalar invariance. The level of measurement invariance at which item intercepts as well as factor loadings are equal across groups; required before comparing group means.

Sensitivity. The proportion of people with a condition who are correctly identified by a test.

Specificity. The proportion of people without a condition who are correctly identified as negative by a test.

Standard error of measurement. The standard deviation of the hypothetical distribution of obtained scores around a person's true score; used to construct confidence intervals around individual scores.

Standard error of the difference. The standard error applicable to the difference between two scores, always larger than the standard error of either score alone.

Standardised administration. Fidelity to the manual's instructions on wording, order, timing, materials, prompting, recording and discontinuation, which is the condition under which norms apply.

Static and dynamic risk factors. Historical and unchangeable factors that establish baseline risk, as against current and modifiable factors that determine present risk.

Structured professional judgement. An approach to risk assessment that combines empirically supported risk factors, clinical judgement and a management plan, rather than producing a predictive score.

Structured interview. A diagnostic interview with fixed questions and coding rules, designed to improve the reliability of diagnosis.

Systemic formulation. An account of a difficulty in terms of patterns of interaction among family members or other participants, rather than in terms of individual deficits.

Test–retest reliability. The consistency of scores across two administrations separated by an interval.

Thought form. The structure, flow and coherence of thinking as observed in speech; distinguished from thought content.

Validity. See construct validity.

Working memory. The capacity to hold and manipulate information over short periods; a distinct cognitive domain and a frequent locus of impairment.

APPENDIX A

Assessment Planning and Quality Checklist

The checklist is intended for use before, during and after an assessment. It is not a substitute for clinical judgement; it is a device for making the reasoning explicit and for catching the omissions that recur in practice.

A.1 Before the assessment

- Restate the referral question in terms of the decision it informs.
- Identify the decision-maker, the timescale and the standard of evidence required.
- Identify immediate safety, medical or safeguarding needs and plan for them.
- Establish what information already exists: records, previous assessments, school or employer reports.
- List the competing hypotheses and the evidence that would discriminate among them.
- Select methods that address the hypotheses directly, and record the rationale for each.
- Check the qualifications required for each instrument and confirm that they are held.
- Confirm the availability of norms appropriate to the client's age, language, culture and ability.
- Plan for language, literacy, sensory, motor and cognitive access, and record any accommodation.

- Set the time budget for the session or sessions and identify what will be deferred if time runs short.
- Prepare the environment: room, seating, materials, freedom from interruption.
- Confirm consent procedures, confidentiality limits and arrangements for feedback.

A.2 During the assessment

- Explain the purpose, process, duration and limits of confidentiality before beginning.
- Observe and record behaviour, not only responses.
- Record any departure from standard administration at the time, with its reason.
- Record verbatim responses where the instrument requires it.
- Monitor effort, fatigue, distress and engagement, and record them.
- Follow up discrepancies between sources as they arise.
- Ask directly about risk and record what was asked and what was disclosed.
- Note any new hypothesis that emerges and record it.

A.3 Scoring and analysis

- Score from the record rather than from memory.
- Apply the manual's rules exactly, including reversal, basal and ceiling rules.
- Enter demographic data accurately and verify that the correct norms were applied.
- Recompute totals independently.
- Compute confidence intervals for the scores that will be interpreted.

- Compute the standard error of the difference before interpreting any difference.
- Check the base rate of any pattern that will be interpreted.
- Evaluate performance validity and response style before interpreting clinical scales.

A.4 Before finalising the report

- Confirm that the report answers the referral question explicitly and early.
- Confirm that each conclusion is traceable to stated evidence.
- Confirm that the evidence has been weighed rather than averaged.
- Confirm that alternative explanations have been considered and recorded.
- Confirm that uncertainty is stated specifically, with what would resolve it.
- Confirm that limitations are stated: language, norms, missing information, validity concerns.
- Confirm that recommendations name an action, an agent, a setting and a review point.
- Confirm that the language is free of pejorative terms and is intelligible to its readers.
- Confirm that consent, confidentiality and disclosure decisions are recorded.
- Arrange peer consultation for any high-stakes or ambiguous conclusion.

A.5 After the assessment

- Provide feedback, invite correction and record the client's response.
- Revise the formulation where the client's response requires it.
- Record the review point and the arrangements for follow-up.

- Follow up a sample of recommendations to establish whether they were implemented and why.
- Record any assessment in which the outcome differed from the prediction, for later calibration.

APPENDIX B

Structure for an Integrated Psychological Report

The structure below is adaptable to setting and purpose. Its logic is that the report should state the question, present the evidence, show the reasoning and answer the question, in that order.

B.1 Identifying information

Client name, date of birth, reference number, date or dates of assessment, assessor and supervising clinician, source of referral, and the intended recipients of the report.

B.2 Reason for referral

The question as the referrer stated it, followed by the question or questions the assessment addressed. Where the two differ, explain why.

B.3 Sources of information

Interview with the client; interviews with informants, named by relationship; records reviewed, with dates; instruments administered, with forms and norm groups; observation, including setting and duration. State what was unavailable.

B.4 Relevant background

Presenting problem and its development; developmental, family, educational, occupational and medical history; substance use; previous assessments and interventions; current circumstances. Distinguish reported from documented information.

B.5 Behavioural observations and mental status

Appearance and behaviour, speech, mood and affect, thought form and content, perception, cognition, insight and judgement. Record observed behaviour separately from reported experience. Note cooperation, effort, fatigue and any factors affecting validity.

B.6 Assessment methods

For each instrument: what it measures, the form used, the norm group, the reliability and validity relevant to this use, and any departure from standard administration. State the rationale for the selection.

B.7 Results by clinically meaningful domain

Present results by domain — for example, mood, anxiety, cognition, personality, functioning — rather than by instrument. For each score report the obtained value, its confidence interval, its percentile or band, and a plain-language description. Integrate each result with the corresponding interview and informant evidence.

B.8 Integrated interpretation and differential considerations

The hypotheses considered, the evidence for and against each, the reasoning that led to the preferred explanation, and the alternatives that remain open. Where sources conflict, state the conflict and its resolution or its persistence.

B.9 Diagnostic conclusions

Diagnoses where the evidence supports them, stated with the classification system used and with provisional status where appropriate. Where a diagnosis is not made, state why.

B.10 Formulation

Predisposing, precipitating, maintaining and protective factors; the explanatory account; the implications for intervention; and the predictions the formulation makes.

B.11 Strengths and protective factors

The client's capacities, resources, relationships, values and achievements, and the factors that support recovery. This section is substantive, not ceremonial.

B.12 Recommendations

Specific, feasible, sequenced and linked to identified needs, each naming an action, an agent, a setting and a review point. Distinguish what is required from what is desirable.

B.13 Limitations and conditions affecting interpretation

What was assessed and what was not; the limits of norms, language, validity and time; and the conditions under which the conclusions would need revision.

B.14 Summary for the reader

A short summary, written for the referrer, stating the question, the answer and the recommended next steps. Where the report will be read by the client, include a version written for them.

APPENDIX C

Case Formulation Template

The template supports the formulation described in Chapters 1 and 16. It is intended to be completed in note form and then written as prose.

C.1 The presenting pattern

Describe the difficulty in behavioural terms, with onset, course, frequency and severity. State the functional impact in the domains that matter for the decision.

C.2 Predisposing factors

- Constitutional and developmental factors, including neurodevelopmental history, temperament and medical history.
- Family and relational history, including attachment experiences and significant losses.
- Cultural and social context, including migration, discrimination, material circumstances and community.
- Earlier episodes of difficulty and their resolution.

C.3 Precipitating factors

The events or changes temporally associated with onset. Distinguish events from the person's appraisal of them, since the appraisal is often the more proximate cause.

C.4 Maintaining factors

Identify the processes that keep the difficulty going:

- cognitive: appraisals, beliefs, attentional biases, rumination and worry;
- behavioural: avoidance, safety behaviours, reassurance-seeking, withdrawal;
- emotional: affect regulation strategies and their consequences;
- physiological: sleep, substances, pain, medication;
- relational: patterns of interaction that elicit and confirm expectations;
- systemic: family, organisational or service factors;
- social: housing, employment, finances, caring responsibilities.

C.5 Protective factors

Reasons for living, relationships, capacities, values, engagement, future orientation and community resources. State how each will be mobilised.

C.6 The formulation as narrative

Write the account in prose: why this person, at this time, in this context, developed this pattern; how the pattern is maintained; and what it costs and achieves. Use language the client could read.

C.7 Predictions and tests

State what the formulation predicts: which intervention should produce which change, and what observation would indicate that the formulation is wrong.

C.8 Intervention implications

Targets, sequence, methods and the arrangements for monitoring. Identify the point of maximum leverage and the barriers to reaching it.

About the Author

Advanced Assessment and Diagnosis is a course textbook prepared by Triune Biblical University Global Extension, USA, an online university based in Shirley, New York, and issued for academic use in its doctoral programme in counselling psychology. It supports CPY 903 and is written for students who are preparing for advanced practice in psychological assessment, diagnosis and case formulation. The book is not for sale.

Index

Accommodation, 78, 79, 86, 129, 139, 257, 264
Acculturation, 265
Adaptive behaviour, 129, 137, 145
Adjustment disorder, 156, 161
Adult Attachment Interview, 98
Anchoring, 20
Anhedonia, 56
Aptitude, 129, 133, 134, 140, 145
AUDIT, 206, 218
Autism Diagnostic Observation Schedule, 231
Base rate, 3, 14, 15, 122
Behavioural addiction, 203, 204, 210, 211, 217
Broad-band inventory, 91
Capacity, 6, 18, 41, 76, 101, 112, 115, 129, 130, 137, 138, 145, 167, 176
Case formulation, 3
Cattell–Horn–Cattell model, 111
Coercive control, 241, 249, 254, 275, 280
Collateral information, 37
Comorbidity, 155, 161, 162, 188
Competing hypotheses, 3
Compulsion, 154
Construct validity, 24
Cultural formulation, 269
Cut score, 63, 262
Differential diagnosis, 38, 291, 294
Differential item functioning, 64
Dyadic Adjustment Scale, 252
Ecological validity, 123
Evidence-based assessment, 3
Executive function, 111, 118, 119, 126
Functional analysis, 149, 159
Functional capacity, 129, 138

g factor, 111
HCR-20, 280
Hypomania, 169
Idiom of distress, 270
Impairment, 15, 16, 107, 121, 186–190, 199, 264, 304
Incremental validity, 58
Insight, 34, 154, 167, 176, 177, 182
International Test Commission, 272
Intersectionality, 268
Level of personality functioning, 91
Likelihood ratio, 62
Measurement invariance, 64
Mental status examination, 25, 26, 33
Minnesota Multiphasic Personality Inventory, 95
Montreal Cognitive Assessment, 121
Multi-informant assessment, 223
Negative symptoms, 167, 172
NEO Personality Inventory, 96
Norms, 49, 50, 104, 251, 263, 271
Obsession, 154
Percentile rank, 60
Performance validity, 66, 81, 111, 121
Personality Assessment Inventory, 95
Positive predictive value, 62
Premorbid functioning, 113
Protective factor, 275, 277, 283, 284
Provisional diagnosis, 22
Psychometrics, 50, 67
Reification, 91
Reliability, 49, 50, 52–54, 56, 59, 67, 68
Safeguarding, 213, 223, 233, 275, 281, 288
Safety planning, 285
Scalar invariance, 64
Sensitivity, 49, 61, 62, 121
Specificity, 49, 61, 62
Standard error of measurement, 49, 68
Standard error of the difference, 54
Standardised administration, 72
Static and dynamic risk factors, 275
Structured Clinical Interview for DSM-5, 46
Structured interview, 22, 25, 41

Structured professional judgement, 280, 284
Systemic formulation, 252
Test–retest reliability, 53
Thought form, 171
Working memory, 86, 118
Yale–Brown Obsessive Compulsive Scale, 158